

# STANDARD TENDER DOCUMENT

# **FOR**

# SUPPLY, DELIVERY, INSTALLATION AND COMMISSIONING OF LOCAL AREA NETWORKS (LANs) FOR KRA IDENTIFIED STATIONS

TENDER NO. KRA/HQS/NCB-092/2022-2023

TIMES TOWER BUILDING P.O. BOX 48240-00100 TEL: +254 709012365

EMAIL: eprocurement@kra.go.ke

## Pre – Bid Link

REGISTER FOR ON-LINE PRE-BID MEETING HERE

PRE-BID CONFERENCE

30<sup>th</sup> MAY, 2023 at 11:00 AM NAIROBI, KENYA.

CLOSING DATE: 7<sup>th</sup> JUNE, 2023 AT 11:00 AM

**BID VALIDITY 335 DAYS** 

### TABLE OF CONTENTS

PREI	FACE	· iii
	ENDIX TO THE PREFACE	
GUID	DELINES FOR PREPARATION OF TENDER DOCUMENTS	. iv
1.	GENERAL	
2.	PART 1 - TENDERING PROCEDURES	. iv
3.	PART 2 – PROCUREMENT ENTITY'S REQUIREMENTS	
4.	PART 3 – CONDITIONS OF CONTRACT AND CONTRACT FORMS	V
INVI	TATION TO TENDER	vii
Section	on I - Instructions to Tenderers	1
<b>A</b> 1	General Provisions	1
2	Fraud and Corruption	1
3	Eligible Tenderers	
4	Eligible Goods and Related Services	
·		
B.	Contents of Request for Tenders Document	3
5.	Sections of Tendering Document	3
6	Clarification of Tender Document	
7	Amendment of Tender Document	4
C.	Preparation of Tenders	5
8	Cost of Tendering	
9	Language of Tender	
10	Documents Comprising the Tender	
11	Form of Tender and Price Schedules	
12	Alternative Tenders	
13	Tender Prices and Discounts	
14	Currencies of Tender and Payment	
15	Documents Establishing the Eligibility and Conformity of the Goods and Related Services	
16 17	Documents Establishing the Eligibility and Qualifications of the Tenderer	
18	Tender Security	o
19	Format and Signing of Tender.	
<b>D.</b>	Submission and Opening of Tenders	
20	Sealing and Marking of Tenders	
21 22	Deadline for Submission of Tenders	
23	Withdrawal, Substitution, and Modification of Tenders.	
24	Tender Opening	
TC.	Frankration and Communication of Trankration	11
<b>E</b> .	Evaluation and Comparison of Tenders	
25 26	Confidentiality	
20 27	Deviations, Reservations, and Omissions	
28	Determination of Responsiveness	
29	Non-conformities, Errors and Omissions	
30	Correction of Arithmetical Errors	
31	Conversion to Single Currency	
32	Margin of Preference and Reservations	
33	Evaluation of Tenders	
34	Comparison of Tenders	
35	Abnormally Low Tenders	
36.	Abnormally High Tenders	

	Post Qualification of the Tenderer	
38.	Lowest Evaluated Tender	
39.	Procuring Entity's Right to Accept Any Tender, and to Reject Any or All	15
F.	Award of Contract	15
40.	Award Criteria	
41.	Notice of Intention to enter into a Contract	
42.	Standstill Period	
43.	Debriefing by the Procuring Entity	
44.	Letter of Award	
45.	Signing of Contract	
46. 47.	Performance Security	
47. 48.	Publication of Procurement Contract	
40.	Procurement Related Complaint	1 /
SECT	TION II – TENDER DATA SHEET (TDS)	18
SECT	FION III - EVALUATION AND QUALIFICATION CRITERIA	22
	neral Provisions	
	aluation of Tenders (ITT 33)	
	ARGIN OF PREFERENCE	
4. Pos	st Qualification of Tenderers (ITT 37)	25
SECT	ΓΙΟΝ IV - TENDERING FORMS	28
Form		
	er	.29
	ficate of Independent Tender Determination	
	declaration	
	s	
	ption	
	erer Information Form	
Tende	erer's Eligibility- Confidential Business Questionnaire Form	
	erer's Eligibility- Confidential Business Questionnaire Form39	
Tende	erer's JV Members Information Form	
Tendo Price	erer's JV Members Information Form	43
Tende Price FORM		43 49
Tende Price FORM		43 49 50
Tendo Price FORM FORM		43 49 50 51
Tendo Price FORM FORM		43 49 50 51
Tendo Price FORM FORM FORM		43 49 50 51 52
Tendo Price FORM FORM MAN		43 49 50 51 52
Tendo Price FORM FORM MAN PAR		43 49 50 51 52 53
Tendo Price FORM FORM MAN PAR' Section Notes 1.		43 49 50 51 52 53 53 54
Tendo Price FORM FORM MAN PART Section Notes 1. 2.	and the state of the schedule of Requirements.  In Schedule of Requirements.  In Schedule Forms  In Schedule Forms  In OF TENDER SECURITY - DEMAND BANK GUARANTEE  In OF TENDER SECURITY (INSURANCE GUARANTEE)  In OF TENDER-SECURING DECLARATION  IN OF TENDER'S AUTHORIZATION FORM  IN OF TENDER'S AUT	43 49 50 51 52 53 53 54 55
Tendo Price FORM FORM MAN PAR' Section Notes 1. 2. 3.		43 49 50 51 52 53 53 54 55 56
Tendo Price FORM FORM MAN PAR' Section Notes 1. 2. 3. 4.		43 49 50 51 52 53 53 54 55 56 58
Tendo Price FORM FORM MAN PAR' Section Notes 1. 2. 3.		43 49 50 51 52 53 53 54 55 56 58
Tendo Price FORM FORM FORM MAN PAR' Sectio Notes 1. 2. 3. 4. 5.		43 49 50 51 52 53 53 54 55 56 56 59
Tendo Price FORM FORM MAN PAR' Section Notes 1. 2. 3. 4. 5. PAR' SECTION		43 49 50 51 52 53 53 54 55 56 58 59
Tendo Price FORM FORM FORM MAN PAR' Section Notes 1. 2. 3. 4. 5. PAR' SECTI		43 49 50 51 52 53 53 55 56 58 59 60 61 74
Tendo Price FORM FORM FORM MAN PAR' Section Notes 1. 2. 3. 4. 5. PAR' SECTI SECTI		43 49 50 51 52 53 53 54 55 56 58 59 60 61 74
Tendo Price FORM FORM FORM MAN PAR' Section Notes 1. 2. 3. 4. 5. PAR' SECTI SECTI FORM	A Schedule Forms	43 49 50 51 52 53 53 55 56 58 59 60 61 74 78
Tendo Price FORM FORM FORM MAN PAR' Section Notes 1. 2. 3. 4. 5. PAR' SECTI SECTI FORM		43 49 50 51 52 53 53 55 56 58 59 60 61 74 78
Tendo Price FORM FORM FORM MAN PAR' Section Notes 1. 2. 3. 4. 5. PAR' SECTI SECTI FORM FORM	A Schedule Forms	43 49 50 51 52 53 53 55 56 58 59 60 61 74 78 79 82
Tendo Price FORM FORM MAN PAR' Section Notes 1. 2. 3. 4. 5. PAR' SECTI SECTI SECTI FORM FORM	A CONTRACT  TON VII - GENERAL CONDITIONS OF CONTRACT  TON VII - SPECIAL CONDITIONS OF CONTRACT  TON VIII - CONTRACT FORMS  M No. 2: REQUEST FOR REVIEW  M OF IENDERS Information Form.  39  EVALUATION FORM.  BANK GUARANTEE  MOF TENDER SECURITY - DEMAND BANK GUARANTEE  MOF TENDER SECURITY (INSURANCE GUARANTEE)  MOF TENDER SECURITY (INSURANCE GUARANTEE)  MOF TENDER SECURITY (INSURANTEE)  MOF TENDER SECURITY FORMS  MOF TENDER SECURITY - DEMAND BANK GUARANTEE  MOR TENDER S	43 49 50 51 52 53 53 54 55 56 58 59 61 74 79 82 82

FORM No. 6 - PERFORMANCE SECURITY [Option 2– Performance Bond]	86
FORM No. 7 - ADVANCE PAYMENT SECURITY [Demand Bank Guarantee]	88
FORM No. 8 - BENEFICIAL OWNERSHIP DISCLOSURE FORM	88



# INVITATION TO TENDER Tender Notice

1. The Kenya Revenue Authority invites sealed bids from eligible candidates for the following tenders:

NO.	DESCRIPTION	ELIGIBILITY	PREBID	CLOSING DATE AND TIME
1	KRA/HQS/NCB-092/2022-2023:	OPEN	30th MAY	7 <sup>TH</sup> JUNE,
	SUPPLY, DELIVERY,		2023	2023 AT
	INSTALLATION AND		AT 11:00AM	11.00AM
	COMMISSIONING OF LOCAL			
	AREA NETWORKS (LANs) FOR			TIMES
	KRA IDENTIFIED STATIONS		VIRTUAL	TOWER


2. Interested eligible candidates may obtain further information and inspect the tender documents with detailed requirements at the office of the:

Deputy Commissioner - Supply Chain Management Times Tower Building, 21<sup>st</sup> Floor, P.O Box 48240- 00100 GPO, Tel. +254 020 310900 Nairobi, Kenya. website: www.kra.go.ke Email :eprocurement@kra.go.ke

- 3. A complete set of bidding documents in English may be obtained from KRA E-Procurement portal available on the KRA website www.kra.go.ke free of charge. Prospective bidders should register for E-Procurement to enable them access the KRA portal under "New Supplier Registration" found under the Tender Tab.
- 4. Qualified and interested tenderers may obtain further information and inspect the Tender Documents during office hours 8:00am-5:00pm. Completed Bids are to be saved as PDF documents marked "KRA/HQS/NCB-092/2022-2023: SUPPLY,DELIVERY, INSTALLATION AND COMMISSIONING OF LOCAL AREA NETWORKS (LANs) FOR KRA IDENTIFIED STATIONS" and submitted to the appropriate KRA E-procurement Web Portal found on the KRA website so as to be received on or before 7th June, 2023 at 11.00 a.m.
- 5. Tendering will be conducted under National Open Competitive method using a standardized tender document. Tendering is open to all qualified and interested Tenderers
- 6. Qualified and interested tenderers may obtain further information and inspect the Tender Documents during office hours *i.e.* 0800 to 1700 hours.
- 7. Tender documents may be viewed and downloaded for free from the website www.kra.go.ke free of charge. Tenderers who download the tender document must forward their particulars immediately to eprocurement@kra.go.ke, telephone +254 02 2817022 and P.O. BOX 48240 00100 to facilitate any further clarification or addendum.
- 8. The tenderer shall chronologically serialize all pages of the tender documents submitted.
- 9. Submission should strictly be done via **the KRA E-Procurement Portal**.
- 10. The deadline for addressing e-system Bid Submission issues/challenges is 24 hours before the tender closing date and time.

- 11. Bids will be opened electronically promptly after closing time and Bidders or their representatives are welcome to witness the opening at Times Tower Building.
- 12. Tenders shall be quoted in Kenya Shillings and shall include all taxes.
- 13. Tenders shall remain valid **for 335 days** from the date of opening of tenders.
- 14. An original hard copy of the Bid Security of not less than the indicated amount or equivalent amount in a freely convertible currency must be dropped in the Tender Security Box located at Times Tower Building, Ground Floor any day before the tender closing date. The Bid Security must be in a sealed envelope bearing the Tender Description and addressed to the address indicated above.
- 15. Tenders will be opened immediately after the **closing date and time** specified above or any other deadline date and time that may be specified later. Tenders will be publicly opened in the presence of the Tenderers' designated representatives who choose to attend Tender Opening at the address indicated above.
- 16. Late tenders will be rejected

Any canvassing or giving of false information will lead to automatic disqualification.



#### SECTION I: INSTRUCTIONS TO TENDERERS

#### **A** General Provisions

#### 1. Scope of Tender

- 1.1 The Procuring Entity as defined in the **TDS** invites tenders for supply of goods and, if applicable, any Related Services incidental thereto, as specified in Section V, Supply Requirements. The name, identification, and number of lots (contracts) of this Tender Document are specified in the **TDS**.
- 12 Throughout this tendering document:
  - a) the term "in writing" means communicated in written form (e.g. by mail, e-mail, fax, including if specified in the **TDS**, distributed or received through the electronic-procurement system used by the Procuring Entity) with proof of receipt;
  - b) if the context so requires, "singular" means "plural" and vice versa;
  - c) "Day" means calendar day, unless otherwise specified as "Business Day". A Business Day is any day that is an official working day of the Procuring Entity. It excludes official public holidays.

#### 2 Fraud and Corruption

- 21 The Procuring Entity requires compliance with the provisions of the Public Procurement and Asset Disposal Act, 2015, Section 62 "Declaration not to engage in corruption". The tender submitted by a person shall include a declaration that the person shall not engage in any corrupt or fraudulent practice and a declaration that the person or his or her sub-contractors are not debarred from participating in public procurement proceedings.
- The Procuring Entity requires compliance with the provisions of the Competition Act 2010, regarding collusive practices in contracting. Any tenderer found to have engaged in collusive conduct shall be disqualified and criminal and/or civil sanctions may be imposed. To this effect, Tenders shall be required to complete and sign the "Certificate of Independent Tender Determination" annexed to the Form of Tender.
- Unfair Competitive Advantage Fairness and transparency in the tender process require that the firms or their Affiliates competing for a specific assignment do not derive a competitive advantage from having provided consulting services related to this tender. To that end, the Procuring Entity shall indicate in the **Data Sheet** and make available to all the firms together with this tender document all information that would in that respect give such firm any unfair competitive advantage over competing firms.

#### 3. Eligible Tenderers

A Tenderer may be a firm that is a private entity, an individual, a state-owned enterprise or institution subject to ITT3.7, or any combination of such entities in the form of a joint venture (JV) under an existing agreement or with the intent to enter into such an agreement supported by a letter of intent. Public employees and their close relatives (spouses, children, brothers, sisters and uncles and aunts) are not eligible to participate in the tender.

In the case of a joint venture, all members shall be jointly and severally liable for the execution of the entire Contract in accordance with the Contract terms. The JV shall nominate a Representative who shall have the authority to conduct all business for and on behalf of any and all the members of the JV during the Tendering process and, in the event the JV is awarded the Contract, during contract execution. The maximum number of JV members shall be specified in the **TDS**.

- Public Officers of the Procuring Entity, their Spouses, Child, Parent, Brothers or Sister. Child, Parent, Brother or Sister of a Spouse their business associates or agents and firms/organizations in which they have a substantial or controlling interest shall not be eligible to tender or be awarded a contract. Public Officers are also not allowed to participate in any procurement proceedings.
- A Tenderer shall not have a conflict of interest. Any Tenderer found to have a conflict of interest shall be disqualified. A Tenderer may be considered to have a conflict of interest for the purpose of this

Tendering process, if the Tenderer:

- a) directly or indirectly controls, is controlled by or is under common control with another Tenderer; or
- b) receives or has received any direct or indirect subsidy from another Tenderer; or
- c) has the same representative or ownership as another Tenderer; or
- d) has a relationship with another Tenderer, directly or through common third parties, that puts it in a position to influence the Tender of another Tenderer, or influence the decisions of the Procuring Entity regarding this Tendering process; or
- e) or any of its affiliates participated as a consultant in the preparation of the design or technical specifications of the goods that are the subject of the Tender; or
- f) or any of its affiliates has been hired (or is proposed to be hired) by the Procuring Entity or Procuring Entity for the Contract implementation; or
- g) would be providing goods, works, or non-consulting services resulting from or directly related to consulting services for the preparation or implementation of the project specified in the **TDS** ITT 1.1 that it provided or were provided by any affiliate that directly or indirectly controls, is controlled by, or is under common control with that firm; or has a close business or family relationship with a professional staff of the Procuring Entity (or of the project implementing agency, who: (i) are directly or indirectly involved in the preparation of the tendering document or specifications of the Contract, and/or the Tender evaluation process of such Contract; or (ii) would be involved in the implementation or supervision of such Contract unless the conflict stemming from such relationship has been resolved in a manner acceptable to the Procuring Entity throughout the Tendering process and execution of the Contract.
- A tenderer shall not be involved in corrupt, coercive, obstructive, collusive or fraudulent practice. A tenderer that is proven to have been involved in any of these practices shall be automatically disqualified.
- A firm that is a Tenderer (either individually or as a JV member) shall not submit more than one Tender, except for permitted alternative Tenders. This includes participation as a subcontractor. Such participation shall result in the disqualification of all Tenders in which the firm is involved. A firm that is not a Tenderer or a JV member, may participate as a subcontractor in more than one Tender. Members of a joint venture may not also make an individual tender, be a subcontractor in a separate tender or be part of another joint venture for the purposes of the same Tender.
- A Tenderer may have the nationality of any country, subject to the restrictions pursuant to ITT3.9. A Tenderer shall be deemed to have the nationality of a country if the Tenderer is constituted, incorporated or registered in and operates in conformity with the provisions of the laws of that country, as evidenced by its articles of incorporation (or equivalent documents of constitution or association) and its registration documents, as the case may be. This criterion also shall apply to the determination of the nationality of proposed subcontractors or sub consultants for any part of the Contract including related Services.
- 3.7 A Tenderer that has been debarred by the PPRA from participating in public procurement shall be ineligible to tender or be awarded a contract. The list of debarred firms and individuals is available from the PPRA's website www.ppra.go.ke
- Tenderers that are state-owned enterprises or institutions may be eligible to compete and be awarded a Contract(s) only if they are (i) a legal public entity of the state Government and/or public administration, (ii) financially autonomous and not receiving any significant subsidies or budget support from any public entity or Government, and (iii) operating under commercial law and vested with legal rights and liabilities similar to any commercial enterprise to enable it compete with firms in the private sector on an equal basis. Public employees and their close relatives are not eligible to participate in the tender.
- Tenderers may be ineligible if their countries of origin (a) as a matter of law or official regulations, Kenya prohibits commercial relations with that country, or(b) by an act of compliance with a decision of the United Nations Security Council taken under Chapter VII of the Charter of the United Nations, Kenya prohibits any import of goods or contracting for supply of goods or services from that country, or any payments to any country, person, or entity in that country. A tenderer shall provide such documentary evidence of eligibility satisfactory to the Procuring Entity, as the Procuring Entity shall reasonably request.
- 3.10 Tenderers shall provide the qualification information statement that the tenderer (including all members of a joint venture and subcontractors) is not associated, or have been associated in the past, directly or indirectly, with a firm or any of its affiliates which have been engaged by the Procuring entity

to provide consulting services for the preparation of the design, specifications, and other documents to be used for the procurement of the goods under this Invitation for tenders.

- 311 Where the law requires tenderers to be registered with certain authorities in Kenya, such registration requirements shall be defined in the **TDS**
- 3.12 The Competition Act of Kenya requires that firms wishing to tender as Joint Venture undertakings which may prevent, distort or lessen competition in provision of services are prohibited unless they are exempt in accordance with the provisions of Section 25 of the Competition Act, 2010. JVs will be required to seek for exemption from the Competition Authority. Exemption shall not be a condition for tender, but it shall be a condition of contract award and signature. A JV tenderer shall be given opportunity to seek such exemption as a condition of award and signature of contract. Application for exemption from the Competition Authority of Kenya may be accessed from the website www.cak.go.ke.
- 3.13 A Kenyan tenderer shall provide evidence of having fulfilled his/her tax obligations by producing a current tax clearance certificate or tax exemption certificate issued by the Kenya Revenue Authority.

#### 4. Eligible Goods and Related Services

- 4.1 All the Goods and Related Services to be supplied under the Contract shall have their origin in any country that is eligible in accordance with ITT 3.9.
- For purposes of this ITT, the term "goods" includes commodities, raw material, machinery, equipment, and industrial plants; and "related services" include services such as insurance, installation, training, and initial maintenance.
- The term "origin" means the country where the goods have been mined, grown, cultivated, produced, manufactured or processed; or, through manufacture, processing, or assembly, another commercially recognized article results that differs substantially in its basic characteristics from its components.
- A procuring entity shall ensure that the items listed below shall be sourced from Kenya and there shall be no substitutions from foreign sources. The affected items are:
  - a) motor vehicles, plant and equipment which are assembled in Kenya;
  - b) furniture, textile, foodstuffs, oil and gas, information communication technology, steel, cement, leather, agro-processed products, sanitary products, and other goods made in Kenya; or
  - c) goods manufactured, mined, extracted or grown in Kenya.
- Any goods, works and production processes with characteristics that have been declared by the relevant national environmental protection agency or by other competent authority as harmful to human beings and to the environment shall not be eligible for procurement.

#### 5. Sections of Tendering Document

5.1 The tendering document consist of Parts 1, 2, and 3, which include all the sections indicated below, and should be read in conjunction with any Addenda issued in accordance with ITT8.

#### **PART 1: Tendering Procedures**

- i) Section I Instructions to Tenderers (ITT)
- ii) Section II Tendering Data Sheet (TDS)
- iii) Section III Evaluation and Qualification Criteria
- iv) Section IV Tendering Forms

#### **PART 2: Supply Requirements**

v) Section V - Schedule of Requirements

#### **PART 3: Contract**

- vi) Section VI General Conditions of Contract (GCC)
- vii) Section VII Special Conditions of Contract (SCC)
- viii) Section VIII- Contract Forms

- The notice of Invitation to Tender or the notice to the prequalified Tenderers issued by the Procuring Entity is not part of the tendering document.
- Unless obtained directly from the Procuring Entity, the Procuring Entity is not responsible for the completeness of the document, responses to requests for clarification, the minutes of the pre-tender meeting (if any), or addenda to the tendering document in accordance with ITT7.
- 54 The Tenderer is expected to examine all instructions, forms, terms, and specifications in the tendering document and to furnish with its Tender all information or documentation as is required by the tendering document.

#### 6. Clarification of Tendering Document

- A Tenderer requiring any clarification of the Tender Document shall contact the Procuring Entity in writing at the Procuring Entity's address specified in the **TDS** or raise its enquiries during the pre-Tender meeting if provided for in accordance with ITT 6.4. The Procuring Entity will respond in writing to any request for clarification, provided that such request is received no later than the period specified in the **TDS** prior to the deadline for submission of tenders. The Procuring Entity shall forward copies of its response to all tenderers who have acquired the Tender documents in accordance with ITT 5.3, including a description of the inquiry but without identifying its source. If so specified in the **TDS**, the Procuring Entity shall also promptly publish its response at the web page identified in the **TDS**. Should the clarification result in changes to the essential elements of the Tender Documents, the Procuring Entity shall amend the Tender Documents following the procedure under ITT 7.
- The Procuring Entity shall specify in the **TDS** if a pre-tender conference will be held, when and where. The Tenderer's designated representative is invited to attend a pre-Tender meeting. The purpose of the meeting will be to clarify issues and to answer questions on any matter that may be raised at that stage.
- The Tenderer is requested to submit any questions in writing, to reach the Procuring Entity not later than the period specified in the **TDS** before the meeting.
- Minutes of the pre-Tender meeting, if applicable, including the text of the questions asked by Tenderers and the responses given, together with any responses prepared after the meeting, will be transmitted promptly to all Tenderers who have acquired the Tender Documents in accordance with ITT 6.3. Minutes shall not identify the source of the questions asked.
- The Procuring Entity shall also promptly publish anonymized (*no names*)Minutes of the pre-Tender meeting at the web page identified **in the TDS**. Any modification to the Tender Documents that may become necessary as a result of the pre-Tender meeting shall be made by the Procuring Entity exclusively through the issue of an Addendum pursuant to ITT 7 and not through the minutes of the pre-Tender meeting. Nonattendance at the pre- Tender meeting will not be a cause for disqualification of a Tenderer.

#### 7. Amendment of Tendering Document

- 7.1 At any time prior to the deadline for submission of Tenders, the Procuring Entity may amend the tendering document by issuing addenda.
- Any addendum issued shall be part of the tendering document and shall be communicated in writing to all who have obtained the tender document from the Procuring Entity in accordance with ITT 6.3. The Procuring Entity shall also promptly publish the addendum on the Procuring Entity's web page in accordance with ITT 7.1.
- To give prospective Tenderers reasonable time in which to take an addendum into account in preparing their Tenders, the Procuring Entity may, at its discretion, extend the deadline for the submission of Tenders, pursuant to ITT 21.2.

#### C. Preparation of Tenders

#### **8.** Cost of Tendering

81 The Tenderer shall bear all costs associated with the preparation and submission of its Tender, and the Procuring Entity shall not be responsible or liable for those costs, regardless of the conduct or outcome of the Tendering process.

#### 9. Language of Tender

9.1 The Tender, as well as all correspondence and documents relating to the Tender exchanged by the Tenderer and the Procuring Entity, shall be written in English Language. Supporting documents and printed literature that are part of the Tender may be in another language provided they are accompanied by an accurate translation of the relevant passages into the English Language, in which case, for purposes of interpretation of the Tender, such translation shall govern.

#### 10. Documents Comprising the Tender

- 10.1 The Tender shall comprise the following:
  - a) Form of Tender prepared in accordance with ITT11;
  - b) Price Schedules: completed in accordance with ITT 11 and ITT 13;
  - c) Tender Security or Tender-Securing Declaration, in accordance with ITT 18.1;
  - d) Alternative Tender: if permissible, in accordance with ITT12;
  - e) Authorization: written confirmation authorizing the signatory of the Tender to commit the Tenderer, in accordance with ITT19.3;
  - f) Qualifications: documentary evidence in accordance with ITT 16.2 establishing the Tenderer qualifications to perform the Contract if its Tender is accepted;
  - g) Tenderer Eligibility: documentary evidence in accordance with ITT16.1 establishing the Tenderer eligibility to tender;
  - h) Eligibility of Goods and Related Services: documentary evidence in accordance with ITT 15, establishing the eligibility of the Goods and Related Services to be supplied by the Tenderer;
  - i) Conformity: documentary evidence in accordance with ITT15.2 that the Goods and Related Services conform to the tender document; and
  - j) any other document required in the **TDS**.
- In addition to the requirements under ITT 10.1, Tenders submitted by a JV shall include a copy of the Joint Venture Agreement entered into by all members. Alternatively, a letter of intent to execute a Joint Venture Agreement in the event of a successful Tender shall be signed by all members and submitted with the Tender, together with a copy of the proposed Agreement.
- 103 The Tenderer shall furnish in the Form of Tender information on commissions gratuities, and fees, if any, paid or to be paid to agents or any other party relating to this Tender.

#### 11. Form of Tender and Price Schedules

11.1 The Form of Tender and Price Schedules shall be prepared using the relevant forms furnished in Section IV, Tendering Forms. The forms must be completed without any alterations to the text. All blank spaces shall be filled in with the information requested. The Tenderer shall chronologically serialise pages of all tender documents submitted.

#### 12. Alternative Tenders

12.1 Unless otherwise specified in the TDS, alternative Tenders shall not be considered.

#### 13. Tender Prices and discounts

- 13.1 The prices quoted by the Tenderer in the Form of Tender and in the Price, Schedules shall conform to the requirements specified below.
- 132 All lots (contracts) and items must be listed and priced separately in the Price Schedules.
- 133 The price to be quoted in the Form of Tender in accordance with ITT10.1 shall be the total price

- of the Tender, including any discounts offered.
- 134 The Tenderer shall quote any discounts and indicate the methodology for their application in the form of tender. Conditional discounts will be rejected.
- Prices quoted by the Tenderer shall be fixed during the performance of the Contract and not subject to variation on any account, unless otherwise specified **in the TDS.** A Tender submitted with an adjustable price quotation shall be treated as non-responsive and shall be rejected, pursuant to ITT 28. However, if in accordance with **the TDS**, prices quoted by the Tenderer shall be subject to adjustment during the performance of the Contract, a Tender submitted with a fixed price quotation shall not be rejected, but the price adjustment shall be treated as zero.
- If specified in ITT 1.1, Tenders are being invited for individual lots (contracts) or for any combination of lots (packages). Unless otherwise specified **in the TDS**, prices quoted shall correspond to 100 % of the items specified for each lot and to 100% of the quantities specified for each item of a lot. Tenderers wishing to offer discounts for the award of more than one Contract shall specify in their Tender the price reductions applicable to each package, or alternatively, to individual Contracts within the package. Discounts shall be submitted in accordance with ITT 13.4 provided the Tenders for all lots (contracts) are opened at the same time.
- 13.7 The terms EXW, CIP, CIF, DDP and other similar terms shall be governed by the rules prescribed in the current edition of Incoterms, published by the International Chamber of Commerce.
- Prices shall be quoted as specified in each Price Schedule included in Section IV, Tendering Forms. The disaggregation of price components is required solely for the purpose of facilitating the comparison of Tenders by the Procuring Entity. This shall not in any way limit the Procuring Entity's right to contract on any of the terms offered. In quoting prices, the Tenderer shall be free to use transportation through carriers registered in any eligible country. Similarly, the Tenderer may obtain insurance services from any eligible country in accordance with ITT 3.6, Eligible Tenders. Prices shall be entered in the following manner:
  - a) For Goods manufactured in Kenya:
    - I) the price of the Goods quoted EXW (ex-works, ex-factory, ex warehouse, ex showroom, or off-the- shelf, as applicable) final destination point indicated in the **TDS**, including all customs duties and sales and other taxes already paid or payable on the components and raw material used in the manufacture or assembly of the Goods;
    - ii) any sales tax and other taxes which will be payable in Kenya on the Goods if the Contract is awarded to the Tenderer; and
    - the price for inland transportation, insurance, and other local services required to convey the Goods to their final destination specified in the TDS.
  - b) For Goods manufactured outside Kenya, to be imported:
    - i) the price of the Goods, quoted CIP named place of destination, in Kenya, as specified in the TDS;
    - ii) the price for inland transportation, insurance, and other local services required to convey the Goods from the named place of destination to their final destination specified in the TDS;
  - c) For Goods manufactured outside Kenya, already imported:
    - i) the price of the Goods, including the original import value of the Goods; plus, any markup (or rebate); plus, any other related local cost, and custom duties and other import taxes already paid or to be paid on the Goods already imported;
    - ii) the custom duties and other import taxes already paid (need to be supported with documentary evidence) or to be paid on the Goods already imported;
    - iii) any sales and other taxes levied in Kenya which will be payable on the Goods if the Contract is awarded to the Tenderer; and
    - **iv**) the price for inland transportation, insurance, and other local services required to convey the Goods from the named place of destination to their final destination (Project Site) specified **in the TDS.**

d) for Related Services, other than inland transportation and other services required to convey the Goods to their final destination, whenever such Related Services are specified in the Schedule of Requirements, the price of each item comprising the Related Services (inclusive of any applicable taxes).

#### 14. Currencies of Tender and Payment

- The currency (ies) of the Tender, the currency (ies) of award and the currency (ies) of contract payments shall be the same.
- The Tenderer shall quote in Kenya shillings. If allowed in the **TDS**, the Tenderer may express the Tender price in any currency, provided it shall use no more than two foreign currencies in addition to the Kenya Shilling.
- The rates of exchange to be used by the Tenderer shall be based on the exchange rates provided by the Central Bank of Kenya on the date 30 days prior to the actual date of tender opening.

#### 15. Documents Establishing the Eligibility and Conformity of the Goods and Related Services

- 15.1 To establish the eligibility of the Goods and Related Services in accordance with ITT 15, Tenderers shall complete the country of origin declarations in the Price Schedule Forms, included in Section IV, Tendering Forms.
- To establish the conformity of the Goods and Related Services to the tendering document, the Tenderer shall furnish as part of its Tender the documentary evidence that the Goods conform to the technical specifications and standards specified in Section VII, Schedule of Requirements.
- The documentary evidence may be in the form of literature, drawings or data, and shall consist of a detailed item by item description of the essential technical and performance characteristics of the Goods and Related Services, demonstrating substantial responsiveness of the Goods and Related Services to the technical specification, and if applicable, a statement of deviations and exceptions to the provisions of the Section VII, Schedule of Requirements.
- The Tenderer shall also furnish a list giving full particulars, including available sources and current prices of spare parts, special tools, etc., necessary for the proper and continuing functioning of the Goods during the period **specified in the TDS** following commencement of the use of the goods by the Procuring Entity.
- Standards for workmanship, process, material, and equipment, as well as references to brand names or catalogue numbers specified by the Procuring Entity in the Schedule of Requirements, are intended to be descriptive only and not restrictive. The Tenderer may offer other standards of quality, brand names, and/or catalogue numbers, provided that it demonstrates, to the Procuring Entity's satisfaction, that the substitutions ensure substantial equivalence or are superior to those specified in the Section VII, Schedule of Requirements.

#### 16. Documents Establishing the Eligibility and Qualifications of the Tenderer

- 16.1 To establish Tenderer eligibility in accordance with ITT 4, Tenderers shall complete the Form of Tender, included in Section IV, Tendering Forms.
- The documentary evidence of the Tenderer qualifications to perform the Contract if its Tender is accepted shall establish to the Procuring Entity's satisfaction:
  - a) that, if required **in the TDS**, a Tenderer that does not manufacture or produce the Goods it offers to supply shall submit the Manufacturer's Authorization using the form included in Section IV, Tendering Forms to demonstrate that it has been duly authorized by the manufacturer or producer of the Goods to supply these Goods in Kenya;
  - b) that, if required **in the TDS**, in case of a Tenderer not doing business within the Kenya, the Tenderer is or will be (if awarded the Contract) represented by an Agent in the country equipped and able to carry out the Supplier's maintenance, repair and spare parts-stocking obligations prescribed in the Conditions of Contract and/or Technical Specifications; and
  - c) that the Tenderer meets each of the qualification criterion specified in Section III, Evaluation and Qualification Criteria.

#### 17. Period of Validity of Tenders

- 17.1 Tenders shall remain valid for the Tender Validity period specified **in the TDS**. The Tender Validity period starts from the date fixed for the Tender submission deadline (as prescribed by the Procuring Entity in accordance with ITT 21.1). A Tender valid for a shorter period shall be rejected by the Procuring Entity as non-responsive.
- In exceptional circumstances, prior to the expiration of the Tender validity period, the Procuring Entity may request Tenderers to extend the period of validity of their Tenders. The request and the

responses shall be made in writing. If a Tender Security is requested in accordance with ITT 18, it shall also be extended for a corresponding period. A Tenderer may refuse the request without forfeiting its Tender Security. A Tenderer granting the request shall not be required or permitted to modify its Tender, except as provided in ITT 17.3.

- 173 If the award is delayed by a period exceeding the number of days to be specified in the **TDS** days beyond the expiry of the initial tender validity period, the Contract price shall be determined as follows:
  - a) in the case of **fixed price** contracts, the Contract price shall be the tender price adjusted by the factor specified **in the TDS**;
  - b) in the case of **adjustable price** contracts, no adjustment shall be made; or in any case, tender evaluation shall be based on the tender price without taking into consideration the applicable correction from those indicated above.

#### **18.** Tender Security

- The Tenderer shall furnish as part of its Tender, either a Tender-Securing Declaration or a Tender Security, as specified in the TDS, in original form and, in the case of a Tender Security, in the amount and currency specified in the TDS.
- 182 A Tender Securing Declaration shall use the form included in Section IV, Tendering Forms.
- 183 If a Tender Security is specified pursuant to ITT 18.1, the Tender Security shall be a demand guarantee in any of the following forms at the Tenderer option:
  - i) cash;
  - ii) a bank guarantee;
  - iii) a guarantee by an insurance company registered and licensed by the Insurance Regulatory Authority listed by the Authority; or
  - iv) a letter of credit; or
  - v) guarantee by a deposit taking micro-finance institution, Sacco society, the Youth Enterprise Development Fund or the Women Enterprise Fund.
- If an unconditional guarantee is issued by a non-Bank financial institution located outside Kenya, the issuing non-Bank financial institution shall have a correspondent financial institution located in Kenya to make it enforceable unless the Procuring Entity has agreed in writing, prior to Tender submission, that a correspondent financial institution is not required. In the case of a bank guarantee, the Tender Security shall be submitted either using the Tender Security Form included in Section IV, Tendering Forms, or in another substantially similar format approved by the Procuring Entity prior to Tender submission. The Tender Security shall be valid for thirty
  - (30) days beyond the original validity period of the Tender, or beyond any period of extension if requested under ITT 17.2.
- If a Tender Security is specified pursuant to ITT 18.1, any Tender not accompanied by a substantially responsive Tender Security shall be rejected by the Procuring Entity as non-responsive.
- If a Tender Security is specified pursuant to ITT 18.1, the Tender Security of unsuccessful Tenderers shall be returned as promptly as possible upon the successful Tenderer signing the Contract and furnishing the Performance Security pursuant to ITT 46. The Procuring Entity shall also promptly return the tender security to the tenderers where the procurement proceedings are terminated, all tenders were determined non-responsive or a bidder declines to extend tender validity period.
- 187 The Tender Security of the successful Tenderer shall be returned as promptly as possible once the successful Tenderer has signed the Contract and furnished the required Performance Security.
- 188 The Tender Security may be forfeited or the Tender Securing Declaration executed:
  - a) if a Tenderer withdraws its Tender during the period of Tender validity specified by the Tenderer in the Form of Tender, or any extension thereto provided by the Tenderer; or
  - b) if the successful Tenderer fails to:
    - i) sign the Contract in accordance with ITT 45; or
    - ii) furnish a Performance Security in accordance with ITT 46.
- Where tender securing declaration is executed, the Procuring Entity shall recommend to the PPRA that PPRA debars the Tenderer from participating in public procurement as provided in the law.

- 18.10 The Tender Security or Tender- Securing Declaration of a JV must be in the name of the JV that submits the Tender. If the JV has not been legally constituted into a legally enforceable JV at the time of Tendering, the Tender Security or Tender-Securing Declaration shall be in the names of all future members as named in the letter of intent referred to in ITT3.1 and ITT 10.2.
- 18.11 A tenderer shall not issue a tender security to guarantee itself.

#### 19. Format and Signing of Tender

- 19.1 The Tenderer shall prepare one original of the documents comprising the Tender as described in ITT 11 and clearly mark it "ORIGINAL." Alternative Tenders, if permitted in accordance with ITT 12, shall be clearly marked "ALTERNATIVE." In addition, the Tenderer shall submit copies of the Tender, in the number **specified in the TDS** and clearly mark them "COPY." In the event of any discrepancy between the original and the copies, the original shall prevail.
- 192 Tenderers shall mark as "CONFIDENTIAL" information in their Tenders which is confidential to their business. This may include proprietary information, trade secrets, or commercial or financially sensitive information.
- The original and all copies of the Tender shall be typed or written in indelible ink and shall be signed by a person duly authorized to sign on behalf of the Tenderer. This authorization shall consist of a written confirmation **as specified in the TDS** and shall be attached to the Tender. The name and position held by each person signing the authorization must be typed or printed below the signature. All pages of the Tender where entries or amendments have been made shall be signed or initialed by the person signing the Tender.
- 19.4 In case the Tenderer is a JV, the Tender shall be signed by an authorized representative of the JV on behalf of the JV, and so as to be legally binding on all the members as evidenced by a power of attorney signed by each members' legally authorized representatives.
- Any inter-lineation, erasures, or overwriting shall be valid only if they are signed or initialed by the person signing the Tender.

#### D. Submission and Opening of Tenders

#### 20 Sealing and Marking of Tenders

- 20.1 Depending on the sizes or quantities or weight of the tender documents, a tenderer may use an envelope, package or container. The Tenderer shall deliver the Tender in a single sealed envelope, or in a single sealed package, or in a single sealed container bearing the name and Reference number of the Tender, addressed to the Procuring Entity and a warning not to open before the time and date for Tender opening date. Within the single envelope, package or container, the Tenderer shall place the following separate, sealed envelopes:
  - a) in an envelope or package or container marked "ORIGINAL", all documents comprising the Tender, as described in ITT 11; and
  - b) in an envelope or package or container marked "COPIES", all required copies of the Tender; and
  - c) if alternative Tenders are permitted in accordance with ITT 12, and if relevant:
    - i) in an envelope or package or container marked "ORIGINAL -ALTERNATIVE TENDER", the alternative Tender; and
    - ii) in the envelope or package or container marked "COPIES- ALTERNATIVE TENDER", all required copies of the alternative Tender.
- 202 The inner envelopes or packages or containers shall:
  - a) bear the name and address of the Procuring Entity.
  - b) bear the name and address of the Tenderer; and
  - c) bear the name and Reference number of the Tender.
- 203 Where a tender package or container cannot fit in the tender box, the procuring entity shall:
  - a) Specify in the **TDS where** such documents should be received.
  - b) maintain a record of tenders received and issue acknowledgement receipt note to each tenderer specifying time and date of receipt.
  - c) Ensure all tenders received are handed over to the tender opening committee for opening at the specified opening place and time.

204 If an envelope or package or container is not sealed and marked as required, the *Procuring Entity* will assume no responsibility for the misplacement or premature opening of the Tender. Tenders misplaced or opened prematurely will not be accepted.

#### 21. Deadline for Submission of Tenders

- 21.1 Tenders must be received by the Procuring Entity at the address and no later than the date and time specified **in the TDS**. When so specified **in the TDS**, Tenderers shall have the option of submitting their Tenders electronically. Tenderers submitting Tenders electronically shall follow the electronic Tender submission procedures **specified in the TDS**.
- The Procuring Entity may, at its discretion, extend the deadline for the submission of Tenders by amending the tendering document in accordance with ITT7, in which case all rights and obligations of the Procuring Entity and Tenderers previously subject to the deadline shall thereafter be subject to the deadline as extended.

#### 22. Late Tenders

22.1 The Procuring Entity shall not consider any Tender that arrives after the deadline for submission of Tenders. Any Tender received by the Procuring Entity after the deadline for submission of Tenders shall be declared late, rejected, and returned unopened to the Tenderer.

#### 23. Withdrawal, Substitution, and Modification of Tenders

- A Tenderer may withdraw, substitute, or modify its Tender after it has been submitted by sending a written notice, duly signed by an authorized representative, and shall include a copy of the authorization (the power of attorney) in accordance with ITT19.3, (except that withdrawal notices do not require copies). The corresponding substitution or modification of the Tender must accompany the respective written notice. All notices must be:
  - a) prepared and submitted in accordance with ITT 20 and 21 (except that withdrawal notices do not require copies), and in addition, the respective envelopes shall be clearly marked "WITHDRAWAL," "SUBSTITUTION," or "MODIFICATION;" and
  - b) received by the Procuring Entity prior to the deadline prescribed for submission of Tenders, in accordance with ITT 22.
- Tenders requested to be withdrawn in accordance with ITT 23.1 shall be returned unopened to the Tenderers.
- No Tender may be withdrawn, substituted, or modified in the interval between the deadline for submission of Tenders and the expiration of the period of Tender validity specified by the Tenderer on the Form of Tender or any extension thereof.

#### 24. Tender Opening

- Except as in the cases specified in ITT 23, the Procuring Entity shall, at the Tender opening, publicly open and read out all Tenders received by the deadline at the date, time and place specified in the TDS in the presence of Tenderers' designated representatives who choose to attend, including to attend any specific electronic tender opening procedures if electronic tendering is permitted in accordance with ITT 21.1, shall be as specified in the TDS.
- First, envelopes marked "WITHDRAWAL" shall be opened and read out and the envelope with the corresponding Tender shall not be opened, but returned to the Tenderer. If the withdrawal envelope does not contain a copy of the "power of attorney" confirming the signature as a person duly authorized to sign on behalf of the Tenderer, the corresponding Tender will be opened. No Tender withdrawal shall be permitted unless the corresponding withdrawal notice contains a valid authorization to request the withdrawal and is read out at Tender opening.
- Next, envelopes marked "SUBSTITUTION" shall be opened and read out and exchanged with the corresponding Tender being substituted, and the substituted Tender shall not be opened, but returned to the Tenderer. No Tender substitution shall be permitted unless the corresponding substitution notice contains a valid authorization to request the substitution and is read out at Tender opening.

- Next, envelopes marked "MODIFICATION" shall be opened and read out with the corresponding Tender. No Tender modification shall be permitted unless the corresponding modification notice contains a valid authorization to request the modification and is read out at Tender opening.
- Next, all remaining envelopes shall be opened one at a time, reading out: the name of the Tenderer and whether there is a modification; the total Tender Prices, per lot (contract) if applicable, including any discounts and alternative Tenders; the presence or absence of a Tender Security, if required; and any other details as the Procuring Entity may consider appropriate.
- Only Tenders, alternative Tenders and discounts that are opened and read out at Tender opening shall be considered further for evaluation. The Form of Tender and pages of the Bills of Quantities are to be initialed by the members of the tender opening committee attending the opening. The number of representatives of the Procuring Entity to sign shall be specified in the **TDS**.
- 24.7 The Procuring Entity shall neither discuss the merits of any Tender nor reject any Tender (except for late Tenders, in accordance with ITT 22.1).
- 248 The Procuring Entity shall prepare a record of the Tender opening that shall include, as a minimum:
  - a) the name of the Tenderer and whether there is a withdrawal, substitution, or modification;
  - b) the Tender Price, per lot (contract) if applicable, including any discounts;
  - c) any alternative Tenders;
  - d) the presence or absence of a Tender Security or Tender-Securing Declaration, if one was required;
  - e) number of pages of each tender document submitted.
- 249 The Tenderers' representatives who are present shall be requested to sign the record. The omission of a Tenderer signature on the record shall not invalidate the contents and effect of the record. A copy of the tender opening register shall be issued to a Tenderer upon request.

#### **E.** Evaluation and Comparison of Tenders

#### 25. Confidentiality

- 25.1 Information relating to the evaluation of Tenders and recommendation of contract award, shall not be disclosed to Tenderers or any other persons not officially concerned with the tendering process until the information on Intention to Award the Contract is transmitted to all Tenderers in accordance with ITT 41.
- 252 Any effort by a Tenderer to influence the Procuring Entity in the evaluation or contract award decisions may result in the rejection of its Tender.
- Notwithstanding ITT 25.2, from the time of Tender opening to the time of Contract Award, if any Tenderer wishes to contact the Procuring Entity on any matter related to the Tendering process, it should do so in writing.

#### **26.** Clarification of Tenders

To assist in the examination, evaluation, comparison of the Tenders, and qualification of the Tenderers, the Procuring Entity may, at its discretion, ask any Tenderer for a clarification of its Tender. Any clarification submitted by a Tenderer in respect to its Tender and that is not in response to a request by the Procuring Entity shall not be considered. The Procuring Entity's request for clarification and the response shall be in writing. No change, including any voluntary increase or decrease, in the prices or substance of the Tender shall be sought, offered, or permitted except to confirm the correction of arithmetic errors discovered by the Procuring Entity in the Evaluation of the Tenders, in accordance with ITT 30.

If a Tenderer does not provide clarifications of its Tender by the date and time set in the Procuring Entity's request for clarification, its Tender may be rejected.

#### 27. Deviations, Reservations, and Omissions

- 27.1 During the evaluation of Tenders, the following definitions apply:
  - a) "Deviation" is a departure from the requirements specified in the Tendering document;

- b) "Reservation" is the setting of limiting conditions or withholding from complete acceptance of the requirements specified in the tendering document; and
- c) "Omission" is the failure to submit part or all of the information or documentation required in the tendering document.

#### 28. Determination of Responsiveness

- 28.1 The Procuring Entity's determination of a Tender's responsiveness is to be based on the contents of the Tender itself, as defined in ITT28.2.
- 28 A substantially responsive Tender is one that meets the requirements of the tendering document without material deviation, reservation, or omission. A material deviation, reservation, or omission is one that:
  - a) if accepted, would:
    - i) affect in any substantial way the scope, quality, or performance of the Goods and Related Services specified in the Contract; or
    - ii) limit in any substantial way, inconsistent with the tendering document, the Procuring Entity's rights or the Tenderer obligations under the Contract; or
  - b) if rectified, would unfairly affect the competitive position of other Tenderers presenting substantially responsive Tenders.
- The Procuring Entity shall examine the technical aspects of the Tender submitted in accordance with ITT 15 and ITT 16, in particular, to confirm that all requirements of Section VII, Schedule of Requirements have been met without any material deviation or reservation, or omission.
- 283 If a Tender is not substantially responsive to the requirements of tendering document, it shall be rejected by the Procuring Entity and may not subsequently be made responsive by correction of the material deviation, reservation, or omission.

#### 29. Non-conformities, Errors and Omissions

- 29.1 Provided that a Tender is substantially responsive, the Procuring Entity may waive any non-conformities in the Tender.
- 292 Provided that a Tender is substantially responsive, the Procuring Entity may request that the Tenderer submit the necessary information or documentation, within a reasonable period of time, to rectify nonmaterial non- conformities or omissions in the Tender related to documentation requirements. Such omission shall not be related to any aspect of the price of the Tender. Failure of the Tenderer to comply with the request may result in the rejection of its Tender.
- Provided that a Tender is substantially responsive, the Procuring Entity shall rectify quantifiable nonmaterial non-conformities related to the Tender Price. To this effect, the Tender Price shall be adjusted, for comparison purposes only, to reflect the price of a missing or non-conforming item or component in the manner specified **in the TDS**. The adjustment shall be based on the *average* price of the item or component as quoted in other substantially responsive Tenders. If the price of the item or component cannot be derived from the price of other substantially responsive Tenders, the Procuring Entity shall use its best estimate.

#### **30.** Arithmetical Errors

- 30.1 The tender sum as submitted and read out during the tender opening shall be absolute and final and shall not be the subject of correction, adjustment or amendment in any way by any person or entity.
- Provided that the Tender is substantially responsive, the Procuring Entity shall handle errors on the following basis:
  - a) Any error detected if considered a major deviation that affects the substance of the tender, shall lead to disqualification of the tender as non-responsive.
  - b) Any errors in the submitted tender arising from a miscalculation of unit price, quantity, subtotal

- and total bid price shall be considered as a major deviation that affects the substance of the tender and shall lead to disqualification of the tender as non-responsive. and
- c) if there is a discrepancy between words and figures, the amount in words shall prevail.
- 303 Tenderers shall be notified of any error detected in their bid during the notification of a ward.

#### 31. Conversion to Single Currency

31.1 For evaluation and comparison purposes, the currency(ies) of the Tender shall be converted in a single currency as specified in the TDS.

#### **32** Margin of Preference and Reservations

- 32.1 A margin of preference may be allowed on locally manufactured goods only when the contract is open to international tendering, where the tender is likely to attract foreign goods and where the contract exceeds the threshold specified in the Regulations.
- For purposes of granting a margin of preference on locally manufactured goods under international competitive tendering, a procuring entity shall not subject the items listed below to international tender and hence no margin of preference shall be allowed. The affected items are:
  - a) motor vehicles, plant and equipment which are assembled in Kenya;
  - b) furniture, textile, foodstuffs, oil and gas, information communication technology, steel, cement, leather agro-processing, sanitary products, and other goods made in Kenya; or
  - c) goods manufactured, mined, extracted or grown in Kenya.
- 323 A margin of preference shall not be allowed unless it is specified so in the **TDS**.
- 324 Contracts procured on basis of international competitive tendering shall not be subject to reservations to specific groups s as provided in ITT 32.5.
- Where it is intended to reserve a contract to a specific group of businesses (these groups are Small and Medium Enterprises, Women Enterprises, Youth Enterprises and Enterprises of persons living with disability, as the case may be), and who are appropriately registered as such by the authority to be specified in the **TDS**, a procuring entity shall ensure that the invitation to tender specifically indicates that only businesses or firms belonging to the specified group are eligible to tender as specified in the **TDS**. No tender shall be reserved to more than one group. If not so stated in the Tender documents, the invitation to tender will be open to all interested tenderers.

#### **33.** Evaluation of Tenders

- 33.1 The Procuring Entity shall use the criteria and methodologies listed in this ITT and Section III, Evaluation and Qualification criteria. No other evaluation criteria or methodologies shall be permitted. By applying the criteria and methodologies, the Procuring Entity shall determine the Lowest Evaluated Tender. This is the Tender of the Tenderer that meets the qualification criteria and whose Tender has been determined to be:
  - a) substantially responsive to the tender documents; and
  - b) the lowest evaluated price.
- Price evaluation will be done for Items or Lots (contracts), as specified **in the TDS**; and the Tender Price as quoted in accordance with ITT 14. To evaluate a Tender, the Procuring Entity shall consider the following:
  - a) price adjustment due to unconditional discounts offered in accordance with ITT 13.4;
  - b) converting the amount resulting from applying (a) and (b) above, if relevant, to a single currency in accordance with ITT 31;
  - c) price adjustment due to quantifiable nonmaterial non-conformities in accordance with ITT 29.3; and
  - d) any additional evaluation factors specified in the TDS and Section III, Evaluation and Qualification Criteria.
- 333 The estimated effect of the price adjustment provisions of the Conditions of Contract, applied over

the period of execution of the Contract, shall not be considered in Tender evaluation.

- Where the tender involves multiple lots or contracts, the tenderer will be allowed to tender for one or more lots (contracts). Each lot or contract will be evaluated in accordance with ITT 33.2. The methodology to determine the lowest evaluated tenderer or tenderers based one lot (contract) or based on a combination of lots (contracts), will be specified in Section III, Evaluation and Qualification Criteria. In the case of multiple lots or contracts, tenderer will be will be required to prepare the Eligibility and Qualification Criteria Form for each Lot.
- 335 The Procuring Entity's evaluation of a Tender will include and consider:
  - a) in the case of Goods manufactured in Kenya, sales and other similar taxes, which will be payable on the goods if a contract is awarded to the Tenderer;
  - b) in the case of Goods manufactured outside Kenya, already imported or to be imported, customs duties and other import taxes levied on the imported Good, sales and other similar taxes, which will be payable on the Goods if the contract is awarded to the Tenderer;
- The Procuring Entity's evaluation of a Tender may require the consideration of other factors, in addition to the Tender Price quoted in accordance with ITT 14. These factors may be related to the characteristics, performance, and terms and conditions of purchase of the Goods and Related Services. The effect of the factors selected, if any, shall be expressed in monetary terms to facilitate comparison of Tenders, unless otherwise specified in the **TDS** from amongst those set out in Section III, Evaluation and Qualification Criteria. The additional criteria and methodologies to be used shall be as specified in ITT 33.2(d).

#### **34.** Comparison of Tenders

34.1 The Procuring Entity shall compare the evaluated costs of all substantially responsive Tenders established in accordance with ITT 33.2 to determine the Tender that has the lowest evaluated cost. The comparison shall be on the basis of total cost (place of final destination) prices for all goods and all prices, plus cost of inland transportation and insurance to place of destination, for goods manufactured within the Kenya, together with prices for any required installation, training, commissioning and other services.

#### 35. Abnormally Low Tenders

- 35.1 An Abnormally Low Tender is one where the Tender price, in combination with other constituent elements of the Tender, appears unreasonably low to the extent that the Tender price raises material concerns with the Procuring Entity as to the capability of the Tenderer to perform the Contract for the offered Tender price.
- In the event of identification of a potentially Abnormally Low Tender by the evaluation committee, the Procuring Entity shall seek written clarification from the Tenderer, including a detailed price analyses of its Tender price in relation to the subject matter of the contract, scope, delivery schedule, allocation of risks and responsibilities and any other requirements of the tendering document.
- 353 After evaluation of the price analysis, in the event that the Procuring Entity determines that the Tenderer has failed to demonstrate its capability to perform the contract for the offered Tender price, the Procuring Entity shall reject the Tender.

#### 36. Abnormally High Tenders

- An abnormally high price is one where the tender price, in combination with other constituent elements of the Tender, appears unreasonably too high to the extent that the Procuring Entity is concerned that it (the Procuring Entity) may not be getting value for money or it may be paying too high a price for the contract compared with market prices or that genuine competition between Tenderers is compromised.
- 36.5 In case of an abnormally high tender price, the Procuring Entity shall make a survey of the market prices, check if the estimated cost of the contract is correct and review the Tender Documents to check if the specifications, scope of work and conditions of contract are contributory to the abnormally high tenders. The Procuring Entity may also seek written clarification from the tenderer on the reason for the high tender price. The Procuring Entity shall proceed as follows:
  - i) If the tender price is abnormally high based on wrong estimated cost of the contract, the Procuring Entity may accept or not accept the tender depending on the Procuring Entity's

- budget considerations.
- ii) If specifications, scope of work and/or conditions of contract are contributory to the abnormally high tender prices, the Procuring Entity shall reject all tenders and may retender for the contract based on revised estimates, specifications, scope of work and conditions of contract, as the case may be.
- 36.6 If the Procuring Entity determines that the Tender Price is abnormally too high because genuine competition between tenderers is compromised (often due to collusion, corruption or other manipulations), the Procuring Entity shall reject all Tenders and shall institute or cause relevant Government Agencies to institute an investigation on the cause of the compromise, before retendering.

#### 37. Post-Qualification of the Tenderer

- 37.1 The Procuring Entity shall determine, to its satisfaction, whether the eligible Tenderer that is selected as having submitted the lowest evaluated cost and substantially responsive Tender, meets the qualifying criteria specified in Section III, Evaluation and Qualification Criteria.
- The determination shall be based upon an examination of the documentary evidence of the Tenderer qualifications submitted by the Tenderer, pursuant to ITT 15 and 16. The determination shall not take into consideration the qualifications of other firms such as the Tenderer subsidiaries, parent entities, affiliates, subcontractors (other than specialized subcontractors if permitted in the tendering document), or any other firm(s) different from the Tenderer.
- An affirmative determination shall be a prerequisite for award of the Contract to the Tenderer. A negative determination shall result in disqualification of the Tender, in which event the Procuring Entity shall proceed to the Tenderer who offers a substantially responsive Tender with the next lowest evaluated cost to make a similar determination of that Tenderer qualifications to perform satisfactorily.

#### **38.** Lowest Evaluated Tender

- 38.1 Having compared the evaluated prices of Tenders, the Procuring Entity shall determine the Lowest Evaluated Tender. The Lowest Evaluated Tender is the Tender of the Tenderer that meets the Qualification Criteria and whose Tender has been determined to be:
  - a) most responsive to the Tender document; and
  - b) the lowest evaluated price.

#### 39. Procuring Entity's Right to Accept Any Tender, and to Reject Any or All Tenders.

39.1 The Procuring Entity reserves the right to accept or reject any Tender, and to annul the Tendering process and reject all Tenders at any time prior to notification Award, without thereby incurring any liability to Tenderers. In case of annulment, all Tenderers shall be notified with reasons and all Tenders submitted and specifically, tender securities, shall be promptly returned to the Tenderers.

#### F. Award of Contract

#### 40. Award Criteria

40.1 The Procuring Entity shall award the Contract to the successful tenderer whose tender has been determined to be the Lowest Evaluated Tender in accordance with procedures in Section 3: Evaluation and Qualification Criteria.

#### 41. KENYA REVENUE AUTHORITY'S Right to Vary Quantities at Time of Award

The KENYA REVENUE AUTHORITY reserves the right at the time of Contract award to increase or decrease, by the percentage (s) for items as indicated **in the TDS.** 

#### 42. Notice of Intention to enter into a Contract

Upon award of the contract and Prior to the expiry of the Tender Validity Period the Procuring Entity shall issue a Notification of Intention to Enter into a Contract / Notification of award to all tenderers which shall contain, at a minimum, the following information:

- a) the name and address of the Tenderer submitting the successful tender;
- b) the Contract price of the successful tender;
- c) a statement of the reason(s) the tender of the unsuccessful tenderer to whom the letter is addressed was unsuccessful, unless the price information in (c) above already reveals the reason;
- d) the expiry date of the Standstill Period; and
- e) instructions on how to request a debriefing and/or submit a complaint during the standstill period;

#### 43. Standstill Period

- 43.1 The Contract shall not be awarded earlier than the expiry of a Standstill Period of 14 days to allow any dissatisfied candidate to launch a complaint. Where only one Tender is submitted, the Standstill Period shall not apply.
- Where standstill period applies, it shall commence when the Procuring Entity has transmitted to each Tenderer the Notification of Intention to Enter into a Contract to the successful Tenderer.

#### 44. Debriefing by the KENYA REVENUE AUTHORITY

- 44.1 On receipt of the Procuring Entity's Notification of Intention to Enter into a Contract referred to in ITT 41, an unsuccessful tenderer may make a written request to the Procuring Entity for a debriefing on specific issues or concerns regarding their tender. The Procuring Entity shall provide the debriefing within five days of receipt of the request.
- Debriefings of unsuccessful Tenderers may be done in writing or verbally. The Tenderer shall bear its own costs of attending such a debriefing meeting.

#### 45. Letter of Award

Prior to the expiry of the Tender Validity Period and upon expiry of the Standstill Period specified in ITT 42, upon addressing a complaint that has been filed within the Standstill Period, the Procuring Entity shall transmit the Letter of Award to the successful Tenderer. The letter of award shall request the successful tenderer to furnish the Performance Security within 21days of the date of the letter.

#### 46. Signing of Contract

- 46.1 Upon the expiry of the fourteen days of the Notification of Intention to enter into contract and upon the parties meeting their respective statutory requirements, the Procuring Entity shall send the successful Tenderer the Contract Agreement.
- Within fourteen (14) days of receipt of the Contract Agreement, the successful Tenderer shall sign, date, and return it to the Procuring Entity.
- The written contract shall be entered into within the period specified in the notification of award and before expiry of the tender validity period.

#### 47. Performance Security

- Within twenty-one (21) days of the receipt of Letter of Acceptance from the Procuring Entity, the successful Tenderer, if required, shall furnish the Performance Security in accordance with the GCC 18, using for that purpose the Performance Security Form included in Section X, Contract Forms. If the Performance Security furnished by the successful Tenderer is in the form of a bond, it shall be issued by a bonding or insurance company that has been determined by the successful Tenderer to be acceptable to the Procuring Entity. A foreign institution providing a bond shall have a correspondent financial institution located in Kenya, unless the Procuring Entity has agreed in writing that a correspondent financial institution is not required.
- Failure of the successful Tenderer to submit the above-mentioned Performance Security or sign the Contract shall constitute sufficient grounds for the annulment of the award and forfeiture of the Tender Security. In that event the Procuring Entity may award the Contract to the Tenderer offering the next lowest Evaluated Tender.
- 473 Performance security shall not be required for a contract, if so specified in the TDS.

#### 48. Publication of Procurement Contract

48.1 Within fourteen days after signing the contract, the Procuring Entity shall publish and publicize the

awarded contract at its notice boards, entity website; and on the Website of the Authority in manner and format prescribed by the Authority. At the minimum, the notice shall contain the following information:

- a) name and address of the Procuring Entity;
- b) name and reference number of the contract being awarded, a summary of its scope and the selection method used;
- c) the name of the successful Tenderer, the final total contract price, the contract duration.
- d) dates of signature, commencement and completion of contract;
- e) names of all Tenderers that submitted Tenders, and their Tender prices as read out at Tender opening;

#### 49. Procurement Related Complaints and Administrative Review

- 49.1 The procedures for making a Procurement-related Complaint are as specified in the TDS.
- 492 A request for administrative review shall be made in the form provided under contract forms.

# SECTION II – TENDER DATA SHEET (TDS)

The following specific data for **Supply, Delivery, Installation and Commissioning of Local Area Networks** shall complement, supplement, or amend the provisions in the Instructions to Tenderers (ITT). Whenever there is a conflict, the provisions herein shall prevail over those in ITT.

ITT Refere nce	Particulars Of Appendix To Instructions To Tenders		
A. Gene	ral		
ITT 1.1	The reference number of the Invitation for Tenders is: <b>KRA/HQS/NCB-092/2022-2023</b> The procuring entity is: <b>KENYA REVENUE AUTHORITY</b>		
	The name of the Contract is: SUPPLY, DELIVERY, INSTALLATION AND COMMISSIONING OF LOCAL AREA NETWORKS (LANs) FOR KRA IDENTIFIED STATIONS		
ITT 1.2(a)	Electronic –Procurement System		
, ,	The Procuring Entity shall use the following electronic-procurement system to manage this Tendering process: <b>Eprocurement –Supplier Portal</b>		
	The electronic-procurement system shall be used to manage the following aspects of the Tendering process:		
	[list the aspects here and modify the relevant parts of the TDS accordingly e.g., issuing tendering document, submissions of Tenders, opening of Tenders]		
ITT 2.3	The Bidders to note that the <b>submission of Technical and Financial bid</b> should be combined and submitted <b>electronically via the supplier KRA Portal to Notes and Attachment Folder</b> .		
	The firms that provided consulting services for the contract being tendered for are: N/A		
ITT 3.1	Maximum number of members in the Joint Venture (JV) shall be: [NOT APPLICABLE)		
ITT 3.7	A list of debarred firms and individuals is available on the PPRA's website: www.ppra.go.ke		
	B. Contents of Tendering Document		
ITT 6.1	(For Clarification of Tender purposes only, the Procuring Entity's address is:		
0.1	Attention: Deputy Commissioner		
	Postal Address: Haile Selassie Avenue		
	Physical Address Times Tower, 21st Floor Boardroom 1		
	Telephone: 0709 012365		
	Electronic mail address: eprocurement@kra.go.ke		
	Requests for clarification should be received by the Procuring Entity no later than: 7 days to the tender closing date. Kenya Revenue Authority shall compile the requested clarification and post them in to KRA website <a href="www.kra.go.ke">www.kra.go.ke</a>		
	NB: Bidders are encouraged to frequently visit the KRA website to access addendum and clarifications that may be posted.		
ITT 6.2	A tender pre- bid shall be held on: 30th MAY 2023 at 11.00 AM.		
	Register via the hyper link provided here : PRE-BID CONFERENCE		
	Due to Covid-19 rules and guidelines, the tender pre-bid shall be virtual and bidders shall register for the pre-bid using the link provided at the invitation to tender page.		

ITT Refere nce	Particulars Of Appendix To Instructions To Tenders
ITT 6.3	Tenders "shall be submitted electronically to the notes and attachment folder on or before 7 <sup>TH</sup> JUNE, 2023 at 11:00 am
	The Kenya Revenue Authority shall use electronic-procurement system to manage this Tendering process.
	KRA shall use electronic-procurement system to manage this procurement process, which includes Issuing Notification of the Tender, Issuing the Tender documents, Bidders submissions of technical and financial proposals to the Authority, Issuance of addendums and opening of Proposals.
	C. Preparation of Tenders
ITT 10 (j)	The Bidders to note that the <b>submission of Technical and Financial Bid</b> shall be combined and submitted through the KRA supplier portal.
	Both the Technical and Financial Proposal shall be submitted <i>electronically via the supplier portal to Notes and Attachment Folder</i> .
ITT 12.1	Alternative Tenders (Are Not Considered.)
13.5	The prices quoted by the Tenderer <i>may</i> be subject to adjustment during the performance of the Contract subject to the Public Procurement and Asset Disposal Act, 2015 and Regulations 2020 and KRA requirements.
ITT 13.8 (a) (i) and (iii)	Place of final destination: <b>KRA Identified Stations</b>
ITT 13.8 (a) (iii)	Final Destination (Project Site): <b>KRA Identified Stations</b>
ITT 13.8 (b) (ii)	The Tenderer shall bear the price for inland transportation, insurance, and other local services required to convey the Goods from the named place of destination to their final destination which is : <b>KRA Identified Stations.</b>
13.8 (c) (iv)	The place of final destination (Project Site) is: <b>KRA Identified Stations</b>
ITT 14.2	Foreign currency requirements: Not Allowed. Bidders to quote in Kenya Shillings (KES) only.
ITT 15.4	Period of time the Goods are expected to be functioning (for the purpose of spare parts): <i>[insert duration</i> ]
ITT 16.2 (a)	Manufacturer's authorization is: [REQUIRED"]
ITT 16.2 (b)	After sales service is: [ "not required"]
ITT 17.1	The Tender validity period shall be <b>335 DAYS</b> .
ITT 17.3	(a) The Number of days beyond the expiry of the initial tender validity period will bedays. (N/A)
	(b) The Tender price shall be adjusted by the following percentages of the tender price: <b>N/A</b>
	(i) By% of the local currency portion of the Contract price adjusted to reflect local inflation during the period of extension, and

ITT Refere nce	Particulars Of Appendix To Instructions To Tenders			
	(ii) By% the foreign currency portion of the Contract price adjusted to reflect the international inflation during the period of extension.			
ITT 18.1	A tender security of Kshs 500,000.00 shall be required. The validity of the bid security shall be 365 days from the tender closing date.  Note: An original hard copy of the Bid Security of not less than the indicated amount or equivalent amount in a freely convertible currency must be dropped in the Tender Security Box located at Times Tower Building, Ground Floor any day before the tender closing date. The Bid Security must be in a sealed envelope bearing the Tender Description and addressed to the address indicated above.			
ITT 19.1	In addition to the original of the Tender, the number of copies is: [N/A)			
ITT 19.3	The written confirmation of authorization to sign on behalf of the Tenderer shall consist of:POWER OF ATTORNEY			
	D. Submission and Opening of Tenders			
ITT 20.3	The Bidders to note that the <b>submission of Technical and Financial Bid</b> should be combined and submitted through the KRA supplier portal.  a) Technical Proposal and Financial Proposal to be submitted <i>electronically via the supplier portal to Notes and Attachment Folder.</i>			
ITT 21.1	The date and time for submission of Tenders are:			
21.1	Date: 7 <sup>TH</sup> JUNE 2023			
	Time: 11.00am			
	For <b>Tender submission purposes</b> only, the Procuring Entity's			
	address is: Attention: Deputy Commissioner			
	Street Address: Haile Selassie Avenue			
	Floor/Room number: 21st Floor			
	City: <u>Times Tower, Nairobi</u> Kenya			
	The Bidders to note that the <b>submission of Technical and Financial Bid</b> shall be combined and submitted through the KRA supplier portal.			
	Both the Technical and Financial Proposal shall be submitted <i>electronically via the</i> supplier portal to Notes and Attachment Folder.			

ITT Refere nce	Par	ticula	rs Of Appendix To Instructions To Tenders			
	LUA'	TION	AND COMPARISON OF TENDERS			
ITT 29.3	re su	The following criteria will be used in the evaluation of all bids. The submission of the required documents will be used in the determination of the Completeness and suitability of the Bid. Bids that do not contain all the information required will be declared non responsive and shall not be evaluated further.				
	pre	ovid	s are advised to read and understand the criteria so as to e the documents required and the right response to the cal specification/scope of service.			
		A) N	MANDATORY REQUIREMENTS:			
	SUI (LA	PPLY, Ns) F	DELIVERY, INSTALLATION AND COMMISSIONING OF LOCAL AREA NETWORK OR KRA IDENTIFIED STATIONS			
	-	1	Description Form of Tender duly filled, signed, stamped and printed on tenderer letter head.			
		2	A detailed signed & stamped price schedule for services.  Bidders are advised that the preferred currency for this tender is Kenya Shillings Only.			
		3	Tender Security of Kshs 500,000.00 - valid for 365 days from the date of tender closing. NB: Original tender security MUST be deposited on the TENDER SECURITY BOX at Ground Floor Times Tower Building, Nairobi.			
		4	Power of Attorney (except for sole proprietors)			
		5	Copy of valid Business License / Permit			
		6	Company Profile Certificate of Incorporation/ Registration			
	-	7	Current CR12 certificate for Limited Companies issued by the Registrar of Companies. This should be within the last twelve (12) months from the tender closing date. Sole proprietors and partners should provide ID cards for the sole proprietor/ partner (bidders can generate the CR12 from ecitizen)			
		8	Commitment letter address to KRA  Bidder MUST commit to undertake concurrent installation of LANs for ALL the station in the Lot they bided for, if awarded.			
		9.	Financial Resources Submit. Reference Letter from the bank indicating that the firm is currently operating an account (not older than 6 months from the date of the tender closing date).			
	   	10.	Submit a three (3) years Audited Account (2019, 2020, 2021/2022) with at least an average annual turnover of Kshs 50 Million OR Submit a bank letter of credit facility from a recognized financial institution that is regulated by CBK of Kshs 30 Million.			

11	Social Obligations Submit certificate of compliance for the following;  • A valid Tax Compliance Certificate
12	Tenderers must duly fill, sign and stamp the following forms found under Section IV – Tendering Forms
	Tenderer's Eligibility - Confidential Business Questionnaire
	Disclosure of Interest- Interest of the Firm in KRA.
	Certificate of Independent Tender Determination
	Self-Declaration Forms - SD1
	• Self-Declaration that the Person/Tenderer will not engage in any Corrupt or Fraudulent Practice. – SD2
	Declaration and Commitment to the Code of Ethics.

#### Note:

Bidders who shall not meet ALL the mandatory requirements shall be disqualified from further evaluation.

#### **B) VENDOR EVALUATION**

The following criteria shall be used in the evaluation of all potential Contractors for the supply, delivery, Installation and Commissioning of LANs.

The documents submitted will be evaluated for suitability and marks awarded which, will contribute to a maximum **30 marks** of the total tender evaluation. The **cut off score shall be 20 marks** for bidders to proceed to the next stage of evaluation.

No	Feature	Minimum Requirements	Maximum Score
1.	Key Personnel	Key Personnel Academic, Professional Certification and relevant Experience	
		The key personnel must have the requisite Academic qualifications, professional and Technical skills and experience in Design and Deployment of Enterprise Network.	15
		The proposed key personnel must include at least 3 Technical Staff with Academic qualification in the field of Electrical and Electronic Engineering/Computer science	
		or other ICT related degrees. The Key Personnel Must equally have Professional Networking Certifications	
		Attach CVs, copies of Academic Certificates and Professional Networking certifications for each of the key personnel.	
		<b>Note:</b> Only a CV supported by relevant academic and professional certificates will be scored.	

ITT Refere nce	Particulars Of Append	ix To Instructions To Tenders		
	2. Firm's Relevant works experience	Degree or Post Graduate in Electrical &Electronics Engineering/Computer science or related field and a valid Professional Networking Certification3 marks Diploma Electrical &Electronics Engineering/Computer science or related field and a valid Professional Networking Certification	15	

ITT Refere nce	Particulars Of Appendix To Instructions To Tenders				
	NB: Reference letter should have full contacts; postal address, telephone and email.				
	Total/Maximum Score	30			
	Cut off Score	20			

The cut -off score is 20 marks.

#### Note:

A bidder must meet the cut-off score in order to proceed to the next stage of evaluation.

#### C) TECHNICAL EVALUATION

Refer to Clause-by-Clause Technical Specifications under **PART 2: SUPPLY REQUIREMENTS - TECHNICAL SPECIFICATION REQUIREMENTS FOR EACH LOT.** 

#### **Note:**

• To be considered for any LOT, bidder(s) MUST comply with ALL the technical requirements under the LOT(s) the bidder is bidding for/ participating in. Failure to comply will lead to automatic disqualification.

#### Site Visit Form

A site visit form may be duly filled for each site visited. (Bidders may choose to visit the site to understand the scope of service before submitting their bids).

#### PRICE SCHEDULES

Bidders <u>MUST</u> complete ALL the Price Schedules in the format provided for the LOT(s) bidding for/participating in. Any in incomplete price schedule will lead to disqualification. (Bidders may choose to bid for multiple Lots but can only be awarded one (1) Lot. In the event a bidder happens to be the lowest evaluated bidder in multiple lots, the bidder shall be awarded the Lot with the highest monetary value among them.)

#### **OVERALL SCORE**

#### **Tender Evaluation Weighting Criteria**

The tender evaluation criteria is weighted as follows

Criteria	Maximum Score/Requirement	Cut-Off Score
Tender Responsiveness	Mandatory	Met
Vendor Evaluation	30	20
Clause-by-Clause Technical Specifications	PASS/FAIL	Met

ITT	Particulars Of Appendix To Instructions To Tenders				
Refere nce					
	for the LOT(s) bidding for.				
	Financial Evaluation	Award shall be to the lowest evaluated bidder per LOT.  In the event a bidder happens to be the lowest evaluated bidder in multiple Lots, the bidder shall be awarded the Lot with			
	Post Qualification Evaluation	<ul> <li>the highest monetary value among them.</li> <li>KRA shall carry out due diligence to ascertain the bidders past performance.</li> </ul>			
	PERFORMANCE SECURITY/BOND  A Performance security shall be required: 5% of contract price.				
ITT 31.1	The currency (ies) of the Tender shall be converted into a single currency – <b>KENYA SHILLING</b> The currency that shall be used for Tender evaluation and comparison purposes to convert all Tender prices expressed in various currencies into a single currency is: KENYA SHILLING.  A Tender Prices shall only be admissible for a Single Currency :Kenya				
ITT 32.3	Shillings only.  A margin of preference and/or reservation [ "shall not"] apply and specify the details.  If a margin of preference applies, the application methodology shall be defined in Section III –  Evaluation and Qualification Criteria.				
ITT 32.5	The invitation to tender is extended to the following group that qualify for ReservationsNot Applicable_ who shall be duly registered with.(These groups are Small and Medium Enterprises, Women Enterprises, Youth Enterprises and Enterprises of persons living with disability, as the case may be; describe precisely which group qualifies).				
ITT 33.2	Price evaluation shal be done Lot-by-Lot for the Supply, Delivery, Installation and Commissioning of Local Area Networks (Lans) for KRA Identified Stations.				
7000	The award will be made on the b	pasis of the Evaluation Criteria provided.			
ITT 33.2 (d)	<b>Additional evaluation factors are</b> A Post Prequalification inform of due diligence may be carried out at reference sites provided by the bidder.				
ITT 33.6	The adjustments shall be determined using the following criteria, from amongst those set of Section III, Evaluation and Qualification Criteria: [refer to Section III, Evaluation Qualification Criteria; insert complementary details if necessary]  (a) Deviation in Delivery schedule: [insert Yes or No. If yes insert the adjustment factor Section III, Evaluation and Qualification Criteria]				
	<ul> <li>(b) Deviation in payment schedule: [insert Yes or No. If yes insert the adjustment factor in Section III, Evaluation and Qualification Criteria]</li> <li>(c) the cost of major replacement component, mandatory spare parts, and service: [insert Yes or No. If yes, insert the Methodology and criteria in Section III, Evaluation and Qualification Criteria]</li> </ul>				
	Tender [insert Yes or No. If ye Evaluation and Qualification Crit (e) Life cycle costs: the costs during the insert the Methodology and criteria.	arts and after-sales services for the equipment offered in the es, insert the Methodology and criteria in Section III, teria] the life of the goods or equipment [insert Yes or No. If yes, ia in Section III, Evaluation and Qualification Criteria] of the equipment offered; [Insert Yes or No. If yes, insert]			
	the Methodology and criteria] (g) [insert any other specific criteria i F. Award of Contract	in Section III, Evaluation and Qualification Criteria]			

ITT	Particulars Of Appendix To Instructions To Tenders		
Refere			
nce			
ITT 41.1	The maximum percentage by which quantities may be increased is: [insert percentage]		
	The maximum percentage by which quantities may be decreased is: [insert percentage]		
ITT 47.4	<b>Performance security</b> may be required in accordance with Sections 142, 143, 144 and 145 of the Public Procurement and Asset Disposal Act, 2015.		
47.5	If required, the <b>Performance Security</b> shall be in form of a Bank Guarantee from a Bank Regulated by Central Bank of Kenya (CBK) or Bank Guarantee from an authorized financial institution or in form of a Performance Guarantee/Bond from an Insurance Company Registered, Listed and Licensed by the Insurance Regulatory Authority (IRA), equivalent to the <b>five (5%) percentage</b> of the contract value as shall be indicated in the Award Letter issued by KRA.		
1TT 49.1	The procedures for making a Procurement-related Complaint are detailed in the "Notice of Intention to Award the Contract" herein and are also available from the PPRA Website <a href="https://www.ppra.go.ke">www.ppra.go.ke</a> .  If a Tenderer wishes to make a Procurement-related Complaint, the Tenderer should submit its complaint following these procedures, in writing (by the quickest means available, that is either by email or fax), to:  For the attention: [insert full name of person receiving complaints]  Title/position: [insert title/position]		
	Title/position: [insert title/position] KENYA REVENUE AUTHORITY: [insert name of KENYA REVENUE AUTHORITY] Email address: [insert email address] In summary, a Procurement-related Complaint may challenge any of the following:  1. the terms of the Tendering Documents; and 2. the KENYA REVENUE AUTHORITY's decision to award the contract.		

#### SECTION III - EVALUATION AND QUALIFICATION CRITERIA

#### 1. General Provisions

- Wherever a Tenderer is required to state a monetary amount, Tenderers should indicate the Kenya Shilling equivalent using the rate of exchange determined as follows:
  - a) For business turnover or financial data required for each year Exchange rate prevailing on the last day of the respective calendar year (in which the amounts for that year is to be converted) was originally established.
  - b) Value of single contract Exchange rate prevailing on the date of the contract signature.
  - c) Exchange rates shall be taken from the publicly available source identified in the ITT 14.3. Any error in determining the exchange rates in the Tender may be corrected by the Procuring Entity.
- This section contains the criteria that the Procuring Entity Procuring Entity shall use to evaluate tender and qualify tenderers. No other factors, methods or criteria shall be used other than those specified in this tender document. The Tenderer shall provide all the information requested in the forms included in Section IV, Tendering Forms. The Procuring Entity should use the Standard Tender Evaluation Report for Goods and Works for evaluating Tenders.

#### 2. Evaluation of Tenders (ITT 33)

#### 21 Successful Tender or Tenders

The Procuring Entity shall use the criteria and methodologies listed in this Section to evaluate Tenders. By applying these criteria and methodologies, the Procuring Entity shall determine the successful Tender or Tenders which has/have been determined to:

- a) be substantially responsive to the tender documents;
- b) offer the lowest evaluated cost to the Procuring Entity for all items of Goods to be procured based on either a single Contract or all multiple Contracts combined, as the case may be, in accordance with the ITT 13.6 inviting Tender prices and discounts, and provisions made of the Tender Document for evaluation of tenders and award of contract (s); and
- c) be offered by Tenderer or Tenderers that substantially meet the qualification criteria applicable for Contract or combined Contracts for which they are selected.

#### 22 Evaluation of Tenders

#### **Preliminary examination for Determination of Responsiveness**

The Procuring Entity will start by examining all tenders to ensure they meet in all respects the eligibility criteria and other mandatory requirements in the ITT, and that the tender is complete in all aspects in meeting the requirements provided for in the preliminary evaluation criteria outlined below. The Standard Tender Evaluation Report Document for Goods and Works for evaluating Tenders provides very clear guide on how to deal with review of these requirements. Tenders that do not pass the Preliminary Examination will be considered non-responsive and will not be considered further.

#### **Tender Evaluation Weighting Criteria**

The tender evaluation criteria is weighted as follows:

Criteria	Maximum Score/Requirement	Cut-Off Score	
Tender Responsiveness	Mandatory	Met	
Vendor Evaluation	30	20	
Clause-by-Clause Technical	PASS/FAIL	Met	
Specifications			
Financial Evaluation	Award shall be to the <b>lowest evaluated bidder per</b>		
	LOT. In the event a bidder happens to be the lowest evaluated bidder in multiple Lots, the bidder shall		
	be awarded the Lot with the highest monetary		
	value among them.		
Post Qualification Evaluation	KRA shall carry out due diliger	nce to ascertain	
	the bidders past performance.		

#### PRICE EVALUATION

Consistent with and in addition to the criteria listed in ITT 33.3 and ITT 29.3; and ITT 34 and its subparagraphs the following criteria shall apply:

#### 221 Evaluation of Technical aspects of the Tender

The Procuring Entity shall evaluate the Technical aspects of the Tender to determine compliance with the Procuring Entity's requirements under Section V 'Schedule of Requirement' and whether the Tenders are substantially responsive to the Technical Specifications and other Requirements.

[The Procuring Entity will highlight herein any particular details, characteristics, functional guarantees or

other requirements under the specifications, which the Tenderer is required to specifically confirm or provide details as per Section V, Supply Requirements or other parts of the Tender Document. To facilitate, a template may be attached or clearly described all information and list of documentation to be submitted by Tenderers to enable evaluation of Technical parts of the Tender]

#### 222 Evaluation of Commercial Terms and Conditions of the Tender (ITT 33.1(a)):

The Procuring Entity shall determine whether the Tenders are substantially responsive to the Commercial and Contractual Terms and Conditions (e.g. Performance securities, Payment and delivery schedules).

[The Procuring Entity will highlight herein any particular requirements under the Contract which the Tenderer is required to specifically confirm or provide information to enable evaluation of Commercial Terms and Conditions of the Tender]

#### **Evaluation Criteria (Other Factors) (ITT 33.6)**

The Procuring Entity's evaluation of a Tender may take into account, in addition to the Tender Price quoted in accordance with ITT 13.8, one or more of the following factors as specified in ITT 33.2(d) and in TDS ITT 33.6, using the following criteria and methodologies.

#### a) Delivery schedule.

The Goods specified in the List of Goods are required to be delivered within the acceptable time range (after the earliest and before the final date, both dates inclusive) specified in Section V, Schedule of Requirements. No credit will be given to deliveries before the earliest date, and Tenders offering delivery after the final date shall be

treated as non-responsive. Within this acceptable period, an adjustment of [insert the adjustment factor], will be added, for evaluation purposes only, to the Tender price of Tenders offering deliveries later than the "Earliest Delivery Date" specified in Section V, Schedule of Requirements. [An adjustment factor of 0.5% per week of delay would be reasonable. However, the adjustment factor should not be more than the rate of Liquidated Damages to be applied in case of delay in delivery of Goods and Services under the Contract conditions.]

#### **b) Deviation in payment schedule**. [insert one of the following]

i. tenderers shall state their Tender price for the payment schedule outlined in the SCC. Tenders shall be evaluated on the basis of this base price. tenderers are, however, permitted to state an alternative payment schedule and indicate the reduction in Tender price they wish to offer for such alternative payment schedule. The Procuring Entity may consider the alternative payment schedule and the reduced Tender price offered by the tenderer selected on the basis of the base price for the payment schedule outlined in the SCC.

or

- ii. The SCC stipulates the payment schedule specified by the Procuring Entity. If a Tender deviate from the schedule and if such deviation is considered acceptable to the Procuring Entity, the Tender will be evaluated by calculating interest earned for any earlier payments involved in the terms outlined in the Tender as compared with those stipulated in the SCC, at the rate per annum [insert adjustment rate].
- c) Cost of major replacement components, mandatory spare parts, and service. [insert one of the followings]

The list of items and quantities of major assemblies, components, and selected spare parts, likely to be required during the initial period of operation specified in the TDS 15.4, is in the List of Goods. An adjustment equal to the total cost of these items, at the unit prices quoted in each Tender, shall be added to the Tender price, for evaluation purposes only.

or

The Procuring Entity will draw up a list of high-usage and high-value items of components and spare parts, along with estimated quantities of usage in the initial period of operation specified in the TDS 15.4. The total cost of these items and quantities will be computed from spare parts unit prices submitted by the tenderer and added to the Tender price, for evaluation purposes only.

or

Tenderer shall provide along with its Tender, the list of recommended spare parts for Goods offered indicating for each item of spare part the recommended quantity and unit, and total CIP final destination prices required during the initial period of operation specified in the TDS 15.4. The prices offered shall not exceed the prevailing prices charged to other parties by the Tenderer. The cost of such spare parts will not be taken into account for tender evaluation. The Procuring Entity may award the contract for spare parts to the Tenderer that is successful for the supply of Goods, by selecting at its option, from the Tender's list of recommended spare parts, such items and quantities against each as the Procuring Entity may deem appropriate at the unit prices indicated by the Tenderer but not exceeding ----% (present) of the cost of Goods [normally not more than 10% or 15%.]

d) Availability in Kenya of spare parts and after sales services for equipment offered in the Tender.

An adjustment equal to the cost to the Procuring Entity of establishing the minimum service facilities and parts inventories if quoted separately, shall be added to the Tender price, for evaluation purposes only.

#### e) Life Cycle Costs

If specified in TDS 33.6, an adjustment to consider the additional life cycle costs for the period specified below, such as the operating and maintenance costs of the Goods, will be added to the Tender price, for evaluation purposes only. The adjustment will be evaluated in accordance with the methodology specified below and the following information:

[Note to Procuring Entity: Life cycle costing should be used when the costs of operation and/or maintenance over the specified life of the goods are estimated to be considerable in comparison with the initial cost and may vary among different Tenders. Life cycle costs shall be evaluated on a net present value basis. If life cycle costs apply, then specify the factors required to determine them for evaluation purposes.

[Either amend the following text as required, or delete if life cycle cost is not applicable]

- i) number of years for life cycle cost determination [insert the number of years of economic life of Goods];
- ii) the discount rate to be applied to determine the net present value of the life-cycle-cost is [insert the discount rate];
- the annual operating and maintenance costs (recurrent costs) shall be determined on the basis of the following methodology: [insert methodology E.G. This should include factors that will be used for determination of life-cycle- cost such as costs of operation and maintenance, residual value at the end of economic life of Goods, major elements that will be used for determination of cost of operation and maintenance such as fuel, power, labor, spare parts, etc. unit prices of elements such as fuel, power, etc., quantity of annual usage such as Kms or Hours of operation of Goods, Formula for calculation of LCC, etc];
- iv) and the following information is required from tenderers [insert any information required from tenderers, including prices e.g. Guaranteed fuel and/or power consumption, cost of labour, spare parts, etc].

#### f) Performance and productivity of the equipment: [insert one of the followings]

i) Performance and productivity of the equipment. An adjustment representing the capitalized cost of additional operating costs over the life of the goods will be added to the Tender price, for evaluation purposes if specified in the TDS 33.6. The adjustment will be evaluated based on the drop in the guaranteed performance or efficiency offered in the Tender below the norm of 100, using the methodology specified below.

[Insert the methodology and criteria if applicable e.g. The Following aspects could be considered in the formulation of this methodology and criteria: (i) Tender price for the equipment; ii) Price of spare parts required for AAA years of operations, iii) Adjustments to tender price for omissions, deviations and exceptions to technical and commercial conditions in the tender documents; iv) Capitalized cost savings due to the equipment efficiency at the rate of XXX (specify currency and amount) for each YYY % (percent) above the minimum ZZZ % (percent) efficiency; v) Capitalized cost for the auxiliary power consumption at PPP (specify currency and amount) per KW for AAA years; and vi) Applicable discount rate of BBB%.]

or

ii) An adjustment to consider the productivity of the goods offered in the Tender will be added to the Tender price, for evaluation purposes only, if specified in ITT 33.6. The adjustment will be evaluated based on the cost per unit of the actual productivity of goods offered in the Tender with respect to minimum required values, using the methodology specified below.

[Insert the methodology and criteria if applicable E.G. The evaluation and comparison of responsive tenders shall be based on the total life cycle cost for XXX years, per unit of output. The life cycle cost shall be the

sum of the initial purchase price of the equipment and the cost of operation in electric energy for XXX years of operation at unit cost of AAA (specify currency and amount) per kwh, discounted to net present value at YYY percent.]

#### g) Specific additional criteria

[Other specific additional criteria to be considered in the evaluation, and the evaluation method shall be detailed in TDS 34.6][If specific **sustainable procurement technical requirements** have been specified in Section VII-Specification, **either** state that (i) those requirements will be evaluated on a pass/fail (compliance basis) **or** otherwise (ii) in addition to evaluating those requirements on a pass/fail (compliance basis), if applicable, specify the monetary adjustments to be applied to Tender Prices for comparison purposes on account of Tenders that exceed the specified minimum sustainable procurement technical requirements.]

#### 224. Multiple Contracts (ITT 33.4)

Multiple contracts will be permitted in accordance with ITT 33.4. Tenderers are evaluated on basis of Lots and the lowest evaluated tenderer identified for each Lot. The Procuring Entity will select one Option of the two Options listed below for award of Contracts.

#### **OPTION 1**

- i) If a tenderer wins only one Lot, the tenderer will be awarded a contract for that Lot, provided the tenderer meets the Eligibility and Qualification Criteria for that Lot.
- ii) If a tenderer wins more than one Lot, the tender will be awarded contracts for all won Lots, provided the tenderer meets the aggregate Eligibility and Qualification Criteria for all the Lots. The tenderer will be awarded the combination of Lots for which the tenderer qualifies and the others will be considered for award to second lowest the tenderers.

#### **OPTION 2**

The Procuring Entity will consider all possible combinations of won Lots [contract(s)] and determine the combinations with the lowest evaluated price. Tenders will then be awarded to the Tenderer or Tenderers in the combinations provided the tenderer meets the aggregate Eligibility and Qualification Criteria for all the won Lots.

#### 225. Alternative Tenders

(ITT 13.1) An alternative if permitted under

ITT 13.1, will be evaluated as follows: [insert

one of the following]

"A Tenderer may submit an alternative Tender only with a Tender for the base case. The Procuring Entity shall only consider the alternative Tenders offered by the Tenderer whose Tender for the base case was determined to be the Lowest Evaluated Tender."

or

"A Tenderer may submit an alternative Tender with or without a Tender for the base case. The Procuring Entity shall consider Tenders offered for alternatives as specified in the Technical Specifications of Section V, Schedule of Requirements. All Tenders received, for the base case, as well as alternative Tenders meeting the specified requirements, shall be evaluated on their own merits in accordance with the same

#### 3. MARGIN OF PREFERENCE

- 31 If the TDS so specifies, the Procuring Entity will grant a margin of preference of 15% (fifteen percent) to Tenderers offering goods manufactured, mined, extracted, grown, assembled or semi-processed in Kenya. Goods assembled or semi-processed in Kenya shall have a local content of not less than 40%.
- 32 The margin of preference will be applied in accordance with, and subject to, the following provisions:
  - a) Tenderers applying for such preference on goods offered shall provide, as part of the data for qualification, such information, including details of the goods produced in Kenya, so as to determine whether, according to the classification established by the Procuring Entity, a particular category of goods or group of goods qualifies for a margin of preference.
  - b) After Tenders have been received and reviewed by the Procuring Entity, goods offered in the responsive Tenders shall be assessed to ascertain they are manufactured, mined, extracted, grown, assembled or semi- processed in Kenya. Responsive tenders shall be classified into the following groups:
    - Group A: Tenders offering goods manufactured in Kenya, for which (a) labour, raw materials, and components from within Kenya account for more than forty (40) percent of the Ex-Works price; and (b) the production facility in which they will be manufactured or assembled has been engaged in manufacturing or assembling such goods at least since the date of Tender Submission date;
    - ii) Group B: All other Tenders offering Goods manufactured in Kenya;
    - *iii)* **Group C:** Tenders offering Goods manufactured outside Kenya that have been already imported or that will be imported.
  - c) To facilitate this classification by the Procuring Entity, the Tenderer shall complete whichever version of the Price Schedule furnished in the Tender Documents is appropriate. Incorrect classification may render the Tender non-responsive as no reclassification will be permitted after Tender opening. Tenderers shall provide correct information especially with respect to duties, taxes etc. paid on previously imported Goods and percentage of local labour, materials and components for Goods manufactured in Kenya as any false information which cannot be supported by documentation may render the Tender non-responsive besides other sanctions for providing falsified information.
  - **d)** The Procuring Entity will first review the Tenders to confirm the appropriateness of the Tender group classification to which Tenderers assigned their Tenders in preparing their Tender Forms and Price Schedules.
  - e) All evaluated Tenders in each group will then be compared to determine the lowest evaluated Tender of each group. Such lowest evaluated Tenders shall be compared with each other and if as a result of this comparison a Tender from Group A or Group B is the lowest, it shall be selected for the award.
  - If as a result of the preceding comparison, the lowest evaluated Tender is a Tender from Group C, all Tenders from Group C shall be further compared with the lowest evaluated Tender from Group A after adding to the evaluated price of goods offered in each Tender from Group C, for the purpose of this further comparison only, an amount equal to 15% (fifteen percent) of the respective CIP Tender price for goods to be imported and already imported goods. Both prices shall include unconditional discounts and be corrected for arithmetical errors. If the Tender from Group A is the lowest, it shall be selected for award. If not, the lowest evaluated Tender from Group C shall be selected as per paragraph (e) above."

#### 4. Post-Qualification of Tenderers (ITT 37)

Note for Procuring Entity to be deleted before issuing the tender documents.

This STD for Procurement of Goods assumes that no Prequalification has taken place before tendering. However, if a Prequalification process is undertaken, the Qualification Criteria stipulated in this Section III, Evaluation and Qualification Criteria must be updated to ensure that the Tenderer and any Sub- Suppliers shall meet or continue to meet the Criteria used at the time of Prequalification.]

#### 4.1 Post-Qualification Criteria (ITT 37.1)

In case the tender <u>was not subject to pre-qualification</u>, the tender that has been determined to be the lowest evaluated tenderer shall be considered for contract award, subject to meeting each of the following conditions (post qualification Criteria applied on a GO/NO GO basis). The Procuring Entity shall carry out the post-qualification of the Tenderer in accordance with ITT 37, using only the requirements specified herein. Requirements not included in the text below shall not be used in the evaluation of the Tenderer's qualifications. The minimum qualification requirements for multiple contracts will be the sum of the minimum requirements for respective individual contracts, unless otherwise specified.

[Note for Procuring Entity to be deleted before issuing the tender documents.

Select requirements (criteria) for post qualification from below as relevant and appropriate for the nature, size and type of Goods and Services to be procured. Generally, for procurement of Goods, unless the value of the item is very large, the criteria for assessment of Manufacturer's technical capability should always be considered more important than its financial resources. For very small value items, the criteria for financial capability may even be omitted].

#### 42 If the Tenderer is a manufacturer

#### a) Financial Capability

i) The Tenderer shall demonstrate that it has access to, or has available, liquid assets, unencumbered real assets, lines of credit, and other financial means (independent of any contractual advance payment) sufficient to meet the supply cash flow of Kenya Shillings

	[or equivalent].
	r I
ii)	Minimum average annual supply turnover of Kenya Shillings[insert
,	amount, specify a figure about 2.5 times the total Tender price)] or equivaler calculated as total certified payments received for contracts of goods manufacture and supplied within the last
	[insert
	number of years). In case of multiple contracts, limitation will be placed on the number of item(s) that will be awarded to the Tenderer.

#### b) Experience and Technical Capacity

The Tenderer shall furnish documentary evidence to demonstrate that it meets the following experience requirement(s) using the form provided in Section IV. In case the Tenderer is a JV, experience and demonstrated technical capacity of only the JV shall be taken into account and not of individual members nor their individual experience/capacity will be aggregated unless all members of the JV have been manufacturing and supplying Goods offered in the Tender to the same technology, processing, design, materials, specifications, model number, etc. in all respects such that Goods manufactured have the same functional characteristics, performance parameters, outputs and other guarantees and fully interchangeable which shall be documented along with other required documents demonstrating capacity to the satisfaction of the Procuring Entity in case individual members claim experience. Otherwise, documents evidencing experience and technical capacity shall be in the name of the JV that submitted the Tender. Wherever the Words "Similar Goods" have

[list the requirement(s), including experience in successfully implementing sustainable procurement requirements, if specified in the tender document.] Samples of Experience Requirements: The shall be manufacturing similar i) Tenderer Goods for the last (spec ify the number of years to cover a sufficiently long period ranging from 2 to 5 years depending upon the Goods to be procured). The Tenderer shall furnish documentary evidence to demonstrate successful completion ii) of at least \_\_\_\_(Insert number) of contracts of similar Goods in the last \_\_\_\_\_ \_ (specify number) each contract costing at least Kenya shillings equivalent and involving a supply of at least\_percentage of required quantity (usually the percentage is about 70-80%) in some cases where Procuring Entity requires deliveries in a scheduled manner over a specified time, include item (iii) below. iii) (Optional) The installed capacity to manufacture number of items (specify the relevant item number) shall not be less than \_units per \_\_ (specify week or month). (Optional) Documentary Evidence of Usage of Goods (When appropriate) The Tenderer shall furnish documentary evidence satisfactory to the Procuring Entity to demonstrate that similar Goods as offered in the Tender have been in successful use or operation for the last years. If the Tenderer is a JV, the evidence of demonstrated usage of Goods supplied in the past shall be in the name of the JV. 43 If Tenderer is a Supplier: If a Tenderer is a Supplier offering the Goods on behalf of or from a Manufacturer under Manufacturer's Authorization Form (Section IV, Tendering Forms), the Manufacturer shall demonstrate the above qualifications 4.2 (b) (i), (ii), and (iii) and the Tenderer shall demonstrate it meets the following criteria. The Tenderer shall demonstrate that it has access to, or has available, liquid assets, unencumbered real assets, lines of credit, and other financial means (independent of any contractual advance payment) sufficient to meet the supply cash flow of Kenya Shillings ii) Minimum annual supply of Kenya Shillings average turnover sert amount] or equivalent calculated as total certified payments received for contracts in progress and/or completed within the last [insert of year] years, divided by [insert number of years] years. Has satisfactorily and substantially completed at least (specify number) contract(s) of a similar nature either within Kenya, the East African Community or abroad, as a prime supplier or a joint venture member, each of a minimum value in Kenya shillings\_\_\_\_\_equivalent. 44 **History of non-performing contracts:** Tenderer (Supplier or/and manufacturer, and each member of JV in case the Tenderer is a JV, shall demonstrate that Non-performance of a contract did not occur as a result of the default of the Tenderer, manufacturer or the member of JV as the case \_(specify years). The may be, in the last required information shall be furnished as per form CON-2].

45

**Pending Litigation** 

been used it includes upgrades, latest and improved versions or models of similar specifications and technology. Refer to Form Exp-1 to provide the required information.

Financial position and prospective long-term profitability of the Single Tenderer, and in the case the Tenderer is a JV, of each member of the JV, shall remain sound according to criteria established with respect to Financial Capability under paragraph I (i) above assuming that all pending litigation will be resolved against the Tenderer. Tenderer shall provide information on pending litigations as per Form CON-2.

#### 4.6. Litigation History

There shall be no consistent history of court/arbitral award decisions against the Tenderer, in the last\_\_\_\_\_\_\_\_\_(specify years). All parties to the contract shall furnish the information on the related Form (CON-2) about any litigation or arbitration resulting from contracts completed or ongoing under its execution over the years specified. A consistent history of awards against the Tenderer or any member of a JV may result in rejection of the tender.

#### **SECTION IV - TENDERING FORMS**

Form of Tender Tenderer Information Form Tenderer JV Members Information Form

Price Schedule: Goods Manufactured Outside Kenya, to be Imported Price Schedule: Goods

Manufactured Outside Kenya, already imported Price Schedule: Goods Manufactured in Kenya

Price and Completion Schedule – Related Services Form of Tender Security – Demand

Guarantee Form of Tender Security (Tender Bond)

Form of Tender-Securing Declaration Manufacturer's Authorization Form

## FORM OF TENDER

## (Amended and issued pursuant to PPRA CIRCULAR No. 02/2022)

INSTR	CUCTIONS TO TENDERERS					
i)						
,	ii) The Tenderer must prepare this Form of Tender on stationery with its letterhead clearly					
showin	howing					
	the Tenderer's complete name and business address. <u>Tenderers are reminded that this is a tour.</u>					
<u>mandai</u>	<u>requirement.</u>					
iii	•					
	DETERMINATION and the SELF DECLARATION FORMS OF THE TENDERER					
	as listed under (s) below.					
Date of	of this Tender submission:[insert date (as day, month and year) of Tender submission]					
Tender	r Name and Identification:[insert identification]					
Altern	ative No.:[insert identification No if this is a Tender for an alternative]					
То:	[Insert complete name of KENYA REVENUE AUTHORITY]					
a)	<b>No reservations:</b> We have examined and have no reservations to the Tendering document, including Addenda issued in accordance with Instructions to tenderers (ITT 7);					
b)	<b>Eligibility</b> : We meet the eligibility requirements and have no conflict of interest in accordance with ITT 3;					
c)	<b>Tender/Proposal-Securing Declaration</b> : We have not been suspended nor declared ineligible by the Procuring Entity based on execution of a Tender-Securing Declaration. Or Proposal-Securing Declaration in Kenya in accordance with ITT 3.6;					
d)	<b>Conformity:</b> We offer to supply in conformity with the Tendering document and in accordance with the Delivery Schedules specified in the Schedule of Requirements the following Goods: [insert a brief description of the Goods and Related Services];					
e)	<b>Tender Price</b> : The total price of our Tender, excluding any discounts offered in item (f) below is:					
	SUPPLY, DELIVERY, INSTALLATION AND COMMISSIONING OF LOCAL AREA NETWORKS (LANs) FOR KRA IDENTIFIED STATIONS:					
	Lot I					
	•••••••••••••••••••••••••••••••••••••••					
	••••••					
Tender in words and figures						
Lot II						
••••••						
	••••••					
	insert the total price of the Tender in words and figures					
	Lot III					

insert the total price of the
Tender in words and figures
Lot IV
•••••••
insert the total price of the
<u>Tender in words and figures</u>
Lot V
••••••
•••••••••••
insert the total price of the
Tender in words and figures

#### OR

Option 2, in case of multiple lots: (a) Total price of each lot [insert the total price of each lot in words and figures, indicating the various amounts and the respective currencies]; and (b) Total price of all lots (sum of all lots) [insert the total price of all lots in words and figures, indicating the various amounts and the respective currencies];

- f) Discounts: The discounts offered and the methodology for their application are:
  - i) The discounts offered are: [Specify in detail each discount offered.]
  - ii) The exact method of calculations to determine the net price after application of discounts are shown below: [Specify in detail the method that shall be used to apply the discounts];
- g) **Tender Validity Period**: Our Tender shall be valid for the period specified in TDS 17.1 (335 **Days**) from the date fixed for the Tender submission deadline specified in TDS 21.1 (as amended, if applicable), and it shall remain binding upon us and may be accepted at any time before the expiration of that period;
- h) **Performance Security**: If our Tender is accepted, we commit to obtain a performance security in accordance with the Tendering document.
- i) One Tender per tenderer: We are not submitting any other Tender(s) as an individual tenderer, and we are not participating in any other Tender(s) as a Joint Venture member, or as a subcontractor, and meet the requirements of ITT 3.9, other than alternative Tenders submitted in accordance with ITT 12;
- j) **Suspension and Debarment**: We, along with any of our subcontractors, suppliers, consultants, manufacturers, or service providers for any part of the contract, are not subject to, and not controlled by any entity or individual that is subject to, a temporary suspension or a debarment imposed by the Procuring Entity. Further, we are not ineligible under the Kenya laws or official regulations or pursuant to a decision of the United Nations Security Council;
- k) **State-owned enterprise or institution**: [select the appropriate **option** and delete the other] [We are not a state-owned enterprise or institution] / [We are a state-owned enterprise or institution

but meet the requirements of ITT 3.7];

1) **Commissions, gratuities, fees:** We have paid, or will pay the following commissions, gratuities, or fees with respect to the Tendering process or execution of the Contract: [insert complete name of each Recipient, its full address, the reason for which each commission or gratuity was paid and the amount and currency of each such commission or gratuity]

Name of Recipient	Address	Reason	Amount

(If none has been paid or is to be paid, indicate "none.")

- m) **Binding Contract**: We understand that this Tender, together with your written acceptance thereof included in your Letter of Acceptance, shall constitute a binding contract between us, until a formal contract is prepared and executed;
- n) **Procuring Entity Not Bound to Accept**: We understand that you are not bound to accept the lowest evaluated cost Tender, the Best Evaluated Tender or any other Tender that you may receive; and
- o) **Fraud and Corruption**: We hereby certify that we have taken steps to ensure that no person acting for us or on our behalf engages in any type of Fraud and Corruption.
- p) **Code of Ethical Conduct**: We undertake to adhere by the Code of Ethics for Persons Participating in Public Procurement and Asset Disposal, copy available from \_\_\_\_\_\_\_(specify website) during the procurement process and the execution of any resulting contract.
- q) Collusive practices: We hereby certify and confirm that the tender is genuine, non-collusive and made with the intention of accepting the contract if awarded. To this effect we have signed the "Certificate of Independent tender Determination" attached below.
- r) **Beneficial Ownership Information:** We commit to provide to the KENYA REVENUE AUTHORITY the Beneficial Ownership Information in conformity with the Beneficial Ownership Disclosure Form upon receipt of notification of intention to enter into a contract in the event we are the successful tenderer in this subject procurement proceeding.
- s) We, the Tenderer, have duly completed, signed and stamped the following Forms as part of our Tender:
  - a) Tenderer's Eligibility; Confidential Business Questionnaire to establish we are not in any conflict to interest;
  - b) Certificate of Independent Tender Determination to declare that we completed the tender without colluding with other tenderers;
  - c) Self-Declaration of the Tenderer to declare that we will, if awarded a contract, not engage in any form of fraud and corruption; and
  - d) Declaration and Commitment to the Code of Ethics for Persons Participating in Public Procurement and Asset Disposal.

Further, we confirm that we have read and understood the full content and scope of fraud and corruption as informed in "Appendix 1- Fraud and Corruption" attached to the Form of Tender.

Name of the tenderer: \*[insert complete name of the tenderer]

Name of the person duly authorized to sign the Tender on behalf of the tenderer: \*\*[insert complete name of person duly authorized to sign the Tender]

Title of the person signing the Tender: [insert complete title of the person signing the Tender]

Signature of the person named above: [insert signature of person whose name and capacity are shown above] Date signed [insert date of signing] day of [insert month], [insert year]

- \*: In the case of the Tender submitted by a Joint Venture specify the name of the Joint Venture as tenderer.
- \*\*: Person signing the Tender shall have the power of attorney given by the tenderer. The power of attorney shall be attached with the Tender Schedules.

#### CERTIFICATE OF INDEPENDENT TENDER DETERMINATION

I, the undersigned, in submitting the accompanying Letter of Tender to the	<u>.</u>	
	[Name	of
Procuring Entity] for:	_[Name	and
number of tender] in response to the request for tenders made by:	[Name	of
Tenderer] do hereby make the following statements that I certify to be true every respect:	e and comple	te in
I certify, on behalf of	[Na	те

- 1. I have read and I understand the contents of this Certificate;
- 2. I understand that the Tender will be disqualified if this Certificate is found not to be true and complete in every respect;
- 3. I am the authorized representative of the Tenderer with authority to sign this Certificate, and to submit the Tender on behalf of the Tenderer;
- 4. For the purposes of this Certificate and the Tender, I understand that the word "competitor" shall include any individual or organization, other than the Tenderer, whether or not affiliated with the Tenderer, who:
  - a) has been requested to submit a Tender in response to this request for tenders;
  - b) could potentially submit a tender in response to this request for tenders, based on their qualifications, abilities or experience;
- 5. The Tenderer discloses that [check one of the following, as applicable]:
  - a) The Tenderer has arrived at the Tender independently from, and without consultation, communication, agreement or arrangement with, any competitor;
  - b) the Tenderer has entered into consultations, communications, agreements or arrangements with one or more competitors regarding this request for tenders, and the Tenderer discloses, in the attached document(s), complete details thereof, including the names of the competitors and the nature of, and reasons for, such consultations, communications, agreements or arrangements;
- 6. In particular, without limiting the generality of paragraphs (5)(a) or (5)(b) above, there has been no consultation, communication, agreement or arrangement with any competitor regarding:
  - a) prices;
  - b) methods, factors or formulas used to calculate prices;
  - c) the intention or decision to submit, or not to submit, a tender; or
  - d) the submission of a tender which does not meet the specifications of the request for Tenders; except as specifically disclosed pursuant to paragraph (5)(b) above;
- 7. In addition, there has been no consultation, communication, agreement or arrangement with any competitor regarding the quality, quantity, specifications or delivery particulars of the works or services to which this request for tenders relates, except as specifically authorized by the procuring authority or as specifically disclosed pursuant to paragraph (5)(b) above;
- 8. the terms of the Tender have not been, and will not be, knowingly disclosed by the Tenderer, directly or indirectly, to any competitor, prior to the date and time of the official tender opening, or of the awarding of the Contract, whichever comes first, unless otherwise required by law or as specifically disclosed pursuant to paragraph (5)(b) above.

Name			
Title			
Date			

[Name, title and signature of authorized agent of Tenderer and Date]

### **SELF-DECLARATION FORMS**

Bidder Official Stamp

#### FORM SD1

SELF DECLARATION THAT THE PERSON/TENDERER IS NOT DEBARRED IN THE MATTER OF THE PUBLIC PROCUREMENT AND ASSET DISPOSAL ACT 2015.

a resi	dent of		
make	a statement as follows:-		
1.	THAT I am the Company Officer/Director of	t of <b>Tender</b> (insert name	nme of the Company) who is No
2.	THAT the aforesaid Bidder, it from participating in procureme		
3.	THAT what is deponed to herei and belief.	n above is true to the best	of my knowledge, information
(Title	)	(Signature)	(Date)

### FORM SD2

# SELF DECLARATION THAT THE PERSON/TENDERER WILL NOT ENGAGE IN ANY CORRUPT OR FRAUDULENT PRACTICE

of	tement as follows:-			
1.	THAT I am the Chief Exof	ect of <b>Tender No</b> title/description) fo	(insert ) or	name of the (insert
2.	THAT the aforesaid Bidder, its serva corrupt or fraudulent practice and h member of the Board, Manage(insert name of the	nas not been reque ement, Staff and	ested to pay any ind/or employees and	nducement to any nd/or agents of
3.	THAT the aforesaid Bidder, its serve inducement to any member of the Boof(name of the part of t	oard, Management,		
4.	THAT the aforesaid Bidder will not other bidders participating in the sub	0 0	ngaged in any corro	sive practice with
5.	THAT what is deponed to herein al and belief.	bove is true to th	ne best of my know	ledge information
	(Title)	(Signature)		(Date)

Bidder's Official Stamp

## DECLARATION AND COMMITMENT TO THE CODE OF ETHICS

(Person) on behalf of (N	lame
of the Business/ Company/Firm)	tions
do hereby commit to abide by the provisions of the Code of Ethics for persons participating Public Procurement and Asset Disposal.	ıg in
Name of Authorized signatory	· • • • • • • • • • • • • • • • • • • •
Sign	
Position	
Office address Telephone	
З-mail	
Name of the Firm/Company	
Date	
Company Seal/ Rubber Stamp where applicable)	
Witness	
Name	
Sign	•••
Oate	

#### **APPENDIX 1- FRAUD AND CORRUPTION**

(Appendix 1 shall not be modified)

#### 1. Purpose

1.1 The Government of Kenya's Anti-Corruption and Economic Crime laws and their sanction's policies and procedures, Public Procurement and Asset Disposal Act (no. 33 of 2015) and its Regulation, and any other Kenya's Acts or Regulations related to Fraud and Corruption, and similar offences, shall apply with respect to Public Procurement Processes and Contracts that are governed by the laws of Kenya.

#### 2. Requirements

- 2.1 The Government of Kenya requires that all parties including Procuring Entities, Tenderers, (applicants/proposers), Consultants, Contractors and Suppliers; any Subcontractors, Sub-consultants, Service providers or Suppliers; any Agents (whether declared or not); and any of their Personnel, involved and engaged in procurement under Kenya's Laws and Regulation, observe the highest standard of ethics during the procurement process, selection and contract execution of all contracts, and refrain from Fraud and Corruption and fully comply with Kenya's laws and Regulations as per paragraphs 1.1 above.
- 22 Kenya's public procurement and asset disposal act (no. 33 of 2015) under Section 66 describes rules to be followed and actions to be taken in dealing with Corrupt, Coercive, Obstructive, Collusive or Fraudulent practices, and Conflicts of Interest in procurement including consequences for offences committed. A few of the provisions noted below highlight Kenya's policy of no tolerance for such practices and behavior:
  - 1) a person to whom this Act applies shall not be involved in any corrupt, coercive, obstructive, collusive or fraudulent practice; or conflicts of interest in any procurement or asset disposal proceeding;
  - 2) A person referred to under subsection (1) who contravenes the provisions of that sub-section commits an offence;
  - 3) Without limiting the generality of the subsection (1) and (2), the person shall be
    - a) disqualified from entering into a contract for a procurement or asset disposal proceeding; or
    - b) if a contract has already been entered into with the person, the contract shall be voidable:
  - 4) The voiding of a contract by the procuring entity under subsection (7) does not limit any legal remedy the procuring entity may have;
  - 5) An employee or agent of the procuring entity or a member of the Board or committee of the procuring entity who has a conflict of interest with respect to a procurement:
    - a) shall not take part in the procurement proceedings;
    - b) shall not, after a procurement contract has been entered into, take part in any decision relating to the procurement or contract; and
    - c) shall not be a subcontractor for the bidder to whom was awarded contract, or a member of the group of bidders to whom the contract was awarded, but the subcontractor appointed shall meet all the requirements of this Act.
  - 6) An employee, agent or member described in subsection (1) who refrains from doing anything prohibited under that subsection, but for that subsection, would have been within his or her duties shall disclose the conflict of interest to the procuring entity;
  - 7) If a person contravenes subsection (1) with respect to a conflict of interest described in subsection (5)(a) and the contract is awarded to the person or his relative or to another person in whom one of them had a direct or indirect pecuniary interest, the contract shall be terminated and all costs incurred by the public entity shall be made good by the awarding officer. Etc.

- In compliance with Kenya's laws, regulations and policies mentioned above, the Procuring Entity:
  - a) Defines broadly, for the purposes of the above provisions, the terms set forth below as follows:
    - i) "corrupt practice" is the offering, giving, receiving, or soliciting, directly or indirectly, of anything of value to influence improperly the actions of another party;
    - ii) "fraudulent practice" is any act or omission, including misrepresentation, that knowingly or recklessly misleads, or attempts to mislead, a party to obtain financial or other benefit or to avoid an obligation;
    - iii) "collusive practice" is an arrangement between two or more parties designed to achieve an improper purpose, including to influence improperly the actions of another party;
    - iv) "coercive practice" is impairing or harming, or threatening to impair or harm, directly or indirectly, any party or the property of the party to influence improperly the actions of a party;
    - v) "obstructive practice" is:
      - deliberately destroying, falsifying, altering, or concealing of evidence material to the investigation or making false statements to investigators in order to materially impede investigation by Public Procurement Regulatory Authority (PPRA) or any other appropriate authority appointed by Government of Kenya into allegations of a corrupt, fraudulent, coercive, or collusive practice; and/or threatening, harassing, or intimidating any party to prevent it from disclosing its knowledge of matters relevant to the investigation or from pursuing the investigation; or
      - acts intended to materially impede the exercise of the PPRA's or the appointed authority's inspection and audit rights provided for under paragraph 2.3 e. below.
  - b) Defines more specifically, in accordance with the above procurement Act provisions set forth for fraudulent and collusive practices as follows:
    - "fraudulent practice" includes a misrepresentation of fact in order to influence a procurement or disposal process or the exercise of a contract to the detriment of the procuring entity or the tenderer or the contractor, and includes collusive practices amongst tenderers prior to or after tender submission designed to establish tender prices at artificial non-competitive levels and to deprive the procuring entity of the benefits of free and open competition.
  - c) Rejects a proposal for award¹ of a contract if PPRA determines that the firm or individual recommended for award, any of its personnel, or its agents, or its subconsultants, sub-contractors, service providers, suppliers and/ or their employees, has, directly or indirectly, engaged in corrupt, fraudulent, collusive, coercive, or obstructive practices in competing for the contract in question;
  - d) Pursuant to the Kenya's above stated Acts and Regulations, may sanction or debar or recommend to appropriate authority (ies) for sanctioning and debarment of a firm or individual, as applicable under the Acts and Regulations;
  - e) Requires that a clause be included in Tender documents and Request for Proposal documents requiring (i) Tenderers (applicants/proposers), Consultants, Contractors, and Suppliers, and their Sub-contractors, Sub-consultants, Service providers, Suppliers, Agents personnel, permit the PPRA or any other appropriate authority appointed by Government of Kenya to inspect<sup>2</sup> all accounts, records and other documents relating to the procurement process, selection and/or contract execution,

- and to have them audited by auditors appointed by the PPRA or any other appropriate authority appointed by Government of Kenya; and
- f) Pursuant to Section 62 of the above Act, requires Applicants/Tenderers to submit along with their Applications/Tenders/Proposals a "Self-Declaration Form" as included in the procurement document declaring that they and all parties involved in the procurement process and contract execution have not engaged/will not engage in any corrupt or fraudulent practices.

<sup>&</sup>lt;sup>1</sup>For the avoidance of doubt, a party's ineligibility to be awarded a contract shall include, without limitation, (i) applying for pre-qualification, expressing interest in a consultancy, and tendering, either directly or as a nominated sub-contractor, nominated consultant, nominated manufacturer or supplier, or nominated service provider, in respect of such contract, and (ii) entering into an addendum or amendment introducing a material modification to any existing contract.

Inspections in this context usually are investigative (i.e., forensic) in nature. They involve fact-finding activities undertaken by the Investigating Authority or persons appointed by the Procuring Entity to address specific matters related to investigations/audits, such as evaluating the veracity of an allegation of possible Fraud and Corruption, through the appropriate mechanisms. Such activity includes but is not limited to: accessing and examining a firm's or individual's financial records and information, and making copies thereof as relevant; accessing and examining any other documents, data and information (whether in hard copy or electronic format) deemed relevant for the investigation/audit, and making copies thereof as relevant; interviewing staff and other relevant individuals; performing physical inspections and site visits; and obtaining third party verification of information.

## TENDERER INFORMATION FORM

[The tenderer shall fill in this Form in accordance with the instructions indicated below. No alterations to its format shall be permitted and no substitutions shall be accepted.]
Date: [insert date (as day, month and year) of Tendersubmission]
Tender Name and Identification: [Insert identification
Alternative No.: [insert identification No if this is a Tender for an alternative
Pageofpages
1. Tenderer's Name [insert Tenderer's legal name]
2. In case of JV, legal name of each member: [insert legal name of each member in JV]
3. Tenderer's actual or intended country of registration: [insert actual or intended country of registration]
4. Tenderer's year of registration: [insert Tenderer's year of registration]
5. Tenderer's Address in country of registration: [insert Tenderer's legal address in country of registration]
6. Tenderer's Authorized Representative Information
Name: [insert Authorized Representative's name]
Address: [insert Authorized Representative's Address]
Telephone/Fax numbers: [insert Authorized Representative's telephone/fax numbers]
Email Address: [insert Authorized Representative's email address]
7. Attached are copies of original documents of [check the box(es) of the attached original documents]
☐ For Kenyan Tenderers a current tax clearance certificate or tax exemption certificate issued by the Kenya Revenue Authority in accordance with ITT 3.14.
□Articles of Incorporation (or equivalent documents of constitution or association), and/or documents of registration of the legal entity named above, in accordance with ITT 3.4.
☐ In case of JV, letter of intent to form JV or JV agreement, in accordance with ITT 3.1.
☐ In case of state-owned enterprise or institution, in accordance with ITT 4.6 documents establishing:
(i) Legal and financial autonomy
(ii) Operation under commercial law
(iii) Establishing that the tenderer is not under the supervision of the KENYA REVENUE AUTHORITY
2. Included are the organizational chart and a list of Board of Directors

## TENDERER'S ELIGIBILITY- CONFIDENTIAL BUSINESS QUESTIONNAIRE FORM

#### a) Instruction to Tenderer

Tender is instructed to complete the particulars required in this Form, one form for each entity if Tender is a JV. Tenderer is further reminded that it is an offence to give false information on this Form.

#### A. Tenderer's details

	ITEM	DESCRIPTION
1	Name of the KENYA REVENUE AUTHORITY	
2	Name of the Tenderer	
3	Full Address and Contact Details of the Tenderer.	<ol> <li>Country</li> <li>City</li> <li>Location</li> <li>Building</li> <li>Floor</li> <li>Postal Address</li> <li>Name and email of contact person.</li> </ol>
4	Reference Number of the Tender	
5	Date and Time of Tender Opening	
6	Current Trade License No and Expiring date	
7	Maximum value of business which the Tenderer handles.	
8		

#### **General and Specific Details**

i) Private or public Company \_

ii) State the nominal and issued capital of the Company-

Gei	iiei a	and Specific Details					
b)	S	Sole Proprietor, provide the following details.					
Naı	me in	ı full					
Age	e			Nationality			
Cou	untry	of Origin		Citizenship			
c)	Pa	artnership, provide the fo	ollowing details.				
		Names of Partners	Nationality	Citizenship	% Shares owned		
	1			•			
	2						
	3						
(d)	R	egistered Company, prov	vide the following de	etails.			

Nominal Kenya Shillings (Equivalent)	
Issued Kenya Shillings (Equivalent)	

#### iii) Give details of Directors as follows.

	Names of Director	Nationality	Citizenship	% Shares owned
1				
2				
3				

### (e) DISCLOSURE OF INTEREST- Interest of the Firm in the KENYA REVENUE AUTHORITY.

(i)	Are there any person/persons in	(Name of KENYA	REVENUE	(AUTHORITY)	who
			has an inte	erest or relation	nship
	in this firm? Yes/No				

If yes, provide details as follows.

	Names of Person	Designation in the KENYA REVENUE AUTHORITY	Interest or Relationship with Tenderer
1			
2			
3			

### (ii) Conflict of interest disclosure

	Type of Conflict	Disclosure YES OR NO	If YES provide details of the relationship with Tenderer
1	Tenderer is directly or indirectly controlled by or is under common control with another tenderer.		
2	Tenderer receives or has received any direct or indirect subsidy from another tenderer.		
3	Tenderer has the same legal representative as another tenderer		
4	Tender has a relationship with another tenderer, directly or through common third parties that puts it in a position to influence the tender of another tenderer, or influence the decisions of the KENYA REVENUE AUTHORITY regarding this tendering process.		
5	Any of the Tenderer's affiliates participated as a consultant in the preparation of the design or technical specifications of the works that are the subject of the tender.		

	Type of Conflict	Disclosure YES OR NO	If YES provide details of the relationship with Tenderer
6	Tenderer would be providing goods, works, non-consulting services or consulting services during implementation of the contract specified in this Tender Document.		
7	Tenderer has a close business or family relationship with a professional staff of the KENYA REVENUE AUTHORITY who are directly or indirectly involved in the preparation of the Tender document or specifications of the Contract, and/or the Tender evaluation process of such contract.		
8	Tenderer has a close business or family relationship with a professional staff of the KENYA REVENUE AUTHORITY who would be involved in the implementation or supervision of the Contract.		
9	Has the conflict stemming from such relationship stated in item 7 and 8 above been resolved in a manner acceptable to the KENYA REVENUE AUTHORITY throughout the tendering process and execution of the Contract?		

## (f) Certification

On behalf of the Tenderer, I certify that the information	ation given above is correct.
Full Name	
Title or Designation	
(Signature)	(Date)

#### TENDERER'S JV MEMBERS INFORMATION FORM

The following table shall be filled in for the tenderer and for each member of a Joint Venture]]. Date:.....[insert date (as day, month and year) of Tender submission]. Tender Name and Identification: [insert identification Alternative No:.....[insert identification No if this is a Tender for an alternative]. Page of pages 1. Tenderer's Name: [insert Tenderer's legal name] 2. Tenderer's JV Member's name: [insert JV's Member legal name] 3. Tenderer's JV Member's country of registration: [insert JV's Member country of registration] 4. Tenderer's JV Member's year of registration: [insert JV's Member year of registration] 5. Tenderer's JV Member's legal address in country of registration: [insert JV's Member legal address in country of registration] Tenderer's JV Member's authorized representative information Name: [insert name of JV's Member authorized representative] Address: [insert address of JV's Member authorized representative] Telephone/Fax numbers: [insert telephone/fax numbers of JV's Member authorized representative] Email Address: [insert email address of JV's Member authorized representative] Attached are copies of original documents of [check the box(es) of the attached original documents l Articles of Incorporation (or equivalent documents of constitution or association), and/or registration documents of the legal entity named above, in accordance with ITT 4.4. In case of a state-owned enterprise or institution, documents establishing legal and financial autonomy, operation in accordance with commercial law, and that they are not under the supervision of the KENYA REVENUE AUTHORITY, in accordance with ITT 4.6. Included are the organizational chart and a list of Board of Directors

[The tenderer shall fill in this Form in accordance with the instructions indicated below.

#### PRICE SCHEDULE FORMS

[The tenderer shall fill in these Price Schedule Forms in accordance with the instructions indicated. The list of line items in column 1 of the **Price Schedules** shall coincide with the List of Goods and Related Services specified by the Procuring Entity in the Schedule of Requirements.]

## **DETAILED PRICE SCHEDULES**

This tender is divided into five (5) lots and each lot covers several stations as highlighted below:

LOTS	STATIONS
Lot I	1. Embu
	2. Garissa
	3. Wajir (Main & Airport Offices)
	4. Murang'a
	5. Isiolo DTD
	6. Isiolo Airport
	7. Nyeri
	8. Nanyuki
Lot II	1. Eldoret - Kiptagich House
	2. Eldoret - KPC
	3. Eldoret – Airport (Cargo, Scanner, Terminal & K9 Offices)
	4. Lodwar
	5. Lokichogio
	6. Lokichogio - Airport
	7. Kericho Main Office
	8. Nakuru - Generation House
	9. Nakuru - KPC
Lot III	1. Kisumu - Lake Basin Mall
	2. Kisumu – Forodha House
	3. Kisumu Pipeline, PPO, Airport, Pier
	4. Kisii (DC & Posta Offices)
	5. Bungoma
	6. Kakamega
	7. Siaya
	8. Busia
	9. Malaba
	10.Isebania
Lot IV	1. Lamu TSO
	2. Lamu Airport
	3. Voi
	4. Diani

	5. Kilifi		
	6. Taveta OSBP		
	7. Kwale		
Lot V	1. JKIA -Forodha		
	2. 5th Floor Times Tower		
	3. Namanga		

## **LOT I: PRICE SCHEDULE**

## 1. EMBU PRICE SCHEDULE

	ITEM DESCRIPTION		BIDDER'S RESPONSE	
		QTY	Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
NO	LAN STRUCTURED CABLING MATERIALS			
1.	12 CORES SM FIBRE CABLE (Metres)	130		
2.	MM ODF 12 PORTS WITH ACCESSORIES	3		
3.	MULTI-MODE FIBRE SFP MODULES 1G	4		
4.	MM LC-LC 1M FIBRE PATCH CORDS	6		
5.	MM LC-LC 3M FIBRE PATCH CORDS	2		
6.	CAT 6A UTP CABLE (ROLL)	60		
7.	CAT 6A PATCH PANEL, T568A/B , 48-PORT	7		
8.	CAT 6A PATCH PANEL, T568A/B , 24-PORT	2		
9.	CAT 6A DUAL DATA OUTLETS (RJ45)	144		
10.	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	288		
11.	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	80		
12.	5M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	40		
13.	18U WALL MOUNT CABINET WITH LOCKABLE DOOR	1		
14.	22U FREE STANDING CABINET WITH LOCKABLE DOOR	1		
15.	32U FREE STANDING CABINET WITH LOCKABLE DOOR	1		
16.	75MM X25MM METAL TRUNKS, 2.4M LENGTH	10		
17.	150MM X50 MM PARTITIONED METAL TRUNKS, 2.4M LENGTH	50		

18.	200MM X50 MM PARTITIONED METAL TRUNKS, 2.4M LENGTH	250	
19.	75MM X50 MM CURVED FLOOR PARTITIONED METAL TRUNKS, 2.4M	10	
20.	150MM PEDESTAL TRUNKING	4	
21.	200MM X50 MM PERFORATED CABLE TRAY IN LENGTHS, 2.4M	25	
22.	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	144	
23.	DUAL-GANG BLANK FACEPLATES	16	
24.	2M THREADED RODS (M10)	110	
25.	300MM TRAPEZE HANGER	50	
26.	RAWL BOLTS (M10) PACKET OF 100 PIECES	1	
27.	NUTS WITH WASHERS (M10) PACKET OF 100 PIECES	1	
28.	1.5KVA RACK-MOUNTED UPS	1	
	SUB-TOTAL (MATERIALS)	•	
29.	LABOUR COST		
	NEW LAN INSTALLATION	Lot	
	FIBRE TERMINATION (PER CORE)	24	
	OLD CABLE UNINSTALLATION	Lot	
	OLD TRUNKING UNINSTALLATION	Lot	
	SUB-TOTAL (LABOUR)		
	GRAND TOTAL IN KSHS – VAT INCLUSIV	Æ	

## 2. GARISSA PRICE SCHEDULE

			BIDDER	'S RESPONSE
	ITEM DESCRIPTION	QTY	Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
NO.	LAN STRUCTURED CABLING MATERIALS	S		
1.	CAT 6A UTP CABLE (ROLL)	19		
2.	CAT 6A PATCH PANEL, T568A/B , 48-PORT	2		
3.	CAT 6A DUAL DATA OUTLETS (RJ45)	48		
4.	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	96		
5.	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	45		
6.	32U FREE STANDING CABINET WITH LOCKABLE DOOR	1		
7.	200MM X50 MM PARTITIONED METAL TRUNKS, 2.4M LENGTH	120		

8.	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	48	
	SUB-TOTAL (MATERIALS)		
9.	LABOUR COST		
	NEW LAN INSTALLATION	Lot	
	TRANSFER EQUIPMENT FROM OLD TO NEW CABINET	Lot	
	OLD CABLE UNINSTALLATION	Lot	
	OLD TRUNKING UNINSTALLATION	Lot	
	SUB-TOTAL (LABOUR)		
	GRAND TOTAL IN KSHS – VA	T INCLUSIV	E

## 3. WAJIR (MAIN & AIRPORT OFFICES) PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	Bidder's response	
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
NO.	LAN STRUCTURED CABLING MATI	ERIALS	3	
1	CAT 6A UTP CABLE (ROLL)	7		
2	CAT 6A PATCH PANEL, T568A/B , 24-PORT	2		
3	CAT 6A DUAL DATA OUTLETS (RJ45)	18		
4	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	36		
5	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	20		
6	12U WALL MOUNT CABINET WITH LOCKABLE DOOR	1		
7	18U WALL MOUNT CABINET WITH LOCKABLE DOOR	1		
8	100MM X50 MM PARTITIONED METAL TRUNKS, 2.4M LENGTH	20		
9	200MM X50 MM PARTITIONED METAL TRUNKS, 2.4M LENGTH	30		
10	100MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	6		
11	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	12		
12	200MM DOUBLE GANG SERVICE PLATES/KNOCKOUTS	24		
13	1.5KVA RACK-MOUNTED UPS	2		
	SUB-TOTAL (MATERIALS)			
14	LABOUR COST			
	NEW LAN INSTALLATION	Lot		
	SUB-TOTAL (LABOUR)			
	GRAND TOTAL IN KSHS – VAT INCLUSIVE			

## 4. MURANG'A PRICE SCHEDULE

	ITEM DESCRIPTION	Bidder's response		
		Qty	Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
1.	CAT 6A UTP CABLE (ROLL)	12		
2.	CAT 6A PATCH PANEL, T568A/B, 48-PORT	1		
3.	CAT 6A DUAL DATA OUTLETS	24		
4.	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	48		
5.	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	30		
6.	22U FREE STANDING CABINET WITH LOCKABLE DOOR	1		
7.	200MM X50 MM PARTITIONED METAL TRUNKS IN LENGTHS OF 2.4M	70		
8.	200MM SERVICE PLATES/KNOCKOUTS	24		
9.	LABOUR (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS)	12		
	GRAND TOTAL IN KSHS - VAT inclusive			

## 5. ISIOLO DTD PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDDER'S RESPONSE	
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
1.	12 CORES SM FIBRE CABLE	150		
2.	SM ODF 12 PORTS WITH ACCESSORIES	2		
3.	SINGLE-MODE FIBRE SFP MODULES 1G	2		
4.	SM LC-LC 1M FIBRE PATCH CORDS	2		
5.	CAT 6A UTP CABLE (ROLL)	10		
6.	CAT 6A PATCH PANEL, T568A/B , 48-PORT	2		
7.	CAT 6A PATCH PANEL, T568A/B , 24-PORT	2		
8.	CAT 6A DUAL DATA OUTLETS (RJ45)	64		
9.	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	128		
10.	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	86		
11.	12U WALL MOUNT CABINET WITH LOCKABLE DOOR	1		
12.	32U FREE STANDING CABINET WITH LOCKABLE DOOR	1		
13.	200MM X50 MM PARTITIONED METAL TRUNKS IN LENGTHS OF 2.4M	110		
14.	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	52		
15.	100MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	2		
16.	150MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	11		
17.	200MM DOUBLE GANG SERVICE PLATES/KNOCKOUTS	8		

	ITEM DESCRIPTION	QTY	BIDDER'S RESPONSE	
			Unit Cost (16% VAT Inclusive)	Inclusive)
			- Kshs	- Kshs
18.	1.5KVA RACK-MOUNTED UPS	1		
	SUB-TOTAL (LAN MATERIALS)			
19.	LABOUR COST - NEW LAN INSTALLATION (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS)	LOT		
	SUB-TOTAL (LABOUR)			
	GRAND TOTAL IN KSHS – VAT INCLUSIVE			

## 6. ISIOLO AIRPORT PRICE SCHEDULE

	ITEM DESCRIPTION		BIDDER'S RESPONSE	
		QTY	Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
	LAN STRUCTURED CABLING MATERIAL	_S		
1.	CAT 6A UTP CABLE (ROLL)	1		
2.	CAT 6A PATCH PANEL, T568A/B , 24-PORT	1		
3.	CAT 6A DUAL DATA OUTLETS (RJ45)	6		
4.	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	12		
5.	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	6		
6.	18U WALL MOUNT CABINET WITH LOCKABLE DOOR	1		
7.	100MM X50 MM PARTITIONED METAL TRUNKS, 2.4M LENGTH	10		
8.	100MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	6		
9.	1.5KVA RACK-MOUNTED UPS	1		
	SUB-TOTAL (MATERIALS)			
10.	LABOUR COST			
	NEW LAN INSTALLATION	Lot		
	SUB-TOTAL (LABOUR)			
	GRAND TOTAL IN KSHS – VAT INCLUSIVE			

## 7. NYERI PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDDER'S RESPONSE	
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
1.	12 Cores MM fiber cable (Metres)	280		
2.	MM ODF 12 Ports with Accessories	3		

	ITEM DESCRIPTION	QTY	BIDDER'S RESPONSE		
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs	
3.	MM ODF 24 Ports with Accessories	1			
4.	Multi-mode fiber SFP Modules 1G	6			
5.	MM LC-LC 1M fiber patch cord	6			
6.	Cat 6A UTP cable (Roll)	70			
7.	Cat 6A patch panel, T568A/B , 48-Port	8			
8.	Cat 6A patch panel, T568A/B , 24-Port	3			
9.	Cat 6A dual data outlets (RJ45)	223			
10.	1M Cat 6A UTP modular stranded T568A/B Patch cords	446			
11.	3M Cat 6A UTP modular stranded T568A/B Patch cords	170			
12.	5M Cat 6A UTP modular stranded T568A/B Patch cords	30			
13.	22U Free standing Cabinet with lockable door	2			
14.	32U Free standing Cabinet with lockable door	1			
15.	200mm x50 mm Partitioned Metal trunks, 2.4M Length	484			
16.	200MM Single Gang Service Plates/Knockouts	223			
17.	200mm x 50mm perforated cable tray, 2.4M Length	75			
18.	Rawl Bolts (M10) packet of 100 pcs	4			
19.	300mm Trapeze Hanger	170			
20.	Nuts with washers (M10) packet of 100pcs	4			
21.	1M Threaded rods (M10)	180			
	SUB-TOTAL (LAN MATERIALS)				
22.	LABOUR COST - NEW LAN INSTALLATION (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS FOR BOTH COPPER & FIBRE)	LOT			
	FIBRE TERMINATION (PER CORE)	36			
	SUB-TOTAL (LABOUR)				
	GRAND TOTAL IN KSHS – VAT INCLUSIVE				

## 8. NANYUKI PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDDER'S RESPONSE	
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
1.	CAT 6A UTP CABLE (ROLL)	2		
2.	CAT 6A DUAL DATA OUTLETS	10		
3.	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	14		
4.	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	14		

	ITEM DESCRIPTION	QTY	BIDDER'S RESPONSE	
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
5.	100MM X50 MM PARTITIONED METAL TRUNKS IN LENGTHS OF 2.4M	10		
6.	100MM X50 MM CURVED FLOOR PARTITIONED METAL TRUNKS, 2.4M	5		
7.	100MM SERVICE PLATES/KNOCKOUTS	7		
8.	100MM PEDESTAL TRUNKING	3		
9.	SINGLE-GANG BLANK FACEPLATES	9		
10.	DUAL-GANG BLANK FACEPLATES	12		
11.	LABOUR (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS)	LOT		
	GRAND TOTAL IN KSHS – VAT INCLUSIVE			

## SUMMARY OF PRICE SCHEDULE FOR LOT I

	LOT I PRICE SCHEDULE			
NO.	STATION	GRAND TOTAL IN KSHS – VAT INCLUSIVE FOR EACH STATION (FROM THE TABLES ABOVE)		
1	Embu			
2	Garissa			
3	Wajir (Main & Airport Offices)			
4	Murang'a			
5	Isiolo DTD			
6	Isiolo Airport			
7	Nyeri			
8	Nanyuki			
	GRAND TOTAL COST IN KSHS - VAT INCLUSIVE TO BE CARRIED TO THE FORM OF TENDER FOR LOT I			

## **LOT II: PRICE SCHEDULE**

## 1. ELDORET KIPTAGICH HOUSE PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDDER'S RESPONSE		
			Unit Cost (16% VAT Inclusive) - Kshs		
1.	12 CORES MM FIBRE CABLE (Metres)	886			
2.	MM ODF 12 PORTS WITH ACCESSORIES	9			
3.	MM ODF 48 PORTS WITH ACCESSORIES	1			
4.	MULTI-MODE FIBRE SFP MODULES 1G	18			
5.	MM LC-LC 1M FIBRE PATCH CORDS	15			
6.	MM LC-LC 3M FIBRE PATCH CORDS	3			
7.	CAT 6A UTP CABLE (ROLL)	112			
8.	CAT 6A PATCH PANEL, T568A/B , 48-PORT	14			
9.	CAT 6A PATCH PANEL, T568A/B , 24-PORT	5			
10.	CAT 6A DUAL DATA OUTLETS (RJ45)	378			
11.	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	774			
12.	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	465			
13.	5M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	65			
14.	22U FREE STANDING CABINET WITH LOCKABLE DOOR	7			
15.	32U FREE STANDING CABINET WITH LOCKABLE DOOR	2			
16.	50MM X25 MM METAL TRUNKS, 2.4M LENGTH	48			
17.	200MM X50 MM PARTITIONED METAL TRUNKS, 2.4M LENGTH	674			
18.	100MM X50 MM CURVED FLOOR PARTITIONED METAL TRUNKS, 2.4M LENGTH	21			
19.	100MM PEDESTAL TRUNKING	11			
20.	200MM X50 MM PERFORATED CABLE TRAY, 2.4M LENGTH	28			
21.	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	378			
22.	SINGLE-GANG BLANK FACEPLATES	33			
23.	DUAL-GANG BLANK FACEPLATES	44			
24.	1M THREADED RODS (M10)	118			
25.	300MM TRAPEZE HANGER	68			
26.	RAWL BOLTS (M10) PACKET OF 100 PIECES	2			
27.	NUTS WITH WASHERS (M10) PACKET OF 100 PIECES	2			
28.	1.5KVA RACK-MOUNTED UPS	2			
	SUB-TOTAL (LAN MATERIALS)	•			
29.	LABOUR COST - NEW LAN INSTALLATION (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS FOR BOTH	LOT			

ITEM DESCRIPTION	ITEM DESCRIPTION QTY BIDDER		A'S RESPONSE	
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
COPPER & FIBRE)				
FIBRE TERMINATION (P	PER CORE)	108		
SUB-TOTAL (LABOUR	R)		1	
GRAND TOTAL II	N KSHS – VAT INCLUS	IVE		

## 2. ELDORET KPC PRICE SCHEDULE

	ITEM DESCRIPTION		BIDDER'S RESPONSE	
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
1	CAT 6A UTP CABLE (ROLL)	2		
2	CAT 6A PATCH PANEL, T568A/B , 24-PORT	1		
3	CAT 6A DUAL DATA OUTLETS (RJ45)	12		
4	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	24		
5	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	22		
6	18U WALL MOUNT CABINET WITH LOCKABLE DOOR	1		
7	100MM X50 MM PARTITIONED METAL TRUNKS, 2.4M LENGTH	16		
8	100MM X50 MM PERFORATED CABLE TRAY IN LENGTHS, 2.4M	5		
9	100MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	12		
10	1M THREADED RODS (M10)	24		
11	150MM TRAPEZE HANGER	12		
12	RAWL BOLTS (M10) PACKET OF 100 PIECES	1		
13	NUTS WITH WASHERS (M10) PACKET OF 100 PIECES	1		
14	LABOUR (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS)	LOT		
	GRAND TOTAL IN KSHS – VAT INCLUSIVE			

# 3. ELDORET AIRPORT (CARGO, SCANNER, TERMINAL & K9 OFFICES) PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDDER'S RESPONSE	
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
1	CAT 6A UTP CABLE (ROLL)	4		
2	CAT 6A PATCH PANEL, T568A/B , 24-PORT	3		
3	CAT 6A DUAL DATA OUTLETS (RJ45)	22		
4	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	38		
5	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	32		
6	12U WALL MOUNT CABINET WITH LOCKABLE DOOR	2		
7	22U FREE STANDING CABINET WITH LOCKABLE DOOR	1		
8	50MM X25MM METAL TRUNKS, 2.4M LENGTH	5		
9	100MM X50 MM PARTITIONED METAL TRUNKS, 2.4M LENGTH	24		
10	100MM X50 MM CURVED FLOOR PARTITIONED METAL TRUNKS, 2.4M	3		
11	100MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	19		
12	SINGLE-GANG BLANK FACEPLATES	3		
13	SINGLE GANG PATTRESS BOX	3		
14	NYLON SELF LOCKING CABLE TIES (12 INCHES ) – PACKET OF 100PCS	1		
15	LABOUR (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS)	LOT		

## 4. LODWAR PRICE SCHEDULE

	ITEM DESCRIPTION		BIDDER'S RESPONSE	
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
1.	CAT 6A UTP CABLE (ROLL)	4		
2.	CAT 6A PATCH PANEL, T568A/B , 48-PORT	1		
3.	CAT 6A DUAL DATA OUTLETS (RJ45)	24		
4.	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	48		
5.	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	30		
6.	5M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	5		
7.	32U FREE STANDING CABINET WITH LOCKABLE	1		

	ITEM DESCRIPTION	QTY	BIDDER'S RESPONSE		
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs	
	DOOR				
8.	200MM X50 MM PARTITIONED METAL TRUNKS, 2.4M LENGTH	35			
9.	75MM X50 MM CURVED FLOOR PARTITIONED METAL TRUNKS, 2.4M	4			
10.	100MM PEDESTAL TRUNKING	1			
11.	100MM X50 MM PERFORATED CABLE TRAY IN LENGTHS, 2.4M	10			
12.	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	24			
13.	SINGLE-GANG BLANK FACEPLATES	3			
14.	DUAL-GANG BLANK FACEPLATES	4			
15.	1M THREADED RODS (M10)	44			
16.	150MM TRAPEZE HANGER	24			
17.	RAWL BOLTS (M10) PACKET OF 100 PIECES	1			
18.	NUTS WITH WASHERS (M10) PACKET OF 100 PIECES	1			
	SUB-TOTAL (LAN MATERIALS)				
19.	LABOUR COST				
	NEW LAN INSTALLATION (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS)	LOT			
	OLD CABLE UNINSTALLATION	LOT			
	OLD TRUNKING UNINSTALLATION	LOT			
	SUB-TOTAL (LABOUR)	<u> </u>	1		
	GRAND TOTAL IN KSHS – VAT INCLUSIV	/E			

## 5. LOKICHOGIO PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDDER'S RESPONSE	
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
1.	CAT 6A UTP CABLE (ROLL)	6		
2.	CAT 6A PATCH PANEL, T568A/B , 48-PORT	1		
3.	CAT 6A DUAL DATA OUTLETS (RJ45)	24		
4.	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	48		
5.	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	25		
6.	5M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	5		
7.	18U WALL MOUNT CABINET WITH LOCKABLE DOOR	1		

	ITEM DESCRIPTION	QTY	BIDDER	'S RESPONSE
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
8.	200MM X50 MM PARTITIONED METAL TRUNKS,	25		
	2.4M LENGTH	35		
9.	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	24		
	SUB-TOTAL (LAN MATERIALS)			
10.	LABOUR COST - NEW LAN INSTALLATION (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS)	LOT		
	SUB-TOTAL (LABOUR)			
	GRAND TOTAL IN KSHS – VAT INCLUSIVE	Ī		

# 6. LOKICHOGIO AIRPORT PRICE SCHEDULE

	ITEM DESCRIPTION		BIDDER'S RESPONSE		
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs	
1.	CAT 6A UTP CABLE (ROLL)	1			
2.	CAT 6A PATCH PANEL, T568A/B , 24-PORT	1			
3.	CAT 6A DUAL DATA OUTLETS (RJ45)	6			
4.	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	12			
5.	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	8			
6.	5M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	2			
7.	22U FREE STANDING CABINET WITH LOCKABLE DOOR	1			
8.	100MM X50 MM PARTITIONED METAL TRUNKS, 2.4M LENGTH	7			
9.	100MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	6			
	SUB-TOTAL (LAN MATERIALS)				
10.	LABOUR COST - NEW LAN INSTALLATION (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS)	LOT			
	SUB-TOTAL (LABOUR)				
	GRAND TOTAL (16% VAT inclusive)		1		

### 7. KERICHO MAIN OFFICE PRICE SCHEDULE

	Item Description		Bidder's response				
		Qty	Unit (16% Inclusive - Kshs	VAT	Total VAT II - Kshs	ıclusiv	
1.	12 CORES MM FIBRE CABLE (Metre)	100					
2.	MM ODF 12 PORTS WITH ACCESSORIES	3					
3.	MULTI-MODE FIBRE SFP MODULES 1G	4					
4.	MM SC-LC 1.5M FIBRE PATCH CORDS	4					
5.	CAT 6A UTP CABLE (ROLL)	5					
6.	CAT 6A PATCH PANEL, T568A/B , 24-PORT	3					
7.	CAT 6A DUAL DATA OUTLETS (RJ45)	20					
8.	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	40					
9.	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	40					
10.	5M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	40					
11.	22U FREE STANDING CABINET WITH LOCKABLE DOOR	3					
12.	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	20					
13.	1.5KVA RACK-MOUNTED UPS	2					
14.	LABOUR (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS)	LOT					
	GRAND TOTAL IN KSHS – VAT INCLUSIVE						

### 8. NAKURU GENERATION HOUSE PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDDER'S RESPONSE		
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs	
1.	12 CORES MM FIBRE CABLE (Metres)	625			
2.	MM ODF 12 PORTS WITH ACCESSORIES	5			
3.	MM ODF 24 PORTS WITH ACCESSORIES	1			
4.	MULTI-MODE FIBRE SFP MODULES 1G	12			
5.	MM LC-LC 1M FIBRE PATCH CORDS	12			
6.	CAT 6A UTP CABLE (ROLL)	93			
7.	CAT 6A PATCH PANEL, T568A/B , 48-PORT	12			
8.	CAT 6A PATCH PANEL, T568A/B , 24-PORT	4			
9.	CAT 6A DUAL DATA OUTLETS (RJ45)	303			
10.	1M Cat 6A UTP MODULAR STRANDED T568A/B				
	PATCH CORDS	606			
11.	3M CAT 6A UTP MODULAR STRANDED T568A/B				
	PATCH CORDS	275			

	ITEM DESCRIPTION		BIDDER	DER'S RESPONSE		
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs		
12.	5M CAT 6A UTP MODULAR STRANDED T568A/B					
	PATCH CORDS	50				
13.	22U FREE STANDING CABINET WITH LOCKABLE					
1.1	DOOR	4				
14.	32U FREE STANDING CABINET WITH LOCKABLE DOOR	1				
15.	200MM X50 MM PARTITIONED METAL TRUNKS IN LENGTHS OF 2.4 METERS	481				
16.	100MM X50 MM CURVED FLOOR PARTITIONED					
	METAL TRUNKS, 2.4M	18				
17.	100MM PEDESTAL TRUNKING	5				
18.	200MM X50 MM PERFORATED CABLE TRAY IN LENGTHS, 2.4M	44				
19.	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	303				
20.	200MM DOUBLE GANG SERVICE PLATES/KNOCKOUTS	74				
21.	SINGLE-GANG BLANK FACEPLATES	10				
22.	DUAL-GANG BLANK FACEPLATES	20				
23.	1M THREADED RODS (M10)	192				
24.	300MM TRAPEZE HANGER	96				
25.	RAWL BOLTS (M10) PACKET OF 100 PIECES	2				
26.	NUTS WITH WASHERS (M10) PACKET OF 100 PIECES	2				
	SUB-TOTAL (LAN MATERIALS)					
27.	LABOUR COST					
	NEW LAN INSTALLATION (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS FOR BOTH COPPER & FIBRE)	Lot				
	FIBRE TERMINATION (PER CORE)	48				
	SUB-TOTAL (LABOUR)					
	GRAND TOTAL IN KSHS – VAT INCLUSIVE					

# 9. NAKURU KPC PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDDER'S RESPONSE	
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
1.	CAT 6A UTP CABLE (ROLL)	2		
2.	CAT 6A PATCH PANEL, T568A/B , 24-PORT	1		
3.	CAT 6A DUAL DATA OUTLETS (RJ45)	12		

	ITEM DESCRIPTION	QTY	BIDDER'S RESPONSE		
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs	
4.	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	24			
5.	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	12			
6.	18U WALL MOUNT CABINET WITH LOCKABLE DOOR	1			
7.	200MM X50 MM PARTITIONED METAL TRUNKS, 2.4M LENGTH	5			
8.	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	12			
	SUB-TOTAL (LAN MATERIALS)				
9.	LABOUR COST - NEW LAN INSTALLATION (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS)	LOT			
	SUB-TOTAL (LABOUR)				
	GRAND TOTAL IN KSHS – VAT INCLUSIVE	I	1		

### SUMMARY OF PRICE SCHEDULE FOR LOT II

	LOT II PRICE SCHEDULE				
NO.	STATION	GRAND TOTAL IN KSHS – VAT INCLUSIVE FOR EACH STATION (FROM THE TABLES ABOVE)			
1	Eldoret - Kiptagich House				
2	Eldoret - KPC				
3	Eldoret – Airport (Cargo, Scanner, Terminal & K9 Offices)				
4	Lodwar				
5	Lokichogio				
6	Lokichogio - Airport				
7	Kericho Main Office				
8	Nakuru - Generation House				
9	Nakuru - KPC				
	GRAND TOTAL IN KSHS – VAT INCLUSIVE TO BE CARRIED TO THE FORM OF TENDER FOR LOT II				

# **LOT III: PRICE SCHEDULE**

### 1. KISUMU LAKE BASIN MALL PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDDE	R'S RESPONSE
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
1	MM ODF 12 PORTS WITH ACCESSORIES	2		
2	MULTI-MODE FIBRE SFP MODULES 1G	8		
3	MM SC-LC 1.5M FIBRE PATCH CORDS	8		
4	CAT 6A UTP CABLE (ROLL)	25		
5	CAT 6A PATCH PANEL, T568A/B , 48-PORT	6		
6	CAT 6A PATCH PANEL, T568A/B , 24-PORT	1		
7	CAT 6A DOUBLE OUTLET MODULES(RJ45)	50		
8	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	100		
9	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	50		
	SUB-TOTAL (LAN MATERIALS)			
10	LABOUR COST - NEW LAN INSTALLATION (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS)	LOT		
	SUB-TOTAL (LABOUR)			
	GRAND TOTAL IN KSHS – VAT INCLUS	IVE		

### 2. KISUMU FORODHA HOUSE PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDDER'S RESPONSE		
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs	
1	CAT 6A UTP CABLE (ROLL)	13			
2	CAT 6A UTP CABLE (ROLL) OUTDOOR	1			
3	CAT 6A PATCH PANEL, T568A/B , 48-PORT	2			
4	CAT 6A PATCH PANEL, T568A/B , 24-PORT	1			
5	CAT 6A DOUBLE OUTLET MODULES(RJ45)	50			
6	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	100			
7	12U WALL MOUNT CABINET WITH LOCKABLE DOOR	1			
8	200MM X50 MM PARTITIONED METAL TRUNKS IN LENGTHS OF 2.4M	20			
9	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	50			

	SUB-TOTAL (LAN MATERIALS)			
	LABOUR (INCLUDING LAN SCHEMATIC DRAWINGS &			
10	FLUKE TESTS)	LOT		
	SUB-TOTAL (LABOUR)			
	GRAND TOTAL IN KSHS – VAT INCLUSIVE			

# ${\bf 3.}\ \ KISUMU\ PIPELINE,\ PPO,\ AIRPORT,\ PIER\ PRICE\ SCHEDULE$

	ITEM DESCRIPTION	QTY	BIDDER'S RESPONSE		
			Unit Cost (16% VAT Inclusive) - Kshs	Unit Cost (16% VAT Inclusive) - Kshs	
1	CAT 6A UTP CABLE (ROLL)	16			
2	CAT 6A UTP CABLE (ROLL) OUTDOOR	1			
3	CAT 6A PATCH PANEL, T568A/B , 24-PORT	4			
4	CAT 6A DUAL DATA OUTLETS (RJ45)	42			
5	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	84			
6	12U WALL MOUNT CABINET WITH LOCKABLE DOOR	2			
7	22U FREE STANDING CABINET WITH LOCKABLE DOOR	2			
8	200MM X50 MM PARTITIONED METAL TRUNKS, 2.4M LENGTH	37			
9	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	54			
10	1.5KVA RACK-MOUNTED UPS	2			
	SUB-TOTAL (LAN MATERIALS)				
11	LABOUR (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS)	LOT			
	SUB-TOTAL (LABOUR)	_			
	GRAND TOTAL IN KSHS – VAT INCLUSIVE				

# 4. KISII (DC & POSTA OFFICES) PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDDER	'S RESPONSE
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
1	12 CORES MM FIBRE CABLE (Metres)	50		
2	MM ODF 12 PORTS WITH ACCESSORIES	2		
3	MULTI-MODE FIBRE SFP MODULES 1G	4		

	ITEM DESCRIPTION	QTY	BIDDER	L'S RESPONSE
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
4	MM SC-LC 1.5M FIBRE PATCH CORDS	4		
5	CAT 6A UTP CABLE (ROLL) OUTDOOR	1		
6	CAT 6A UTP CABLE (ROLL)	16		
7	CAT 6A PATCH PANEL, T568A/B , 48-PORT	2		
8	CAT 6A PATCH PANEL, T568A/B , 24-PORT	2		
9	CAT 6A DUAL DATA OUTLETS	52		
10	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	104		
11	200MM X50 MM PARTITIONED METAL TRUNKS IN LENGTHS OF 2.4M	115		
12	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	52		
13	22U FREE STANDING CABINET WITH LOCKABLE DOOR	2		
14	12U FREE STANDING CABINET WITH LOCKABLE DOOR	1		
	SUB-TOTAL (LAN MATERIALS)			
15	LABOUR (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS FOR BOTH COPPER & FIBRE)	LOT		
	SUB-TOTAL (LABOUR)			
	GRAND TOTAL IN KSHS – VAT INCLUSIVE			

5. BUNGOMA PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDDER	R'S RESPONSE
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
1	12 CORES MM FIBRE CABLE (Metres)	30		
2	MM ODF 12 PORTS WITH ACCESSORIES	2		
3	MULTI-MODE FIBRE SFP MODULES 1G	4		
4	MM SC-LC 1.5M FIBRE PATCH CORDS	4		
5	CAT 6A UTP CABLE (ROLL)	23		
6	CAT 6A PATCH PANEL, T568A/B , 48-PORT	1		
7	CAT 6A PATCH PANEL, T568A/B , 24-PORT	2		
8	CAT 6A DOUBLE OUTLET MODULES(RJ45)	48		
9	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	96		
10	200MM X50 MM PARTITIONED METAL TRUNKS IN LENGTHS OF 2.4M	44		
11	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	48		
12	22U FREE STANDING CABINET WITH LOCKABLE DOOR	1		
13	12U WALL MOUNT CABINET WITH LOCKABLE DOOR	1		
	SUB-TOTAL (LAN MATERIALS)			
14	LABOUR (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS FOR BOTH COPPER & FIBRE)	LOT		
	SUB-TOTAL (LABOUR)			
	GRAND TOTAL IN KSHS – VAT INCLUS	IVE		

### 6. KAKAMEGA PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDDEI	R'S RESPONSE
			Unit Cost (16% VAT Inclusive) - Kshs	Total Price 16% Vat (Inclusive) - Kshs
1	12 CORES MM FIBRE CABLE (Metres)	30		
2	MM ODF 12 PORTS WITH ACCESSORIES	2		
3	MULTI-MODE FIBRE SFP MODULES 1G	4		
4	MM SC-LC 1.5M FIBRE PATCH CORDS	4		
5	CAT 6A UTP CABLE (ROLL)	20		
6	CAT 6A PATCH PANEL, T568A/B , 48-PORT	1		
7	CAT 6A PATCH PANEL, T568A/B , 24-PORT	2		
8	CAT 6A DOUBLE OUTLET MODULES(RJ45)	48		
9	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	96		
10	200MM X50 MM PARTITIONED METAL TRUNKS IN LENGTHS OF 2.4M	54		
11	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	48		
12	22U FREE STANDING CABINET WITH LOCKABLE DOOR	1		
13	12U WALL MOUNT CABINET WITH LOCKABLE DOOR	1		
	SUB-TOTAL (LAN MATERIALS)			
14	LABOUR (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS FOR BOTH COPPER & FIBRE)	LOT		
	SUB-TOTAL (LABOUR)			
	GRAND TOTAL IN KSHS – VAT INCLUS	IVE		

# 7. SIAYA PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDDER'S RESPONSE	
			Unit Cost (16% VAT Inclusive) - Kshs	Total Price 16% Vat (Inclusive) - Kshs
1	12 CORES MM FIBRE CABLE (Metres)	50		
2	MM ODF 12 PORTS WITH ACCESSORIES	2		
3	MULTI-MODE FIBRE SFP MODULES 1G	4		
4	MM SC-LC 1.5M FIBRE PATCH CORDS	4		
5	CAT 6A UTP CABLE (ROLL)	15		
6	CAT 6A PATCH PANEL, T568A/B , 24-PORT	2		
7	CAT 6A DOUBLE OUTLET MODULES(RJ45)	24		
8	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	48		
9	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	10		

10	22U FREE STANDING CABINET WITH LOCKABLE DOOR	2		
	200MM X50 MM PARTITIONED METAL TRUNKS IN			
11	LENGTHS OF 2.4M	50		
12	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	24		
13	1.5KVA RACK-MOUNTED UPS	1		
	LABOUR (INCLUDING LAN SCHEMATIC DRAWINGS &			
14	FLUKE TESTS FOR BOTH COPPER & FIBRE)	LOT		
	GRAND TOTAL IN KSHS – VAT INCLUSIVE			

### 8. BUSIA PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDDER'S RESPONSE	
NO.			Unit Cost (16% VAT Inclusive) - Kshs	Total Price 16% Vat (Inclusive) - Kshs
1	12 CORES MM FIBRE CABLE (Metres)	50		
2	MM ODF 12 PORTS WITH ACCESSORIES	2		
3	MULTI-MODE FIBRE SFP MODULES 1G	4		
4	MM SC-LC 1.5M FIBRE PATCH CORDS	4		
5	CAT 6A UTP CABLE (ROLL)	20		
6	CAT 6A PATCH PANEL, T568A/B , 48-PORT	1		
7	CAT 6A PATCH PANEL, T568A/B , 24-PORT	2		
8	CAT 6A DOUBLE OUTLET MODULES(RJ45)	50		
9	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	100		
10	200MM X50 MM PARTITIONED METAL TRUNKS IN LENGTHS OF 2.4M	10		
11	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	50		
12	100MM X50 MM CURVED FLOOR PARTITIONED METAL TRUNKS, 2.4M	5		
13	100MM PEDESTAL TRUNKING	2		
	SUB-TOTAL (LAN MATERIALS)	1		
14	LABOUR (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS FOR BOTH COPPER & FIBRE)	LOT		
	SUB-TOTAL (LABOUR)			
	<b>GRAND TOTAL IN KSHS – VAT INCL</b>	USIV	E	

### 9. MALABA PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDDER	'S RESPONSE
			Unit Cost (16% VAT Inclusive) - Kshs	Total Price 16% Vat (Inclusive) - Kshs
1	12 CORES MM FIBRE CABLE	30		
2	MM ODF 12 PORTS WITH ACCESSORIES	2		
3	MULTI-MODE FIBRE SFP MODULES 1G	4		
4	MM SC-LC 1.5M FIBRE PATCH CORDS	4		

5	CAT 6A UTP CABLE (ROLL)	20		
6	CAT 6A PATCH PANEL, T568A/B , 48-PORT	1		
7	CAT 6A PATCH PANEL, T568A/B , 24-PORT	2		
8	CAT 6A DOUBLE OUTLET MODULES(RJ45)	50		
9	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	100		
10	200MM X50 MM PARTITIONED METAL TRUNKS IN LENGTHS OF 2.4M	10		
11	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	50		
12	100MM X50 MM CURVED FLOOR PARTITIONED METAL TRUNKS, 2.4M	4		
13	100MM PEDESTAL TRUNKING	1		
14	SINGLE GANG BLANK FACEPLATES	3		
15	DOUBLE GANG BLANK FACEPLATES	4		
16	LABOUR (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS FOR BOTH COPPER & FIBRE)	LOT		
	GRAND TOTAL IN KSHS – VAT INCLUSIVE			

### 10. ISEBANIA PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDDER	A'S RESPONSE
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
1	CAT 6A UTP CABLE (ROLL)	15		
2	CAT 6A PATCH PANEL, T568A/B , 24-PORT	2		
3	CAT 6A DOUBLE OUTLET MODULES(RJ45)	24		
4	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	48		
5	200MM X50 MM PARTITIONED METAL TRUNKS IN LENGTHS OF 2.4M	20		
6	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	24		
7	100MM X50 MM CURVED FLOOR PARTITIONED METAL TRUNKS, 2.4M	14		
8	22U FREE STANDING CABINET WITH LOCKABLE DOOR SUB-TOTAL (LAN MATERIALS)	1		
9	LABOUR (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS)	LOT		
	SUB-TOTAL (LABOUR)			
	GRAND TOTAL IN KSHS – VAT INCLUSIVE			

### SUMMARY OF PRICE SCHEDULE FOR LOT III

	LOT III PRICE SCHEDULE				
STATION INCLUSIVE FOR EACH		GRAND TOTAL IN KSHS – VAT INCLUSIVE FOR EACH STATION (FROM THE TABLES ABOVE)			
1	Kisumu - Lake Basin Mall				
2	Kisumu – Forodha House				

3	Kisumu Pipeline, PPO, Airport, Pier	
4	Kisii (DC & Posta Offices)	
5	Bungoma	
6	Kakamega	
7	Siaya	
8	Busia	
9	Malaba	
10	Isebania	
	GRAND TOTAL IN KSHS – VAT INCLUSIVE TO BE CARRIED TO THE FORM OF TENDER FOR LOT III	

# **LOT IV: PRICE SCHEDULE**

### 1. LAMU TSO PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDDER'S RESPONSE	
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
1.	CAT 6A UTP CABLE (ROLL) OUTDOOR	12		
2.	CAT 6A PATCH PANEL, T568A/B , 48-PORT	1		
3.	CAT 6A PATCH PANEL, T568A/B , 24-PORT	1		
4.	CAT 6A DUAL DATA OUTLETS (RJ45)	36		
5.	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	72		
6.	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	36		
7.	32U FREE STANDING CABINET WITH LOCKABLE DOOR	1		
8.	200MM X50 MM PARTITIONED METAL TRUNKS IN LENGTHS OF 2.4M	100		
9.	200MM SERVICE PLATES/KNOCKOUTS	36		
10.	1.5KVA RACK-MOUNTED UPS	1		
	SUB-TOTAL (LAN MATERIALS)			
11.	LABOUR (INCLUDING LAN SCHEMATIC DRAWING & FLUKE TESTS)	LOT		
	GRAND TOTAL IN KSHS – VAT INCLUSIVI	E		

### 2. LAMU AIRPORT PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDDER'	S RESPONSE
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
1.	CAT 6A UTP CABLE (ROLL)	1		
2.	CAT 6A PATCH PANEL, T568A/B , 24-PORT	1		

3.	CAT 6A DUAL DATA OUTLETS (RJ45)	6	
4.	1M CAT 6A UTP MODULAR STRANDED	12	
	T568A/B PATCH CORDS	12	
5.	3M CAT 6A UTP MODULAR STRANDED	8	
	T568A/B PATCH CORDS	0	
6.	12U WALL MOUNT CABINET WITH LOCKABLE	1	
	DOOR		
7.	100MM X50 MM PARTITIONED METAL	10	
	TRUNKS, 2.4M LENGTH	10	
8.	100MM SINGLE GANG SERVICE	6	
	PLATES/KNOCKOUTS		
9.	100MM DOUBLE GANG SERVICE	4	
	PLATES/KNOCKOUTS	_	
10.	1.5KVA RACK-MOUNTED UPS	1	
	CLID TOTAL (LANIMATERIALS)		
	SUB-TOTAL (LAN MATERIALS)		
11.	LABOUR (INCLUDING LAN SCHEMATIC	LOT	
	DRAWING & FLUKE TESTS)		
	GRAND TOTAL IN KSHS – VAT		
	INCLUSIVE		

# 3. VOI PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDDER	'S RESPONSE
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
1.	CAT 6A UTP CABLE (ROLL)	15		
2.	CAT 6A PATCH PANEL, T568A/B , 48-PORT	2		
3.	CAT 6A DUAL DATA OUTLETS (RJ45)	48		
4.	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	96		
5.	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	46		
6.	5M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	46		
7.	32U FREE STANDING CABINET WITH LOCKABLE DOOR	1		
8.	100MM X50 MM PARTITIONED METAL TRUNKS, 2.4M LENGTH	15		
9.	250MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	48		
10.	250MM DOUBLE GANG SERVICE PLATES/ KNOCKOUTS	25		
	SUB-TOTAL (MATERIALS)			
10.	LABOUR			
	NEW LAN INSTALLATION (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS)	LOT		
	OLD CABLE UNINSTALLATION	LOT		
	OLD TRUNKING UNINSTALLATION	LOT		
_	SUB-TOTAL (LABOUR)			

ITEM DESCRIPTION	QTY	BIDDER	S RESPONSE
		Unit Cost (16% VAT Inclusive)	Total Cost (16% VAT Inclusive)
		- Kshs	- Kshs
GRAND TOTAL IN KSHS - INCLUSIVE OF VAT			

**NB**: KRA will provide **65 pieces** of 250mmx50mm partitioned trunkings, and bidders are expected to include the installation cost of associated accessories. Additionally, a sample of the sleeves required for installing the trunkings will be made available for reference.

# 4. DIANI PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDDER'S RESPONSE	
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
1.	12 CORES MM FIBRE CABLE (Metres)	60		
2.	MM ODF 12 PORTS WITH ACCESSORIES	2		
3.	MM ODF 24 PORTS WITH ACCESSORIES	1		
4.	MULTI-MODE FIBRE SFP MODULES 1G	5		
5.	MM SC-LC 1.5M FIBRE PATCH CORDS	6		
6.	CAT 6A UTP CABLE (ROLL)	8		
7.	CAT 6A PATCH PANEL, T568A/B , 48-PORT	1		
8.	CAT 6A PATCH PANEL, T568A/B , 24-PORT	3		
9.	CAT 6A SINGLE DATA OUTLETS (RJ45)	60		
10.	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	120		
11.	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	57		
12.	5M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	57		
13.	12U WALL MOUNT CABINET WITH LOCKABLE DOOR	2		
14.	32U FREE STANDING CABINET WITH LOCKABLE DOOR	1		
15.	200MM X50 MM PARTITIONED METAL TRUNKS, 2.4M LENGTH	85		
16.	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	60		
17.	1.5KVA RACK-MOUNTED UPS	1		
	SUB-TOTAL (MATERIALS)			
16.	LABOUR			
	NEW LAN INSTALLATION (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS)	LOT		
	FIBRE TERMINATION (PER CORE)	24		
	OLD CABLE UNINSTALLATION	LOT		
	OLD TRUNKING UNINSTALLATION	LOT		
	SUB-TOTAL (LABOUR)			
	GRAND TOTAL IN KSHS – VAT INCLUSIVE			

# 5. KILIFI PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDD	ER'S RESPONSE
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
1.	CAT 6A UTP CABLE (ROLL)	2		
2.	CAT 6A PATCH PANEL, T568A/B , 48-PORT	1		
3.	CAT 6A DUAL DATA OUTLETS	24		
4.	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	48		
5.	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	36		
6.	5M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	12		
7.	32U FREE STANDING CABINET WITH LOCKABLE DOOR	1		
8.	200MM X50 MM PARTITIONED METAL TRUNKS IN LENGTHS OF 2.4M	40		
9.	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	24		
10	1.5 KVA RACK-MOUNTED UPS	1		
	SUB-TOTAL (LAN MATERIALS)			
11	LABOUR COST (INCLUDING LAN SCHEMATIC DRAWING & FLUKE TESTS)	LOT		
	GRAND TOTAL IN KSHS – VAT INCI	LUSIVI	<u> </u>	

### 6. TAVETA OSBP PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDDER	L'S RESPONSE
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
1.	12 CORES MM FIBRE CABLE (Metres)	150		
2.	MM ODF 12 PORTS WITH ACCESSORIES	1		
3.	MULTI-MODE FIBRE SFP MODULES 1G	2		
4.	MM SC-LC 1.5M FIBRE PATCH CORDS	2		
5.	CAT 6A UTP CABLE (ROLL)	30		
6.	CAT 6A PATCH PANEL, T568A/B , 48-PORT	5		
7.	CAT 6A PATCH PANEL, T568A/B , 24-PORT	2		
8.	CAT 6A DUAL DATA OUTLETS (RJ45)	120		
9.	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	240		
10.	3M CAT 6A UTP MODULAR STRANDED T568A/B	80		
	PATCH CORDS			
11.	5M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	40		
	TATOTICORDS			

	ITEM DESCRIPTION	QTY	BIDDER'S RESPONSE	
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
12.	32U FREE STANDING CABINET WITH LOCKABLE DOOR	3		
13.	100MM X50 MM PARTITIONED METAL TRUNKS, 2.4M LENGTH	18		
14.	200MM X50 MM PERFORATED CABLE TRAY IN LENGTHS, 2.4M	42		
15.	250MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	120		
16.	2M THREADED RODS (M10)	148		
17.	300MM TRAPEZE HANGER	74		
18.	RAWL BOLTS (M10) PACKET OF 100 PIECES	2		
19.	NUTS WITH WASHERS (M10) PACKET OF 100 PIECES	2		
	SUB-TOTAL (MATERIALS)			
20.	LABOUR			
	NEW LAN INSTALLATION (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS FOR BOTH COPPER & FIBER)	LOT		
	FIBRE TERMINATION (PER CORE)	24		
	OLD CABLE UNINSTALLATION	LOT		
	OLD TRUNKING UNINSTALLATION	LOT		
	SUB-TOTAL (LABOUR)			
	GRAND TOTAL IN KSHS – VAT INCLUSIVE			

**NB**: KRA will provide **250 pieces** of 250mmx50mm partitioned trunkings, and bidders are expected to include the installation cost of associated accessories. Additionally, a sample of the sleeves required for installing the trunkings will be made available for reference.

### 7. KWALE PRICE SCHEDULE

	ITEM DESCRIPTION	QTY	BIDDER	R'S RESPONSE
			Unit Cost (16% VAT Inclusive) - Kshs	Total Cost (16% VAT Inclusive) - Kshs
1.	CAT 6A UTP CABLE (ROLL)	1		
2.	CAT 6A PATCH PANEL, T568A/B , 24-PORT	1		
3.	CAT 6A DUAL DATA OUTLETS (RJ45)	7		
4.	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	14		
5.	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	14		
6.	22U FREE STANDING CABINET WITH LOCKABLE DOOR	1		
7.	100MM X50 MM PARTITIONED METAL TRUNKS IN LENGTHS OF 2.4M	15		
8.	100MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	7		
9.	1.5KVA RACK-MOUNTED UPS	1		
10.	LABOUR (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS)	LOT		

ITEM DESCRIPTION	QTY	BIDDER	R'S RESPONSE
			Total Cost (16% VAT
		VAT Inclusive) - Kshs	Inclusive) - Kshs
GRAND TOTAL IN KSHS – VAT INCLUSIVE			

### SUMMARY OF PRICE SCHEDULE FOR LOT IV

	LOT IV PRICE SCHEDULE				
NO.	STATION	GRAND TOTAL IN KSHS – VAT INCLUSIVE FOR EACH STATION (FROM THE TABLES ABOVE)			
1	Lamu TSO				
2	Lamu Airport				
3	Voi				
4	Diani				
5	Kilifi				
6	Taveta OSBP				
7	Kwale				
	GRAND TOTAL IN KSHS – VAT INCLUSIVE TO BE CARRIED TO THE FORM OF TENDER FOR LOT IV				

# **LOT V: PRICE SCHEDULE**

### 1. JKIA FORODHA PRICE SCHEDULE

	ITEM DESCRIPTION		Bidde	Bidder's response	
			Unit Cost (16% VAT Inclusive) -Kshs	Total Cost (16% VAT Inclusive) -Kshs	
1.	12 CORES SM FIBRE CABLE (Metres)	310			
2.	SM ODF 12 PORTS WITH ACCESSORIES	4			
3.	SINGLE-MODE FIBRE SFP MODULES 1G	2			
4.	SM LC-LC 1.5M FIBRE PATCH CORDS	6			
5.	CAT 6A UTP CABLE (ROLL)	70			
6.	CAT 6A PATCH PANEL, T568A/B , 48-PORT	7			
7.	CAT 6A PATCH PANEL, T568A/B , 24-PORT	1			
8.	CAT 6A DUAL DATA OUTLETS (RJ45)	168			
9.	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	336			
10.	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	168			
11.	22U FREE STANDING CABINET WITH LOCKABLE	2			

	ITEM DESCRIPTION Q		Bidde	Bidder's response	
			Unit Cost (16% VAT Inclusive) -Kshs	Total Cost (16% VAT Inclusive) -Kshs	
	DOOR				
12.	32U FREE STANDING CABINET WITH LOCKABLE DOOR	1			
13.	100MM X50 MM PARTITIONED METAL TRUNKS, 2.4M LENGTH	70			
14.	150MM X50 MM PARTITIONED METAL TRUNKS, 2.4M LENGTH	1			
15.	200MM X50 MM PARTITIONED METAL TRUNKS, 2.4M LENGTH	142			
16.	100MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	6			
17.	150MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	10			
18.	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	134			
19.	1.5KVA RACK-MOUNTED UPS	4			
	SUB-TOTAL (LAN MATERIALS)				
20.	LABOUR				
	NEW LAN INSTALLATION (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS FOR BOTH COPPER & FIBRE)	Lot			
	FIBRE TERMINATION (PER CORE)	36			
	OLD CABLE UNINSTALLATION	Lot			
	OLD TRUNKING UNINSTALLATION	Lot			
	TRANSFER EQUIPMENT FROM OLD TO NEW CABINET	Lot			
	SUB-TOTAL (LABOUR)				
	GRAND TOTAL IN KSHS – VAT INCLUSIVE				

# 2. 5TH FLOOR TIMES TOWER PRICE SCHEDULE

	ITEM DESCRIPTION	Qty	Bidder's response	
			Unit Cost (16% VAT Inclusive) -Kshs	Total Cost (16% VAT Inclusive) -Kshs
1.	12 CORES MM FIBRE CABLE (Metres)	300		
2.	MM ODF 12 PORTS WITH ACCESSORIES	2		
3.	MULTI-MODE FIBRE SFP MODULES 1G	8		
4.	MM SC-LC 1M FIBRE PATCH CORDS	8		
5.	CAT 6A UTP CABLE (ROLL)	16		
6.	CAT 6A PATCH PANEL, T568A/B , 48-PORT	2		
7.	CAT 6A PATCH PANEL, T568A/B , 24-PORT	3		

	ITEM DESCRIPTION		Bidder's response		
				Total Cost (16% VAT Inclusive) -Kshs	
8.	CAT 6A DUAL DATA OUTLETS (RJ45)	70			
9.	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	140			
10.	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	85			
11.	22U FREE STANDING CABINET WITH LOCKABLE DOOR	2			
12.	50MM X25MM METAL TRUNKS, 2.4M LENGTH	6			
13.	200MM X50 MM PARTITIONED METAL TRUNKS, 2.4M LENGTH	43			
14.	75MM X50 MM CURVED FLOOR PARTITIONED METAL TRUNKS, 2.4M	20			
15.	150MM PEDESTAL TRUNKING	20			
16.	200MM SINGLE GANG SERVICE PLATES/KNOCKOUTS	24			
17.	SINGLE-GANG BLANK FACEPLATES	60			
18.	DUAL-GANG BLANK FACEPLATES	80			
	SUB-TOTAL (LAN MATERIALS)		•		
20.	LABOUR				
	NEW LAN INSTALLATION (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE TESTS)	LOT			
	FIBRE TERMINATION (PER CORE)	24			
	SUB-TOTAL (LABOUR)				
	GRAND TOTAL IN KSHS – VAT INCLUSIVE				

# 3. NAMANGA PRICE SCHEDULE

		Bidder's response		
	ITEM DESCRIPTION	Qty	Unit Cost (16% VAT Inclusive) -Kshs	`
1.	CAT 6A UTP CABLE (ROLL)	4		
2.	CAT 6A PATCH PANEL, T568A/B , 24-PORT	1		
3.	CAT 6A DUAL DATA OUTLETS (RJ45)	11		
4.	1M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	22		
5.	3M CAT 6A UTP MODULAR STRANDED T568A/B PATCH CORDS	15		
6.	200MM X50 MM PARTITIONED METAL TRUNKS IN LENGTHS OF 2.4M	25		
7.	200MM SERVICE PLATES/KNOCKOUTS	11		
	SUB-TOTAL (LAN MATERIALS)			
8.	LABOUR COST - NEW LAN INSTALLATION (INCLUDING LAN SCHEMATIC DRAWINGS & FLUKE	LOT		

		Bidder's	response
ITEM DESCRIPTION	Qty		Total Cost (16% VAT Inclusive) -Kshs
TESTS)			
SUB-TOTAL (LABOUR)			
GRAND TOTAL IN KSHS – VAT INCLUSIVE			

#### SUMMARY OF PRICE SCHEDULE FOR LOT V

	LOT V PRICE SCHEDULE			
NO.	STATION	GRAND TOTAL IN KSHS – VAT INCLUSIVE FOR EACH STATION (FROM THE TABLES ABOVE)		
1	JKIA -Forodha			
2	5th Floor Times Tower			
3	Namanga			
	GRAND TOTAL IN KSHS – VAT INCLUSIVE TO BE CARRIED TO THE FORM OF TENDER FOR LOT V			

Name of tenderer	[insert complete name of tenderer]
Signature of tenderer	[signature of person signing the Tender]
Date	[insert date]

<sup>\* [</sup>For previously imported Goods, the quoted price shall be distinguishable from the original import value of these Goods declared to customs and shall include any rebate or mark-up of the local agent or representative and all local costs except import duties and taxes, which have been and/or have to be paid by the KENYA REVENUE AUTHORITY. For clarity, the tenderers are asked to quote the price including import duties, and additionally to provide the import duties and the price net of import duties which is the difference of those values.]

### FORM OF TENDER SECURITY-[Option 1-Demand Bank Guarantee]

Bei	neficiary:				
Red	tequest for Tenders No:				
Da	te:				
	NDER GUARANTEE No.:				
	arantor:				
1.	We have been informed that				
2.	Furthermore, we understand that, according to the Beneficiary's conditions, Tenders must be supported by a Tender guarantee.				
3.	At the request of the Applicant, we, as Guarantor, hereby irrevocably undertake to pay the Beneficiary any sum or sums not exceeding in total an amount of() upon receipt by us of the Beneficiary's complying demand, supported by the Beneficiary's statement, whether in the demand itself or a separate signed document accompanying or identifying the demand, stating that either the Applicant:				
(a)	has withdrawn its Tender during the period of Tender validity set forth in the Applicant's Letter of Tender ("the Tender Validity Period"), or any extension thereto provided by the Applicant; or				
b)	having been notified of the acceptance of its Tender by the Beneficiary during the Tender Validity Period or any extension there to provided by the Applicant, (i) has failed to execute the contract agreement, or (ii) has failed to furnish the Performance.				
4.	This guarantee will expire: (a) if the Applicant is the successful Tenderer, upon our receipt of copies of the contract agreement signed by the Applicant and the Performance Security and, or (b) if the Applicant is not the successful Tenderer, upon the earlier of (i) our receipt of a copy of the Beneficiary's notification to the Applicant of the results of the Tendering process; or (ii) thirty days after the end of the Tender Validity Period.				
5.	Consequently, any demand for payment under this guarantee must be received by us at the office indicated above on or before that date.				
	$\overline{[signature(s)]}$				

Note: All italicized text is for use in preparing this form and shall be deleted from the final product.

### **FORMAT OF TENDER SECURITY [Option 2–Insurance Guarantee]**

TEN	DER GUARANTEE No.:	
1.	[Date of submission of tender] f	(hereinafter called "the tenderer") has submitted its tender dated for the
2.	having our registered office at	that WE of
	Sealed with the Common Seal of the sai	d Guarantor thisday of 20
3.	NOW, THEREFORE, THE CONDITI	ON OF THIS OBLIGATION is such that if the Applicant:
		g the period of Tender validity set forth in the Principal's Letter of eriod"), or any extension thereto provided by the Principal; or
	Validity Period or any extension agreement; or (ii) has failed to	ceptance of its Tender by the Procuring Entity during the Tender thereto provided by the Principal; (i) failed to execute the Contract furnish the Performance Security, in accordance with the Instructions curing Entity's Tendering document.
	receipt of the Procuring Entity's first its demand, provided that in its dema	ediately pay to the Procuring Entity up to the above amount upon written demand, without the Procuring Entity having to substantiate nd the Procuring Entity shall state that the demand arises from the s, specifying which event(s) has occurred.
4.	the contract agreement signed by the is not the successful Tenderer, upon the	Applicant is the successful Tenderer, upon our receipt of copies of Applicant and the Performance Security and, or (b) if the Applicant ne earlier of (i) our receipt of a copy of the Beneficiary's notification to Tendering process; or (ii)twenty-eight days after the end of the
5.	Consequently, any demand for payment above on or before that date.	t under this guarantee must be received by us at the office indicated
	[Date ]	[Signature of the Guarantor]
	[Witness]	[Seal]

Note: All italicized text is for use in preparing this form and shall be deleted from the final product.

### FORM OF TENDER-SECURING DECLARATION

[The Bidder shall complete this Form in accordance with the instructions indicated]
Date:[insert date (as day, month and year) of Tender Submission]
Tender No.:
To:[insert complete name of
Purchaser] I/We, the undersigned, declare that:
1. I/We understand that, according to your conditions, bids must be supported by a Tender-Securing Declaration.
I/We accept that I/we will automatically be suspended from being eligible for tendering in any contract with the Purchaser for the period of time of[insert number of months or years] starting on[insert date], if we are in breach of our obligation(s) under the bid conditions, because we – (a) have withdrawn our tender during the period of tender validity specified by us in the Tendering Data Sheet; or (b) having been notified of the acceptance of our Bid by the Purchaser during the period of bid validity, (i) fail or refuse to execute the Contract, if required, or (ii) fail or refuse to furnish the Performance Security, in accordance with the instructions to tenders.
3. I/We understand that this Tender Securing Declaration shall expire if we are not the successful Tenderer(s), upon the earlier of:
a) our receipt of a copy of your notification of the name of the successful Tenderer; or
b) thirty days after the expiration of our Tender.
4. I/We understand that if I am/we are/in a Joint Venture, the Tender Securing Declaration must be in the name of the Joint Venture that submits the bid, and the Joint Venture has not been legally constituted at the time of bidding, the Tender Securing Declaration shall be in the names of all future partners as named in the letter of intent.
Signed:
Capacity / title (director or partner or sole proprietor, etc.)
Name:
Duly authorized to sign the bid for and on behalf of:[insert complete name
Tenderer]. Dated on
signing].
Seal or stamp.

#### MANUFACTURER'S AUTHORIZATION FORM

Title:.....[Insert title]

The tenderer shall include it in its Tender, if so indicated in the TDS.] Date:.....[insert date (as day, month and year) of Tender submission] ITT No:.....[insert number ofITTTender for an alternative] To: ..... [Insert complete name of KENYA REVENUE AUTHORITY] WHEREAS We...... [insert complete name of Manufacturer], who are of......[insert type of goods manufactured], having factories at [insert full address of Manufacturer's factories], do hereby authorize [insert complete name of tenderer] to submit a Tender the purpose of description of the Goods], and to subsequently negotiate and sign the Contract. We hereby extend our full guarantee and warranty in accordance with Clause 28 of the General Conditions of Contract, with respect to the Goods offered by the above firm. Signed:.....[Insert signature(s) of authorized representative(s) of the Manufacturer] 

[The tenderer shall require the Manufacturer to fill in this Form in accordance with the instructions indicated. This letter of authorization should be on the letterhead of the Manufacturer and should be signed by a person with the proper authority to sign documents that are binding on the Manufacturer.



#### SECTION V TECHNICAL SPECIFICATIONS

SUPPLY, DELIVERY, INSTALLATION AND COMMISSIONING OF LOCAL AREA NETWORKS (LANs) FOR IDENTIFIED KRA STATIONS

#### Introduction

KRA hereby invites bids from prospective bidders for supply, delivery, installation and commissioning of local area networks (lans) for identified kra stations.

The scope of this tender include the following:

✓ Supply, Delivery, Installation and Commissioning of Local Area Networks (LANs) for identified KRA Stations.

#### 1. 0 GENERAL REQUIREMENTS

#### Instructions to Bidders

- 1. Bidders are required to propose Genuine Products which are brand new, internationally recognized and mature brands.
- 2. There are several Lots in this tender. Each Lot has a group of Sites (stations). A separate Local Area Network is required to be installed in each site within a given Lot.
- 3. Bidders may choose to bid for multiple Lots but can only be awarded one (1) Lot.
- 4. The Successful bidder in each Lot is required to undertake concurrent Installation of LANs for all the sites within the awarded Lot.
- 5. Bidders <u>MUST</u> provide substantive responses <u>FOR ALL THE FEATURES</u> in the minimum technical specifications irrespective of any attached technical documents. Use of the words such **YES**, **COMPLIANT**, **NO**, **TICK**, **BLANK SPACES** etc will be considered non-responsive and shall lead to bidder's disqualification.

#### 1.1 General

The Kenya Revenue Authority (hereinafter referred to as "KRA") The Kenya Revenue Authority was established by an Act of Parliament, Chapter 469 of the laws of Kenya, which became effective on the 1<sup>st</sup> of July 1995. KRA is charged with collecting revenue on behalf of the Government of Kenya.

The core functions of the Authority are: -

- To assess, collect and account for all revenues in accordance with the written laws and the specified provisions of the written laws.
- To advise on matters relating to the administration of, and collection of revenue under the written laws or the specified provisions of the written laws
- To perform such other functions in relation to revenue as the Minister may direct.

#### KRA/HQS/NCB -092/2022-2023:

# SUPPLY, DELVERY, INSTALLATION AND COMMISSIONING OF LOCAL AREA NETWORKS (LANs) FOR IDENTIFIED KRA STATIONS.

The structured cabling (LANs) for most of the KRA stations were first deployed around 2005 when the Authority embarked on the journey to automate most of its critical processes.

Whereas the number of staff in each station has grown substantially over the years, there has been no corresponding LAN infrastructure upgrades in the affected stations to cater for the increased demand for connectivity.

This has therefore led to the installation of unstructured temporary LANs.

These makeshift LANS did not only create untidy office environment but they are also prone to frequent Network failures, which seriously impact revenue collection efforts. Hence, the need to upgrade the Authority's LAN infrastructure.

KRA is keen to address these historical LAN infrastructure challenges by upgrading the structured cabling for the identified stations.

For purposes of this Tender, KRA aims to procure and install modern LAN infrastructure for the identified stations with a view to improving access to IT services and address the other challenges associated with the existing temporary LANs.

#### 2.1 Scope of works

There are several LOTs in this tender. Each LOT has a group of Sites (stations). A separate structured cabling (LAN) is required to be installed in each site within a given LOT.

The structured cabling activities include, but not limited to, the installation of metal trunking, pulling and termination of both UTP and Fiber cables, cable management, labeling etc.

The fiber works primarily entail the installation of indoor fiber cables to interconnect floors within the same building. However, there may be few occasions where outdoor fiber cable needs to be installed to extend connectivity services to another operational area within the KRA station.

It is important to note that this is a general description of the scope of works for the deployment of Local Area Networks (LANs). However, each site/station will have its own set of requirements and unique scope of works. The installation exercise will be handled in a case by case basis.

#### 2.2 Site visits

Site visit is **optional**. However, bidders are encouraged to visit the following Ten (10) stations. These sites have elaborate office designs with numerous floors, wings, and satellite offices. The visits will give bidders in-depth understanding of the scope

of works, office layouts, conditions and characteristics of the sites, which will enable them to submit more precise and competitive bids.

The sites are as follows:-

LOT	STATION
Lot I	1. Nyeri
	2. Embu
Lot II	1. Nakuru
	2. Eldoret
Lot III	1. Lake Basin
	2. Forodha
Lot IV	1. Taveta OSBP
	2. Diani
Lot V	1. JKIA
	2. Times Towers

# TECHNICAL SPECIFICATION REQUIREMENTS

### LOTS SUMMARY

### **LOT I**

NO.	STATION	
1	Embu	
2	Garissa	
3	Wajir (Main & Airport Offices)	
4	Murang'a	
5	Isiolo DTD	
6	Isiolo Airport	
7	Nyeri	
8	Nanyuki	

### **LOT II**

NO.	STATION
1	Eldoret - Kiptagich House
2	Eldoret - KPC
3	Eldoret – Airport (Cargo, Scanner, Terminal & K9 Offices)
4	Lodwar
5	Lokichogio
6	Lokichogio - Airport
7	Kericho Main Office
8	Nakuru - Generation House
9	Nakuru - KPC

# LOT III

NO.	STATION		
1	Kisumu - Lake Basin Mall		
2	Kisumu – Forodha House		
3	Kisumu Pipeline, PPO, Airport, Pier		
4	Kisii (DC & Posta Offices)		
5	Bungoma		
6	Kakamega		
7	Siaya		
8	Busia		
9	Malaba		
10	Isebania		

# $\underline{\textbf{LOT IV}}$

NO.	STATION
1	Lamu TSO
2	Lamu Airport
3	Voi
4	Diani
5	Kilifi
6	Taveta OSBP
7	Kwale

# $\underline{\text{LOT } V}$

NO.	STATION
1	JKIA -Forodha
2	5th Floor Times Tower
3	Namanga

#### CLAUSE-BY-CLAUSE RESPONSES TO TECHNICAL REQUIRMENTS

The tender is categorized into five separate lots, each covering a specific group of stations. Each station within a given lot has its own unique technical specifications and therefore must be responded to individually for the bidder to be considered for that specific station.

### A. LOT I TECHNICAL SPECIFICATIONS

#### I. MINIMUM TECHNICAL SPECIFICATIONS FOR EMBU

#### 1. Minimum Technical Specifications for 12 Core Single Mode Armored Fiber Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years(bidder must specify brand)	
2.	Jacket characteristics	Water Blocking Aramid Yarn	
	& Material	Armored	
		PVC	
3.	Mode of operation	Single mode	
4.	Core density	12 cores	
5.	Attenuation (Max)	3.50 dB/km @ 850nm	
6.	Standards	Optical and mechanical performance:	
		IEC 60794-2, IEC 60794-2-20, ISO	
		11801, EN 50173-1	

#### 2. Minimum Technical Specifications for 12 Port Multimode Modular Fiber ODF

	Feature	Minimum Requirements	Bidder's response
	D 1	7	
1.	Brand	Internationally recognized, matured	
		brand	
2.	Mode of operation	Multimode	
3.	Port density	• 12 ports (24 cores)	
		Fully populated	
4.	Form Factor	1HU	
5.	Adapter	LC	
6.	Accessories	• 24 Pigtail connectors	
		• 24 core Splice tray	
		• 30 Heat shrink sleeves	

#### 3. Minimum Technical Specifications for 1G Multimode SFP Transceiver Modules

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand (bidder must specify brand )	
2.	Mode of operation	Multimode	
3.	Compatibility	Must be compatible with Cisco switches	
4.	Form Factor	Small pluggable form factor	
5.	Capacity	1 Gigabyte (1G)	

#### 4. Minimum Technical Specifications for 1M LC-LC Multimode Fiber Patch Cords

	Feature	<b>Minimum Requirements</b>	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years.	
2.	Mode	Multimode <b>OM3 50/125</b>	
3.	Connector	Must be <b>LC-LC</b>	
4.	Length	1m	

### 5. Minimum Technical Specifications for 3M LC-LC Multimode Fiber Patch Cords

	Feature	<b>Minimum Requirements</b>	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years.	
2.	Mode	Multimode <b>OM3 50/125</b>	
3.	Connector	Must be <b>LC-LC</b>	
4.	Length	3m	

### 6. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized,	
		matured brand, in existence for at	
		least 10 years (bidder must	
		specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating	500 to 550 MHZ	
	frequency		
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

### 7. Minimum Technical Specifications for CAT 6A 48-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	48 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	

	Feature	Minimum Requirements	Bidder's response
12.	Panel material	18 gauge cold rolled steel, black e-	
		coated	
13.	Category and	CAT6A and downward	
	compatibility	compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

### 8. Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

### 9. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	•
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8- position) plugs Should also be backward compatible to cat 5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	

	Feature	<b>Minimum Requirements</b>	Bidder's response
13.	Termination	By Z-tool	

### 10. Minimum Technical Specifications for 1m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

### 11. Minimum Technical Specifications for 3m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

### 12. Minimum Technical Specifications for 5m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	5 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

### 13. Minimum Technical Specifications for 18U Wall Mount Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand	
2.	Form Factor	18 U wall-mount data cabinet with a	
		hinged back	
3.	Dimension	600x800mm	

	Feature	Minimum Requirements	Bidder's response
4.	Construction	Front door: with glass window	
		Rear: Hinged Back Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

### 14. Minimum Technical Specifications for 22U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	22 U floor standing standard data cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window Rear door: high-flow mesh Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

### 15. Minimum Technical Specifications for 32U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	32 U floor standing standard data cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window Rear door: high-flow mesh Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

### 16. Minimum Technical Specifications for 75mmx25mm Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	75mm by 25mm	

3.	Length	2.4m	
4.	Gauge	1.2mm	

### 17. Minimum Technical Specifications for 150mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	150mm by 50mm, two compartments	
3.	Length	2.4 M	
4.	Gauge	1.2mm	

#### 18. Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4m	
4.	Gauge	1.2mm	

### 19. Minimum Technical Specifications for 75mmx50mm Curved Floor Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	75mm by 50mm	
3.	Form	Curved	
4.	Length	2.4m	
5.	Gauge	1.2mm	

### 20. Minimum Technical Specifications for 150mm Pedestal Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	<ul> <li>Powder coated metal trunking with pre-punched fixing holes for permanent floor structures.</li> <li>Rounded corners.</li> </ul>	
2.	Size	150mm	
3.	Outlets	<ul><li>4 single gang data outlet</li><li>4 dual gang power outlet</li></ul>	
4.	Height	400mm	
5.	Gauge	1.2mm	

#### 21. Minimum Technical Specifications for 200mmx50mm Perforated Cable Trays

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Perforated galvanized tray	
2.	Length	2.4 M	

		Feature	Minimum Requirements	Bidder's Response
ſ	3.	Size	200mm by 50mm	
	4.	Gauge	2mm thick	

### 22. Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 250mm by 50mm trunking	
5.	Gauge	1.2mm	

### 23. Minimum Technical Specifications for Double Gang Blank Faceplates

	Feature	Minimum Requirements	Bidder's Response
1.	Size	Double gang	
2.	Colour	White	
3.	Material	High impact plastic (ABS UL 94V-0 compliant)	
4.	Assembly	Blank double gang complete with screws	

### 24. Minimum Technical Specifications for 2m Threaded Rods

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Steel threaded rods	
2.	Length	2m	
3.	Size	M10	

#### 25. Minimum Technical Specifications for 300mm Trapeze Hanger

	Feature	<b>Minimum Requirements</b>	Bidder's Response
1.	Material	Galvanize steel	
2.	Rod hole size	12mm at the ends	
3.	Type	Flat	
4.	Length	300mm	
5.	Width	50mm	
6.	Thickness	3mm	

#### 26. Minimum Technical Specifications for Rawl Bolts M10 Mm

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Steel threaded rods	
2.	Size	M10	
3.	Packaging	Packets of 100pcs	

### 27. Minimum Technical Specifications for M10 Nuts with Washers

	Feature	<b>Minimum Requirements</b>	Bidder's Response
1.	Material	Steel	

	Feature	Minimum Requirements	Bidder's Response
2.	Size	• Nuts M10	
		• Washers M10	
3.	Packaging	Packets of 100pcs	

### 28. Minimum Technical Specifications for 1.5KVA Rack-Mounted UPS

	Feature	Minimum Requirement	Bidders Response
		Internationally recognized brand (bidder must specify brand and model)	
		Output	
1.	Output Power Capacity	900 Watts / 1500 VA	
2.	Power	900 Watts / 1500 VA	
3.	Nominal Output Voltage	230V	
4.	Output Voltage Distortion	Less than 5% at full load	
5.		47 - 53 Hz for 50 Hz nominal, 57 - 63 Hz for 60 Hz nominal	
6.	Topology	Line interactive	
7.	Waveform Type	Stepped approximation to a Sine wave	
8.	Output Connections	Four (4) IEC 320 C13 Two (2) IEC jumpers	
		Input	
9.	Nominal Input Voltage	230V	
10.	Input Frequency	50/60 Hz +/- 3 Hz (auto sensing)	
11.		IEC-320 C14	
12.	Battery Type	Maintenance free sealed lead-acid with suspended electrolyte, leak proof	
13.	Input voltage range for main operations	180 - 287V	
14.	Input voltage adjustable range for mains operation	170 - 300V	
15.		3 hour(s)	
16.	at Half Load	20.9 minutes (432.5 Watts)	
17.	Typical Backup Time at Full Load	7.6 minutes (865 Watts)	
18.	Interface Ports	Communications & Managem RJ-45 Serial, USB	nent
19.	Control panel	Multi-function LCD status and	
20.	Audible Alarm	control console Alarm when on battery : distinctive low battery alarm : configurable delays	
	·	Surge Protection and Filteri	ng

	Feature	Minimum Requirement	Bidders Response
21.	Surge energy rating	459Joules	
22.	Filtering	Full time multi-pole noise filtering: 0.3% IEEE surge let-through: zero clamping response time: meets UL 1449	
23.	Data Line filtering	RJ-45 modem/Fax/DSL/10-100 Base-T protection	
24.	Standard Warranty	2 years repair or replace	
25.	Accessories	Power cords (at least 1.83M), CD with software, Documentation CD, Rack Mounting brackets, Smart UPS signaling RS-232 cable, USB cable, User Manual	

#### 29. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### The Scope of Works

The successful bidder shall be required to carry out the following works; Installation of a new LAN to replace the old existing LAN. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc. The fiber works entail the installation of indoor or outdoor fiber cables to interconnect floors within the same building or offices within the same campus. Fiber installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before the commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

## Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per the LAN design and the engineer's instructions. All cables must run through the trunkings.	
2.	Horizontal cabling	The horizontal cabling should be done neatly and professionally as per the LAN design and the engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre. Installation of fibre should be carried out according to the instructions of the network engineer on site. At least 6 cores must be terminated for each side of a cable (i.e. 12 terminations).	
4.	Tools & accessories	The contractor must have all the tools and accessories required to install and test Local area Networks (LANs).	
5.	Quality of works	The contractor is required to provide high standard installation service and quality workmanship. Cable management must also be neatly done.  The trunking joints must flush and with no gapes.	

		Knockouts must be installed neatly with no gapes or	
		spaces.	
		The knockouts <b>MUST</b> be of the same shade as that of	
		the trunkings.	
6.	Old cable	The contractor will be required to carefully uninstall	
	/trunking	old cabling and/or trunking in areas where the LAN is	
	uninstallation	undergoing an overhaul. This should be done neatly to	
		avoid tampering with the wall painting and	
		cable/trunking to be reused.	
7.	Equipment	The contractor will be required to carefully uninstall	
	migration	equipment from the old cabinet and migrate them to	
		the newly installed cabinet. This should be done	
		carefully to avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The	
	· ·	contractor will be required to return to site and rectify	
		any defects that may occur within the defect liability	
		period at no extra cost to the Authority.	
9.	Drawings and	On completion of the works the contractor <b>MUST</b>	
	documentation	provide all the relevant documentation and the LAN	
		schematic diagram for each site.	
10.	Labeling	All the data points and ports on the Patch panels must	
	Ü	be well labeled with Printed labels. The patch cords	
		must also be labeled on both ends to match port	
		numbers.	
11.	Testing and	The Contractor is required to carry out professional	
	Commissioning	tests and provide results both in printed and in soft	
		copy. This shall apply to both copper and fibre.	
		A joint test and commissioning will be carried out by	
		KRA and the contractor.	

#### II. MINIMUM TECHNICAL SPECIFICATIONS FOR GARISSA

## 1. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years (bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

#### 2. Minimum Technical Specifications for CAT 6A 48-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	48 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to	
		read	
7.	Contact materials	Plated phosphor bronze, stainless	
		steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e-	
		coated	
13.	Category and	CAT6A and downward compatible	
	compatibility	with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 3. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs Should also be backward compatible to cat 5e	

	Feature	Minimum Requirements	Bidder's response
10.	Shield	Hinged cable retention/ grounding	
		clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

## 4. Minimum Technical Specifications for 1m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 5. Minimum Technical Specifications for 3m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

#### 6. Minimum Technical Specifications for 32U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	32 U floor standing standard data cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window Rear door: high-flow mesh Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

#### 7. Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4m	
4.	Gauge	1.2mm	

#### 8. Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	250mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 250mm by 50mm trunking	
5.	Gauge	1.2mm	

#### 9. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### **The Scope of Works**

The successful bidder shall be required to carry out the following works; Installation of a new LAN to replace the old existing LAN. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc. The fiber works entail the installation of indoor or outdoor fiber cables to interconnect floors within the same building or offices within the same campus. Fiber installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before the commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

## Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation.

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per the LAN design and the engineer's instructions. All cables must run through the trunkings.	
2.	Horizontal cabling	The horizontal cabling should be done neatly and professionally as per the LAN design and the engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre. Installation of fibre should be carried out according to the instructions of the network engineer on site. At least 6 cores must be terminated for each side of a cable (i.e. 12 terminations).	

4.	Tools & accessories	The contractor must have all the tools and accessories required to install and test Local area Networks (LANs).	
5.	Quality of works	The contractor is required to provide high standard installation service and quality workmanship. Cable management must also be neatly done.  The trunking joints must flush and with no gapes. Knockouts must be installed neatly with no gapes or spaces. The knockouts <b>MUST</b> be of the same shade as that of the trunkings.	
6.	Old cable /trunking uninstallation	The contractor will be required to carefully uninstall old cabling and/or trunking in areas where the LAN is undergoing an overhaul. This should be done neatly to avoid tampering with the wall painting and cable/trunking to be reused.	
7.	Equipment migration	The contractor will be required to carefully uninstall equipment from the old cabinet and migrate them to the newly installed cabinet. This should be done carefully to avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The contractor will be required to return to site and rectify any defects that may occur within the defect liability period at no extra cost to the Authority.	
9.	Drawings and documentation	On completion of the works the contractor <u>MUST</u> provide all the relevant documentation and the LAN schematic diagram for each site.	
10.	Labeling	All the data points and ports on the Patch panels must be well labeled with Printed labels. The patch cords must also be labeled on both ends to match port numbers.	
11.	Testing and Commissioning	The Contractor is required to carry out professional tests and provide results both in printed and in soft copy. This shall apply to both copper and fibre.  A joint test and commissioning will be carried out by KRA and the contractor.	

## III. MINIMUM TECHNICAL SPECIFICATIONS FOR WAJIR (MAIN & AIRPORT OFFICES)

## 1. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at	
		least 10 years (bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

## 2. Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 3. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	

	Feature	<b>Minimum Requirements</b>	Bidder's response
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8- position) plugs Should also be backward compatible to cat 5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

## 4. Minimum Technical Specifications for 1M CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 5. Minimum Technical Specifications for 3M CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 6. Minimum Technical Specifications for 12U Wall Mount Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
	Para Parlan		
2.	Form Factor	12 U wall-mount data cabinet with	
		a hinged back	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window	
		Rear: Hinged Back	
		Both doors keyed locks for security	
		1.2mm solid sides	

	Feature	Minimum Requirements	Bidder's response
		Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Three (3) pieces of 1U black metallic horizontal Dual-sided cable managers	

## 7. Minimum Technical Specifications for 18U Wall Mount Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	18 U wall-mount data cabinet with a <b>hinged back</b>	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window Rear: Hinged Back Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

## 8. Minimum Technical Specifications for 100mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	100mm by 50mm, two compartments	
3.	Length	2.4m	
4.	Gauge	1.2mm	

## 9. Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4m	
4.	Gauge	1.2mm	

## 10. Minimum Technical Specifications for 100mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	

2.	Height	100mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 100mm by 50mm trunking	
5.	Gauge	1.2mm	

## 11. Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	
5.	Gauge	1.2mm	

## 12. Minimum Technical Specifications for 200mm Double Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Double Gang	
4.	Compatibility	Compatible with 250mm by 50mm trunking	
5.	Gauge	1.2mm	

## 13. Minimum Technical Specifications for 1.5KVA Rack-Mounted UPS

	Feature	Minimum Requirement	<b>Bidders Response</b>
	Brand and Model	Internationally recognized brand (bidder must specify brand and model)	
		Output	
1.	Output Power Capacity	900 Watts / 1500 VA	
2.	Max Configurable Power	900 Watts / 1500 VA	
3∙	Nominal Output Voltage	230V	
4.	Output Voltage Distortion	Less than 5% at full load	
5.		47 - 53 Hz for 50 Hz nominal, 57 - 63 Hz for 60 Hz nominal	
6.	Topology	Line interactive	
7.	Waveform Type	Stepped approximation to a Sine wave	
8.	Output Connections	Four (4) IEC 320 C13 Two (2) IEC jumpers	
	-	Input	

	Feature	Minimum Requirement	Bidders Response
9.	Nominal Input Voltage	230V	
10.	Input Frequency	50/60 Hz +/- 3 Hz (auto sensing)	
11.	Input Connections	IEC-320 C14	
12.	Battery Type	Maintenance free sealed lead-acid with suspended electrolyte, leak proof	
13.	Input voltage range for main operations	180 - 287V	
14.	Input voltage adjustable range for mains operation		
15.	Typical recharge time	3 hour(s)	
16.	Typical Backup Time at Half Load	20.9 minutes (432.5 Watts)	
17.	Typical Backup Time at Full Load	7.6 minutes (865 Watts)	
		Communications & Manager	nent
18.	Interface Ports	RJ-45 Serial, USB	
19.	Control panel	Multi-function LCD status and control console	
20.	Audible Alarm	Alarm when on battery : distinctive low battery alarm : configurable delays	
	•	Surge Protection and Filter	ing
21.	Surge energy rating	459Joules	
22.	Filtering	Full time multi-pole noise filtering: 0.3% IEEE surge let-through: zero clamping response time: meets UL 1449	
23.	Data Line filtering	RJ-45 modem/Fax/DSL/10-100 Base-T protection	
24.	Standard Warranty	2 years repair or replace	
25.	Accessories	Power cords (at least 1.83M), CD with software, Documentation CD, Rack Mounting brackets, Smart UPS signaling RS-232 cable, USB cable, User Manual	

#### 14. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### The Scope of Works

The successful bidder shall be required to carry out the following works; Installation of a new LAN to replace the old existing LAN. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc. The fiber works entail the installation of indoor or outdoor fiber cables to interconnect floors within the same building or offices within the same campus. Fiber installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before the commencement of the LAN installation. A technical inspection will be carried out on the LAN

materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

## Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per	
		the LAN design and the engineer's instructions.	
		All cables must run through the trunkings.	
	** ' . 1		
2.	Horizontal	The horizontal cabling should be done neatly and	
	cabling	professionally as per the LAN design and the	
	77 I' 1	engineer's instructions on site.	
3.	Vertical	The backbone is typically done using fibre.	
	cabling	Installation of fibre should be carried out according	
		to the instructions of the network engineer on site. At least 6 cores must be terminated for each side of	
		a cable (i.e. 12 terminations).	
4.	Tools &	The contractor must have all the tools and	
4.	accessories	accessories required to install and test Local area	
	accessories	Networks (LANs).	
5.	Quality of	The contractor is required to provide high standard	
J.	works	installation service and quality workmanship.	
		Cable management must also be neatly done.	
		The trunking joints must flush and with no gapes.	
		Knockouts must be installed neatly with no gapes	
		or spaces.	
		The knockouts <b>MUST</b> be of the same shade as that	
		of the trunkings.	
6.	Old cable	The contractor will be required to carefully	
	/trunking	uninstall old cabling and/or trunking in areas	
	uninstallation	where the LAN is undergoing an overhaul. This	
		should be done neatly to avoid tampering with the	
		wall painting and cable/trunking to be reused.	
7.	Equipment	The contractor will be required to carefully	
	migration	uninstall equipment from the old cabinet and	
		migrate them to the newly installed cabinet. This	
		should be done carefully to avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The	
0.	warranty	contractor will be required to return to site and	
		rectify any defects that may occur within the defect	
		liability period at no extra cost to the Authority.	
9.	Drawings and	On completion of the works the contractor <b>MUST</b>	
۶۰	documentation	provide all the relevant documentation and the	
		LAN schematic diagram for each site.	
10.	Labeling	All the data points and ports on the Patch panels	
		must be well labeled with Printed labels. The patch	
		cords must also be labeled on both ends to match	
		port numbers.	
11.	Testing and	The Contractor is required to carry out professional	
	Commissionin	tests and provide results both in printed and in soft	
	g	copy. This shall apply to both copper and fibre.	
		A joint test and commissioning will be carried out	
		by KRA and the contractor.	

#### IV. MINIMUM TECHNICAL SPECIFICATIONS FOR MURANG'A

## 1. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized,	
		matured brand, in existence for	
		at least 10 years (bidder must	
		specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC	
		11801	

## 2. Minimum Technical Specifications for CAT 6A 48-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	48 port	
3.	Cable Management	Rear Cable management bar installed	
4.	Labels	Printable labels MUST be available	
5.	Wiring	T568A/T568B compliant and easy to read	
6.	Contact materials	Plated phosphor bronze, stainless steel	
7.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
8.	Current rating	1.5 A	
9.	Contact resistance	20 mΩ	
10.	Insulation resistance	500 ΜΩ	
11.	Panel material	18 gauge cold rolled steel, black e-coated	
12.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	

## 3. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual angled RJ45 outlet module installed on a single gang face plate	
3.	Contact resistance	20 mΩ	
4.	Insulation Resistance	500 ΜΩ	
5.	Current rating	1.5 A PoE , PoE+	
6.	Contact Materials	Plated phospher bronze, stainless steel	
7.	Plug compatibility	Compatible with RJ45 (8-position) plugs Should also be backward compatible to cat 5e	
8.	Termination	By Z-tool	

## 4. Minimum Technical Specifications for 1M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

#### 5. Minimum Technical Specifications for 3M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

#### 6. Minimum Technical Specifications for 22U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	22 U floor standing standard data cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window Rear door: high-flow mesh Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

## 7. Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4 M	
4.	Gauge	1.2mm	

## 8. Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	
5.	Gauge	1.2mm	

#### 9. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### **The Scope of Works**

The successful bidder shall be required to carry out the following works; Installation of new LAN for KRA Murang'a station. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as	
		per the LAN design and the engineer's	
		instructions.	
		All cables must run through the trunkings.	
2.	Horizontal	The horizontal cabling should be done neatly	
	cabling	and professionally as per the LAN design and	
	Wanting alling	the engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fiber. Installation of fiber should be carried out	
		according to the instructions of the network	
		engineer on site. At least 6 cores must be	
		terminated for each side of a cable (i.e. 12	
		terminations).	
4.	Tools &	The contractor must have all the tools and	
٦٠	accessories	accessories required to install and test Local	
		area Networks (LANs).	
5.	Quality of works	The contractor is required to provide high	
		standard installation service and quality	
		workmanship. Cable management must also be	
		neatly done.	
		The trunking joints must flush and with no	
		gapes. Knockouts must be installed neatly with	
		no gapes or spaces.	
		The knockouts <b>MUST</b> be of the same shade as	
	01.1	that of the trunkings.	
6.	Old	The contractor will be required to carefully	
	cable/trunking uninstallation	uninstall old cabling and/or trunking in areas where the LAN is undergoing an overhaul. This	
	ullilistaliation	should be done neatly to avoid tampering with	
		the wall painting and cable/trunking to be	
		reused.	
7.	Equipment	The contractor will be required to carefully	
, -	migration	uninstall equipment from the old cabinet and	
	o o	migrate them to the newly installed cabinet.	
		This should be done carefully to avoid damaging	
		the equipment.	
8.	Warranty	The defect liability period shall be one (1) year.	
		The contractor will be required to return to site	
		and rectify any defects that may occur within	
		the defect liability period at no extra cost to the	
0	Drowings and	Authority.  On completion of the works the contractor	
9.	Drawings and documentation	MUST provide all the relevant documentation	
	documentation	and the LAN schematic diagram for each site.	
10.	Labeling	All the data points and ports on the Patch panels	
-0.		must be well labeled with Printed labels. The	
		patch cords must also be labeled on both ends	
		to match port numbers.	
11.	Testing and	The Contractor is required to carry out	
	Commissioning	professional tests and provide results both in	
		printed and in soft copy. This shall apply to both	
		copper and fiber.	
		A joint test and commissioning will be carried	
		out by KRA and the contractor.	

#### V. MINIMUM TECHNICAL SPECIFICATIONS FOR ISIOLO DTD

#### 1 Minimum Technical Specifications for 12 Core Single Mode Armored Fiber Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years(bidder must specify brand)	
2.	Jacket characteristics	Water Blocking Aramid Yarn	
	& Material	Armored	
		PVC	
3.	Mode of operation	Single mode	
4.	Core density	12 cores	
5.	Attenuation (Max)	3.50 dB/km @ 850nm	
6.	Standards	Optical and mechanical performance:	
		IEC 60794-2, IEC 60794-2-20, ISO	
		11801, EN 50173-1	

#### 2 Minimum Technical Specifications for 12 Port Single-Mode Modular Fiber ODF

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand	
2.	Mode of operation	Single-Mode	
3.	Port density	• 12 ports (24 cores)	
		Fully populated	
4.	Form Factor	1HU	
5.	Adapter	LC	
6.	Accessories	• 24 Pigtail connectors	
		• 24 core Splice tray	
		• 30 Heat shrink sleeves	

#### 3 Minimum Technical Specifications for 1G Single-Mode SFP Transceiver Modules

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand (bidder must specify brand )	
2.	Mode of operation	Single-Mode	
3.	Compatibility	Must be compatible with Cisco switches	
4.	Form Factor	Small pluggable form factor	
5.	Capacity	1 Gigabyte (1G)	

#### 4 Minimum Technical Specifications for 1M LC-LC Single-Mode Fiber Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years.	
2.	Mode	Single mode OS1/OS2	
3.	Connector	Must be <b>LC-LC</b>	
4.	Length	1m	

## 5 Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years (bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	

## 6 Minimum Technical Specifications for CAT 6A 48-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	48 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 7 Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 8 Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs Should also be backward compatible to cat 5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

## 9 Minimum Technical Specifications for 1M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 10 Minimum Technical Specifications for 3M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 11 Minimum Technical Specifications for 12U Wall Mount Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	12 U wall-mount data cabinet with a hinged back	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window  Rear: Hinged Back Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Three (3) pieces of 1U black metallic horizontal Dual-sided cable managers	

## 12 Minimum Technical Specifications for 32U Wall Mount Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	32 U floor standing standard data cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window Rear door: high-flow mesh Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

## 13 Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4 M	
4.	Gauge	1.2mm	

## 14 Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	
5.	Gauge	1.2mm	

## 15 Minimum Technical Specifications for 100mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	100mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 100mm by 50mm trunking	
5.	Gauge	1.2mm	

## 16 Minimum Technical Specifications for 150mm Single Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	150mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 150mm by 50mm trunking	

## 17 Minimum Technical Specifications for 200mm Double Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Double Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	
5.	Gauge	1.2mm	

## 18 Minimum Technical Specifications for 1.5KVA Rack-Mounted UPS

	Feature	Minimum Requirement	Bidders Response	
	Brand and Model	Internationally recognized brand (bidder must specify brand and model)		
		Output		
1.	Output Power Capacit	y 900 Watts / 1500 VA		
2.	Max Configurable Power	900 Watts / 1500 VA		
3.	Nominal Output Voltage	230V		
4.	Output Voltage Distortion	Less than 5% at full load		
5.	Output Frequency (sync to mains)	47 - 53 Hz for 50 Hz nominal, 57 - 63 Hz for 60 Hz nominal		
6.	Topology	Line interactive		
7.	Waveform Type	Stepped approximation to a Sine wave		
8.	Output Connections	Four (4) IEC 320 C13 Two (2) IEC jumpers		
	Input			

	Feature	Minimum Requirement	Bidders Response
9.	Nominal Input Voltage	230V	
10.	Input Frequency	50/60 Hz +/- 3 Hz (auto sensing)	
11.	Input Connections	IEC-320 C14	
12.	Battery Type	Maintenance free sealed lead-acid with suspended electrolyte, leak proof	
13.	Input voltage range for main operations	180 - 287V	
14.	Input voltage adjustable range for mains operation	170 - 300V	
15.	Typical recharge time	3 hour(s)	
16.	Typical Backup Time at Half Load	20.9 minutes (432.5 Watts)	
17.	Typical Backup Time at Full Load	7.6 minutes (865 Watts)	
		Communications & Manage	ement
18.	Interface Ports	RJ-45 Serial, USB	
19.	Control panel	Multi-function LCD status and control console	
20.	Audible Alarm	Alarm when on battery : distinctive low battery alarm : configurable delays	
		Surge Protection and Filte	ring
21.	Surge energy rating	459Joules	
22.	Filtering	Full time multi-pole noise filtering : 0.3% IEEE surge let-through : zero clamping response time : meets UL 1449	
23.	Data Line filtering	RJ-45 modem/Fax/DSL/10-100 Base-T protection	
24.	Standard Warranty	2 years repair or replace	
25.	Accessories	Power cords (at least 1.83M), CD with software, Documentation CD, Rack Mounting brackets, Smart UPS signaling RS-232 cable, USB cable, User Manual	

#### 19 TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### The Scope of Works

The successful bidder shall be required to carry out the following works; Installation of new LAN for KRA Isiolo TSO Station. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc. The fibre works entail the installation of indoor or outdoor fibre cables to interconnect floors within the same building or offices within the same campus. Fibre installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

## Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per the LAN design and the engineer's instructions. All cables must run through the trunkings.	
2.	Horizontal cabling	The horizontal cabling should be done neatly and professionally as per the LAN design and the engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre. Installation of fibre should be carried out according to the instructions of the network engineer on site. At least 6 cores must be terminated for each side of a cable (i.e. 12 terminations).	
4.	Tools & accessories	The contractor must have all the tools and accessories required to install and test Local area Networks (LANs).	
5.	Quality of works	The contractor is required to provide high standard installation service and quality workmanship. Cable management must also be neatly done.  The trunking joints must flush and with no gapes. Knockouts must be installed neatly with no gapes or spaces.  The knockouts <b>MUST</b> be of the same shade as that of the trunkings.	
6.	Old cable/trunkin g uninstallatio	The contractor will be required to carefully uninstall old cabling and/or trunking in areas where the LAN is undergoing an overhaul. This should be done neatly to avoid tampering with the	
7.	Equipment migration	wall painting and cable/trunking to be reused.  The contractor will be required to carefully uninstall equipment from the old cabinet and migrate them to the newly installed cabinet. This should be done carefully to avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The contractor will be required to return to site and rectify any defects that may occur within the defect liability period at no extra cost to the Authority.	
9.	Drawings and documentati on	On completion of the works the contractor <u>MUST</u> provide all the relevant documentation and the LAN schematic diagram for each site.	
10.	Labeling	All the data points and ports on the Patch panels must be well labeled with Printed labels. The patch cords must also be labeled on both ends to match port numbers.	
11.	Testing and Commissioni ng	The Contractor is required to carry out professional tests and provide results both in printed and in soft copy. This shall apply to both copper and fibre.  A joint test and commissioning will be carried out by KRA and the contractor.	

## VI. MINIMUM TECHNICAL SPECIFICATIONS FOR ISIOLO AIRPORT

## 1 Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10 years	
		(bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

## 2 Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 3 Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs Should also be backward compatible to cat 5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

## 4 Minimum Technical Specifications for 1M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 5 Minimum Technical Specifications for 3M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 6 Minimum Technical Specifications for 18U Wall Mount Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	18 U wall-mount data cabinet with a hinged back	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window	
		Rear: Hinged Back	
		Both doors keyed locks for security	
		1.2mm solid sides	
		Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

## 7 Minimum Technical Specifications for 100mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre- punched fixing holes for permanent wall structures	
2.	Size	100mm by 50mm, two compartments	
3.	Length	2.4m	
4.	Gauge	1.2mm	

## 8 Minimum Technical Specifications for 100mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	100mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	
5.	Gauge	1.2mm	

## 9 Minimum Technical Specifications for 1.5KVA Rack-Mounted UPS

	Feature	Minimum Requirement	Bidders Response			
	Brand and Model	Internationally recognized brand (bidder must specify brand and model)				
	Output					
1.	Output Power Capacity	900 Watts / 1500 VA				
2.	Max Configurable Power	900 Watts / 1500 VA				
3.	Nominal Output Voltage	230V				
4.	Output Voltage Distortion	Less than 5% at full load				
5.	Output Frequency (sync to mains)	47 - 53 Hz for 50 Hz nominal, 57 - 63 Hz for 60 Hz nominal				
6.	Topology	Line interactive				
7.	Waveform Type	Stepped approximation to a Sine wave				
8.	Output Connections	Four (4) IEC 320 C13 Two (2) IEC jumpers				
		Input				
9.	Nominal Input Voltage	230V				
10.	Input Frequency	50/60 Hz +/- 3 Hz (auto sensing)				
11.	Input Connections	IEC-320 C14				
12.	Battery Type	Maintenance free sealed lead-acid with suspended electrolyte, leak proof				
13.	Input voltage range for main operations	180 - 287V				
14.	Input voltage adjustable range for mains operation	170 - 300V				
15.	Typical recharge time	3 hour(s)				
16.	Typical Backup Time at Half Load	20.9 minutes (432.5 Watts)				
17.	Typical Backup Time at Full Load	7.6 minutes (865 Watts)				
		Communications & Manager	nent			
18.	Interface Ports	RJ-45 Serial, USB				
19.	Control panel	Multi-function LCD status and control console				

	Feature	Minimum Requirement	Bidders Response
20.	Audible Alarm	Alarm when on battery : distinctive low battery alarm : configurable delays	
		Surge Protection and Filteri	ing
21.	Surge energy rating	459Joules	
22.	Filtering	Full time multi-pole noise filtering: 0.3% IEEE surge let-through: zero clamping response time: meets UL 1449	
23.	Data Line filtering	RJ-45 modem/Fax/DSL/10-100 Base-T protection	
24.	Standard Warranty	2 years repair or replace	
25.	Accessories	Power cords (at least 1.83M), CD with software, Documentation CD, Rack Mounting brackets, Smart UPS signaling RS-232 cable, USB cable, User Manual	

#### 10 TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES.

#### **The Scope of Works**

The successful bidder shall be required to carry out the following works; Installation of new LAN for KRA Isiolo Airport Station. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc. The fibre works entail the installation of indoor or outdoor fibre cables to interconnect floors within the same building or offices within the same campus. Fibre installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

## Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per the LAN design and the engineer's instructions. All cables must run through the trunkings.	
2.	Horizontal cabling	The horizontal cabling should be done neatly and professionally as per the LAN design and the engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre. Installation of fibre should be carried out according to the instructions of the network engineer on site. At least 6 cores must be terminated for each side of a cable (i.e. 12 terminations).	
4.	Tools & accessories	The contractor must have all the tools and accessories required to install and test Local area Networks (LANs).	
5.	Quality of works	The contractor is required to provide high standard installation service and quality workmanship. Cable management must also be neatly done.  The trunking joints must flush and with no gapes.	

		Knockouts must be installed neatly with no gapes	
		or spaces.	
		The knockouts <b>MUST</b> be of the same shade as that	
		of the trunkings.	
6.	Old	The contractor will be required to carefully	
	cable/trunkin	uninstall old cabling and/or trunking in areas	
	g	where the LAN is undergoing an overhaul. This	
	uninstallatio	should be done neatly to avoid tampering with the	
	n	wall painting and cable/trunking to be reused.	
7.	Equipment	The contractor will be required to carefully	
	migration	uninstall equipment from the old cabinet and	
		migrate them to the newly installed cabinet. This	
		should be done carefully to avoid damaging the	
		equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The	
		contractor will be required to return to site and	
		rectify any defects that may occur within the defect	
		liability period at no extra cost to the Authority.	
9.	Drawings	On completion of the works the contractor <b>MUST</b>	
	and	provide all the relevant documentation and the	
	documentati	LAN schematic diagram for each site.	
	on	, and the second	
10.	Labeling	All the data points and ports on the Patch panels	
		must be well labeled with Printed labels. The patch	
		cords must also be labeled on both ends to match	
		port numbers.	
11.	Testing and	The Contractor is required to carry out	
	Commissioni	professional tests and provide results both in	
	ng	printed and in soft copy. This shall apply to both	
	_	copper and fibre.	
		A joint test and commissioning will be carried out	
		by KRA and the contractor.	

#### VII. MINIMUM TECHNICAL SPECIFICATIONS FOR NYERI

## 1 Minimum Technical Specifications for 12 Core Multimode Armored Fiber Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years(bidder must specify brand)	
2.	Jacket characteristics	Water Blocking Aramid Yarn	
	& Material	Armored	
		PVC	
3.	Mode of operation	Multimode	
4.	Core density	12 cores	
5.	Attenuation (Max)	3.50 dB/km @ 850nm	
6.	Standards	Optical and mechanical performance:	
		IEC 60794-2, IEC 60794-2-20, ISO	
		11801, EN 50173-1	

## 2 Minimum Technical Specifications for 12 Port Multimode Modular Fiber ODF

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Mode of operation	Multimode	
3.	Port density	• 12 ports (24 cores) • Fully populated	
4.	Form Factor	1HU	
5.	Adapter	LC	
6.	Accessories	<ul><li>24 Pigtail connectors</li><li>24 core Splice tray</li><li>30 Heat shrink sleeves</li></ul>	

## 3 Minimum Technical Specifications for 24 Port Multimode Modular Fiber ODF

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Mode of operation	Multimode	
3.	Port density	• 24 ports (48 cores) • Fully populated	
4.	Form Factor	1HU	
5.	Adapter	LC	
6.	Accessories	<ul><li>48 Pigtail connectors</li><li>48 core Splice tray</li><li>60 Heat shrink sleeves</li></ul>	

## 4 Minimum Technical Specifications for 1G Multimode SFP Transceiver Modules

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand (bidder must specify brand )	
2.	Mode of operation	Multimode	
3.	Compatibility	Must be compatible with Cisco switches	
4.	Form Factor	Small pluggable form factor	

	Feature	Minimum Requirements	Bidder's response
5.	Capacity	1 Gigabyte (1G)	

## 5 Minimum Technical Specifications for 1M LC-LC Multimode Fiber Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10 years.	
2.	Mode	Multimode <b>OM3 50/125</b>	
3.	Connector	Must be <b>LC-LC</b>	
4.	Length	1m	

## 6 Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10 years	
		(bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

## 7 Minimum Technical Specifications for CAT 6A 48-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	48 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 8 Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to	
		read	

	Feature	Minimum Requirements	Bidder's response
1.	Contact materials	Plated phosphor bronze, stainless steel	
2.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
3.	Current rating	1.5 A	
4.	Contact resistance	20 mΩ	
5.	Insulation resistance	500 ΜΩ	
6.	Panel material	18 gauge cold rolled steel, black e- coated	
7.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
8.	Termination	By Z-tool	

## 9 Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years	
		(bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module	
		installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position)	
		plugs	
		Should also be backward compatible to	
		cat 5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

## 10 Minimum Technical Specifications for 1M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 11 Minimum Technical Specifications for 3M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	

	Feature	Minimum Requirements	Bidder's response
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot	
		to labelling on the faceplates	

## 12 Minimum Technical Specifications for 5M CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	5 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 13 Minimum Technical Specifications for 22U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized,	
		matured brand	
2.	Form Factor	22 U floor standing standard data	
		cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window	
		Rear door: high-flow mesh	
		Both doors keyed locks for security	
		1.2mm solid sides	
		Installed axial fan kits	
5.	Power outlets in the	6-Way universal PDU 3A/220 - 240	
	cabinet	V AC earthed and fused with	
		shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic	
		horizontal Dual-sided cable	
		managers	

## 14 Minimum Technical Specifications for 32U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	32 U floor standing standard data cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window Rear door: high-flow mesh Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

#### 15 Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre- punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4 M	
4.	Gauge	1.2mm	

## 16 Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	
5.	Gauge	1.2mm	

## 17 Minimum Technical Specifications for 200mmx50mm Perforated Cable Trays

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Perforated galvanized tray	
2.	Length	2.4 M	
3.	Size	200mm by 50mm	
4.	Gauge	2mm thick	

## 18 Minimum Technical Specifications for Rawl Bolts M10 MM

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Steel threaded rods	
2.	Size	M10	
3.	Packaging	Packets of 100pcs	

## 19 Minimum Technical Specifications for 300mm Trapeze Hanger

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Galvanize steel	
2.	Rod hole size	12mm at the ends	
3.	Туре	Flat	
4.	Length	300mm	
5.	Width	50mm	
6.	Thickness	3mm	

#### 20 Minimum Technical Specifications for M10 Nuts with Washers

	Feature	<b>Minimum Requirements</b>	Bidder's Response
1.	Material	Steel	
2.	Size	• Nuts M10	
		• Washers M10	
3.	Packaging	Packets of 100pcs	

#### 21 Minimum Technical Specifications for 1m Threaded Rods

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Steel threaded rods	
2.	Length	1m	
3.	Size	M10	

#### 22 TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### The Scope of Works

The successful bidder shall be required to carry out the following works; Installation of new LAN for KRA Nyeri Station. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc. The fibre works entail the installation of indoor or outdoor fibre cables to interconnect floors within the same building or offices within the same campus. Fibre installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

## Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation.

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly	2.1007 5 1105 6 2.150
		as per the LAN design and the engineer's	
		instructions.	
	** ' . 1	All cables must run through the trunkings.	
2.	Horizontal	The horizontal cabling should be done neatly	
	cabling	and professionally as per the LAN design and	
		the engineer's instructions on site.	
3.	Vertical	The backbone is typically done using fibre.	
	cabling	Installation of fibre should be carried out	
		according to the instructions of the network	
		engineer on site. At least 6 cores must be	
		terminated for each side of a cable (i.e. 12	
		terminations).	
4.	Tools &	The contractor must have all the tools and	
	accessories	accessories required to install and test Local	
		area Networks (LANs).	
5.	Quality of	The contractor is required to provide high	
	works	standard installation service and quality	
		workmanship. Cable management must also	
		be neatly done.	
		The trunking joints must flush and with no	
		gapes. Knockouts must be installed neatly	
		with no gapes or spaces.	
		The knockouts <b>MUST</b> be of the same shade as	
		that of the trunkings.	
6.	Old	The contractor will be required to carefully	
	cable/trunking	uninstall old cabling and/or trunking in areas	
	uninstallation	where the LAN is undergoing an overhaul.	

		This should be done neatly to avoid tampering with the wall painting and cable/trunking to be reused.	
7.	1 1	The contractor will be required to	
	migration	carefully uninstall equipment from the	
		old cabinet and migrate them to the newly	
		installed cabinet. This should be done	
		carefully to avoid damaging the	
0	TA7	equipment.	
8.	Warranty	The defect liability period shall be one (1) year.	
		The contractor will be required to return to site and rectify any defects that may occur	
		within the defect liability period at no extra	
		cost to the Authority.	
9.		On completion of the works the contractor	
	documentation	MUST provide all the relevant	
		documentation and the LAN schematic	
	т.11:	diagram for each site.	
10	o. Labeling	All the data points and ports on the Patch panels must be well labeled with Printed	
		labels. The patch cords must also be labeled on	
		both ends to match port numbers.	
11	. Testing and	The Contractor is required to carry out	
	Commissioning	professional tests and provide results both in	
		printed and in soft copy. This shall apply to	
		both copper and fibre.	
		A joint test and commissioning will be carried	
	ı	out by KRA and the contractor.	l

#### VIII. MINIMUM TECHNICAL SPECIFICATIONS FOR NANYUKI

## 1. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	<b>Minimum Requirements</b>	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10 years	
		(bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

## 2. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs Should also be backward compatible to cat 5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

## 3. Minimum Technical Specifications for 1M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 4. Minimum Technical Specifications for 3M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	

	Feature	Minimum Requirements	Bidder's response
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

#### 5. Minimum Technical Specifications for 100mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre- punched fixing holes for permanent wall structures	
2.	Size	100mm by 50mm, two compartments	
3.	Length	2.4 M	
4.	Gauge	1.2mm	

#### 6. Minimum Technical Specifications for 100mmx50mm Curved Floor Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre- punched fixing holes for permanent wall structures	
2.	Size	100mm by 50mm, two compartments	
3.	Form	Curved	
4.	Length	2.4 M	
5.	Gauge	1.2mm	

#### 7. Minimum Technical Specifications for 100mm Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Width	100mm	
3.	Compatibility	Compatible with 200mm by 50mm trunking	
4.	Gauge	1.2mm	

#### 8. Minimum Technical Specifications for 100mm Pedestal Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	<ul> <li>Powder coated metal trunking with pre-punched fixing holes for permanent floor structures.</li> <li>Rounded corners.</li> </ul>	
2.	Size	100mm	
3.	Outlets	<ul><li>4 single gang data outlet</li><li>4 dual gang power outlet</li></ul>	
4.	Height	400mm	
5.	Gauge	1.2mm	

#### 9. Minimum Technical Specifications for Single Gang Blank Faceplates

	Feature	Minimum Requirements	Bidder's Response
1.	Size	Single gang	
2.	Colour	White	
3.	Material	High impact plastic (ABS UL 94V-0 compliant)	
4.	Assembly	Blank single gang complete with screws	

#### 10. Minimum Technical Specifications for Double Gang Blank Faceplates

	Feature	Minimum Requirements	Bidder's Response
1.	Size	Double gang	
2.	Colour	White	
3.	Material	High impact plastic (ABS UL 94V-0 compliant)	
4.	Assembly	Blank double gang complete with screws	

#### 11. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### The Scope of Works

The successful bidder shall be required to carry out the following works; Revamping of the existing LAN for KRA Nanyuki station. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation.

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as	
		per the LAN design and the engineer's	
		instructions.	
	Horizontal	All cables must run through the trunkings.	
2.	cabling	The horizontal cabling should be done neatly and professionally as per the LAN design and the	
	Cabillig	engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre.	
٥٠	vertical caping	Installation of fibre should be carried out	
		according to the instructions of the network	
		engineer on site. At least 6 cores must be	
		terminated for each side of a cable (i.e. 12	
		terminations).	
4.	Tools &	The contractor must have all the tools and	
	accessories	accessories required to install and test Local area	
	0 11 6 1	Networks (LANs).	
5.	Quality of works	The contractor is required to provide high	
		standard installation service and quality workmanship. Cable management must also be	
		neatly done.	
		The trunking joints must flush and with no gapes.	
		Knockouts must be installed neatly with no gapes	
		or spaces.	
6.	Old	The contractor will be required to carefully	
	cable/trunking	uninstall old cabling and/or trunking in areas	
	uninstallation	where the LAN is undergoing an overhaul. This	
		should be done neatly to avoid tampering with	
		the wall painting and cable/trunking to be	
		reused.	

7.	Equipment	The contractor will be required to carefully	
	migration	uninstall equipment from the old cabinet and	
		migrate them to the newly installed cabinet. This	
		should be done carefully to avoid damaging the	
		equipment.	
8.	Warranty	The defect liability period shall be one (1) year.	
		The contractor will be required to return to site	
		and rectify any defects that may occur within the	
		defect liability period at no extra cost to the	
		Authority.	
9.	Drawings and	On completion of the works the contractor	
	documentation	<b>MUST</b> provide all the relevant documentation	
		and the LAN schematic diagram for each site.	
10.	Labeling	All the data points and ports on the Patch panels	
		must be well labeled with Printed labels. The	
		patch cords must also be labeled on both ends to	
		match port numbers.	
11.	Testing and	The Contractor is required to carry out	
	Commissioning	professional tests and provide results both in	
		printed and in soft copy. This shall apply to both	
		copper and fibre.	
		A joint test and commissioning will be carried out	
		by KRA and the contractor.	

# **B. LOT II TECHNICAL SPECIFICATIONS**

#### I. MINIMUM TECHNICAL SPECIFICATIONS FOR ELDORET KIPTAGICH HOUSE

## 1 Minimum Technical Specifications for 12 Core Multimode Armored Fiber Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years(bidder must specify brand)	
2.	Jacket	Water Blocking Aramid Yarn	
	characteristics &	Armored	
	Material	PVC	
3.	Mode of operation	Multimode	
4.	Core density	12 cores	
5.	Attenuation (Max)	3.50 dB/km @ 850nm	
6.	Standards	Optical and mechanical performance:	
		IEC 60794-2, IEC 60794-2-20, ISO	
		11801, EN 50173-1	

## 2 Minimum Technical Specifications for 12 Port Multimode Modular Fiber ODF

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand	
2.	Mode of operation	Multimode	
3.	Port density	• 12 ports (24 cores)	
		Fully populated	
4.	Form Factor	1HU	
5.	Adapter	LC	
6.	Accessories	• 24 Pigtail connectors	
		• 24 core Splice tray	
		• 30 Heat shrink sleeves	

## 3 Minimum Technical Specifications for 48 Port Multimode Modular Fiber ODF

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Mode of operation	Multimode	
3.	Port density	• 48 ports (96 cores) • Fully populated	
4.	Form Factor	1HU	
5.	Adapter	LC	
6.	Accessories	<ul><li>96 Pigtail connectors</li><li>96 core Splice tray</li><li>120 Heat shrink sleeves</li></ul>	

## 4 Minimum Technical Specifications for 1G Multimode SFP Transceiver Modules

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand (bidder must specify brand )	
2.	Mode of operation	Multimode	
3.	Compatibility	Must be compatible with Cisco switches	

	Feature	Minimum Requirements	Bidder's response
4.	Form Factor	Small pluggable form factor	
5.	Capacity	1 Gigabyte (1G)	

# 5 Minimum Technical Specifications for 1M LC-LC Multimode Fiber Patch Cords

	Feature	<b>Minimum Requirements</b>	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10 years.	
2.	Mode	Multimode <b>OM3 50/125</b>	
3.	Connector	Must be <b>LC-LC</b>	
4.	Length	1m	

## 6 Minimum Technical Specifications for 3M LC-LC Multimode Fiber Patch Cords

	Feature	<b>Minimum Requirements</b>	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10 years.	
2.	Mode	Multimode <b>OM3 50/125</b>	
3.	Connector	Must be <b>LC-LC</b>	
4.	Length	3m	

# 7 Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

# 8 Minimum Technical Specifications for CAT 6A 48-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	48 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

# 9 Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 10 Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs Should also be backward compatible to cat 5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

# 11 Minimum Technical Specifications for 1M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	

	Feature	Minimum Requirements	Bidder's response
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 12 Minimum Technical Specifications for 3M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

# 13 Minimum Technical Specifications for 5M CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	5 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 14 Minimum Technical Specifications for 22U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand	
2.	Form Factor	22 U floor standing standard data	
		cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window	
		Rear door: high-flow mesh	
		Both doors keyed locks for security	
		1.2mm solid sides	
		Installed axial fan kits	
5.	Power outlets in the	6-Way universal PDU 3A/220 - 240 V	
	cabinet	AC earthed and fused with shutters	
	0.11	P' (-) ' C II 11 1 + 11'	
6.	Cable manager	Five (5) pieces of 1U black metallic	
		horizontal Dual-sided cable managers	

# 15 Minimum Technical Specifications for 32U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	32 U floor standing standard data cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window Rear door: high-flow mesh Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

# 16 Minimum Technical Specifications for 50mmx25mm Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre- punched fixing holes for permanent wall structures	
2.	Size	50mm by 25mm	
3.	Length	2.4m	
4.	Gauge	1.2mm	

## 17 Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre- punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4 M	
4.	Gauge	1.2mm	

# 18 Minimum Technical Specifications for 100mmx50mm Curved Floor Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre- punched fixing holes for permanent wall structures	
2.	Size	100mm by 50mm, two compartments	
3.	Form	Curved	
4.	Length	2.4 M	
5.	Gauge	1.2mm	

## 19 Minimum Technical Specifications for 100mm Pedestal Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	<ul> <li>Powder coated metal trunking with pre-punched fixing holes for permanent floor structures.</li> <li>Rounded corners.</li> </ul>	
2.	Size	100mm	
3.	Outlets	<ul><li>4 single gang data outlet</li><li>4 dual gang power outlet</li></ul>	
4.	Height	400mm	
5.	Gauge	1.2mm	

## 20 Minimum Technical Specifications for 200mmx50mm Perforated cable trays

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Perforated galvanized tray	
2.	Length	2.4 M	
3.	Size	200mm by 50mm	
4.	Gauge	2mm thick	

## 21 Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	
5.	Gauge	1.2mm	

## 22 Minimum Technical Specifications for Single Gang Blank Faceplates

	Feature	Minimum Requirements	Bidder's Response
1.	Size	Single gang	
2.	Colour	White	
3.	Material	High impact plastic (ABS UL 94V-0 compliant)	
4.	Assembly	Blank single gang complete with screws	

#### 23 Minimum Technical Specifications for Double Gang Blank Faceplates

	Feature	Minimum Requirements	Bidder's Response
1.	Size	Double gang	
2.	Colour	White	
3.	Material	High impact plastic (ABS UL 94V-0 compliant)	

Ī	4.	Assembly	Blank double gang complete with
			screws

## 24 Minimum Technical Specifications for 1m Threaded Rods

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Steel threaded rods	
2.	Length	1m	
3.	Size	M10	

#### 25 Minimum Technical Specifications for 300mm Trapeze Hanger

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Galvanize steel	
2.	Rod hole size	12mm at the ends	
3.	Туре	Flat	
4.	Length	300mm	
5.	Width	50mm	
6.	Thickness	3mm	

## 26 Minimum Technical Specifications for Rawl Bolts M10 MM

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Steel threaded rods	
2.	Size	M10	
3.	Packaging	Packets of 100pcs	

## 27 Minimum Technical Specifications for M10 Nuts with Washers

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Steel	
2.	Size	• Nuts M10	
		• Washers M10	
3.	Packaging	Packets of 100pcs	

## 28 Minimum Technical Specifications for 1.5KVA Rack-Mounted UPS

	Feature	Minimum Requirement	Bidders Response
	Brand and Model	Internationally recognized brand (bidder must specify brand and model)	
		Output	
1.	Output Power Capacity	900 Watts / 1500 VA	
2.	Max Configurable Power	900 Watts / 1500 VA	
3.	Nominal Output Voltage	230V	
4.	Output Voltage Distortion	Less than 5% at full load	
5.		47 - 53 Hz for 50 Hz nominal, 57 - 63 Hz for 60 Hz nominal	
6.	Topology	Line interactive	

	Feature	Minimum Requirement	Bidders Response
7.	Waveform Type	Stepped approximation to a Sine wave	
8.	Output Connections	Four (4) IEC 320 C13 Two (2) IEC jumpers	
		Input	
9.	Nominal Input Voltage	230V	
10.	Input Frequency	50/60 Hz +/- 3 Hz (auto sensing)	
11.	Input Connections	IEC-320 C14	
12.	Battery Type	Maintenance free sealed lead-acid with suspended electrolyte, leak proof	
13.	Input voltage range for main operations	180 - 287V	
14.	Input voltage adjustable range for mains operation	170 - 300V	
15.	Typical recharge time	3 hour(s)	
16.	Typical Backup Time at Half Load	20.9 minutes (432.5 Watts)	
17.	Typical Backup Time at Full Load	7.6 minutes (865 Watts)	
	-	Communications & Manager	ment
18.	Interface Ports	RJ-45 Serial, USB	
19.	Control panel	Multi-function LCD status and control console	
20.	Audible Alarm	Alarm when on battery : distinctive low battery alarm : configurable delays	
		Surge Protection and Filter	ring
21.	Surge energy rating	459Joules	
22.	Filtering	Full time multi-pole noise filtering : 0.3% IEEE surge let-through : zero clamping response time : meets UL 1449	
23.	Data Line filtering	RJ-45 modem/Fax/DSL/10-100 Base-T protection	
24.	Standard Warranty	2 years repair or replace	
25.	Accessories	Power cords (at least 1.83M), CD with software, Documentation CD, Rack Mounting brackets, Smart UPS signaling RS-232 cable, USB cable, User Manual	

#### 29 TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### **The Scope of Works**

The successful bidder shall be required to carry out the following works; Installation of new LAN for KRA Eldoret Kiptagich House. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc. The fibre works entail the installation of indoor or outdoor fibre cables to interconnect floors within the same building or

offices within the same campus. Fibre installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation.

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per the	
		LAN design and the engineer's instructions.	
		All cables must run through the trunkings.	
2.	Horizontal	The horizontal cabling should be done neatly and	
	cabling	professionally as per the LAN design and the engineer's	
		instructions on site.	
3.	Vertical	The backbone is typically done using fibre. Installation	
	cabling	of fibre should be carried out according to the instructions of the network engineer on site. At least 6	
		cores must be terminated for each side of a cable (i.e. 12	
		terminations).	
4.	Tools &	The contractor must have all the tools and accessories	
	accessories	required to install and test Local area Networks (LANs).	
5.	Quality of	The contractor is required to provide high standard	
	works	installation service and quality workmanship. Cable	
		management must also be neatly done.	
		The trunking joints must flush and with no gapes. Knockouts must be installed neatly with no gapes or	
		spaces.	
		The knockouts <b>MUST</b> be of the same shade as that of	
		the trunkings.	
6.	Old	The contractor will be required to carefully uninstall old	
	cable/trunking	cabling and/or trunking in areas where the LAN is	
	uninstallation	undergoing an overhaul. This should be done neatly to avoid tampering with the wall painting and	
		cable/trunking to be reused.	
7.	Equipment	The contractor will be required to carefully	
	migration	uninstall equipment from the old cabinet and	
	G	migrate them to the newly installed cabinet. This	
		should be done carefully to avoid damaging the	
		equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The	
		contractor will be required to return to site and rectify any defects that may occur within the defect liability	
		period at no extra cost to the Authority.	
9.	Drawings and	On completion of the works the contractor <b>MUST</b>	
	documentation	provide all the relevant documentation and the LAN	
	~ 1 1'	schematic diagram for each site.	
10.	Labeling	All the data points and ports on the Patch panels must	
		be well labeled with Printed labels. The patch cords must also be labeled on both ends to match port	
		numbers.	
11.	Testing and	The Contractor is required to carry out professional	
	Commissioning	tests and provide results both in printed and in soft	
		copy. This shall apply to both copper and fibre.	
		A joint test and commissioning will be carried out by	
		KRA and the contractor.	

#### II. MINIMUM TECHNICAL SPECIFICATIONS FOR ELDORET KPC

## 1. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years (bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

## 2. Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

# 3. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs	

	Feature	Minimum Requirements	Bidder's response
		Should also be backward compatible	
		to cat 5e	
10.	Shield	Hinged cable retention/ grounding	
		clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

# 4. Minimum Technical Specifications for 1M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

# 5. Minimum Technical Specifications for 3M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

# 6. Minimum Technical Specifications for 18U Wall Mount Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.		18 U wall-mount data cabinet with a <b>hinged back</b>	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window  Rear: Hinged Back Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

## 7. Minimum Technical Specifications for 100mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	100mm by 50mm, two compartments	
3.	Length	2.4 M	
4.	Gauge	1.2mm	

## 8. Minimum Technical Specifications for 100mmx50mm Perforated Cable Trays

	Feature	<b>Minimum Requirements</b>	Bidder's Response
1.	Material	Perforated galvanized tray	
2.	Length	2.4 M	
3.	Size	100mm by 50mm	
4.	Gauge	2mm thick	

## 9. Minimum Technical Specifications for 100mm Single Gang Service Plates

	Feature	<b>Minimum Requirements</b>	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	100mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 100mm by 50mm trunking	
5.	Gauge	1.2mm	

## 10. Minimum Technical Specifications for 1M Threaded Rods

	Feature	Minimum Requirements	Bidder's response
1.	Material	Steel threaded rods	
2.	Length	1m	
3.	Size	M10	

# 11. Minimum Technical Specifications for 150MM Trapeze Hanger

	Feature	<b>Minimum Requirements</b>	Bidder's response
1.	Material	Galvanize steel	
2.	Rod hole size	12mm at the ends	
3.	Type	Flat	
4.	Length	150mm	
5.	Width	50mm	
6.	Thickness	3mm	

#### 12. Minimum Technical Specifications for Rawl Bolts M10

	Feature	Minimum Requirements	Bidder's response
1.	Material	Steel threaded rods	
2.	Size	M10	
3.	Packaging	Packets of 100pcs	

#### 13. Minimum Technical Specifications for M10 Nuts with Washers

	Feature	Minimum Requirements	Bidder's response
1.	Material	Steel	
2.	Size	Nuts M10     Washers M10	
3.	Packaging	Packets of 100pcs	

#### 14. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### **The Scope of Works**

The successful bidder shall be required to carry out the following works; Installation of new LAN for KRA Eldoret KPC Office. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labelling, Drawings and Documentation

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed	
		neatly as per the LAN design and the	
		engineer's instructions.	
		All cables must run through the	
		trunkings.	
2.	Horizontal cabling	The horizontal cabling should be done	
		neatly and professionally as per the LAN	
		design and the engineer's instructions on	
		site.	
3.	Vertical cabling	The backbone is typically done using	
		fibre. Installation of fibre should be	
		carried out according to the instructions	
		of the network engineer on site. At least 6	
		cores must be terminated for each side of	
		a cable (i.e. 12 terminations).	
4.	Tools & accessories	The contractor must have all the tools	
		and accessories required to install and	
		test Local Area Networks (LANs).	

5.	Quality of works	The contractor is required to provide high standard installation service and quality workmanship. Cable management must also be neatly done. The trunking joints must flush and with no gapes. Knockouts must be installed neatly with no gapes or spaces.	
6.	Old cable/trunking uninstallation	The contractor will be required to carefully uninstall old cabling and/or trunking in areas where the LAN is undergoing an overhaul. This should be done neatly to avoid tampering with the wall painting and cable/trunking to be reused.	
7.	Equipment migration	The contractor will be required to carefully uninstall equipment from the old cabinet and migrate them to the newly installed cabinet. This should be done carefully to avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The contractor will be required to return to site and rectify any defects that may occur within the defect liability period at no extra cost to the Authority.	
9.	Drawings and documentation	On completion of the works the contractor <u>MUST</u> provide all the relevant documentation and the LAN schematic diagram for each site.	
10.	Labelling	All the data points and ports on the Patch panels must be well labeled with Printed labels. The patch cords must also be labeled on both ends to match port numbers.	
11.	Testing and Commissioning	The Contractor is required to carry out professional tests and provide results both in printed and in soft copy. This shall apply to both copper and fiber.  A joint test and commissioning will be carried out by KRA and the contractor.	

# III. MINIMUM TECHNICAL SPECIFICATIONS FOR ELDORET AIRPORT (CARGO, SCANNER, TERMINAL & K9 OFFICES)

#### 1. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years (bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

#### 2. Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 3. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs	

	Feature	Minimum Requirements	Bidder's response
		Should also be backward compatible	
		to cat 5e	
10.	Shield	Hinged cable retention/ grounding	
		clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

# 4. Minimum Technical Specifications for 1M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 5. Minimum Technical Specifications for 3M CAT 6A Ethernet Patch cords

	Feature	<b>Minimum Requirements</b>	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

# 6. Minimum Technical Specifications for 12U Wall Mount Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	12 U wall-mount data cabinet with a <b>hinged back</b>	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window  Rear: Hinged Back Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 VAC earthed and fused with shutters	
6.	Cable manager	Three (3) pieces of 1U black metallic horizontal Dual-sided cable managers	

## 7. Minimum Technical Specifications for 22U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	22 U floor standing standard data cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window Rear door: high-flow mesh Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 VAC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

## 8. Minimum Technical Specifications for 50mmx25mm Trunking

	Feature	<b>Minimum Requirements</b>	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	50mm by 25mm	
3.	Length	2.4m	
4.	Gauge	1.2mm	

## 9. Minimum Technical Specifications for 100mmx50mm Partitioned Trunking

	Feature	Minimum Requirements I	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	100mm by 50mm, two compartments	
3.	Length	2.4 M	
4.	Gauge	1.2mm	

# 10. Minimum Technical Specifications for 100mmx50mm Curved Floor Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	100mm by 50mm, two compartments	
3.	Form	Curved	
4.	Length	2.4m	
5.	Gauge	1.2mm	

#### 11. Minimum Technical Specifications for 100mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	100mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 100mm by 50mm trunking	
5.	Gauge	1.2mm	

#### 12. Minimum Technical Specifications for Single Gang Pattress Box

	Feature	Minimum Requirements	Bidder's Response
1.	Size	150mm x 75mm x 35mm	
2.	Material	Brushed Steel or powder coated steel	
3.	Assembly	Single Gang complete with screws	

#### 13. Minimum Technical Specifications for Single Gang Blank Faceplates

	Feature	Minimum Requirements	Bidder's Response
1.	Size	Single gang	
2.	Colour	White	
3.	Material	High impact plastic (ABS UL 94V-0 compliant)	
4.	Assembly	Blank single gang complete with screws	

#### 14. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### **The Scope of Works**

The successful bidder shall be required to carry out the following works; Installation of new LAN for KRA Eldoret Airport Offices (Cargo, Scanner, Terminal & K9). The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labelling, Drawings and Documentation

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed	
		neatly as per the LAN design and the	
		engineer's instructions.	
		All cables must run through the trunkings.	
2.	Horizontal	The horizontal cabling should be done	
	cabling	neatly and professionally as per the LAN	
		design and the engineer's instructions on	
	Mantinal	site.	
3.	Vertical cabling	The backbone is typically done using fibre. Installation of fibre should be carried out	
	Cabillig	according to the instructions of the	
		network engineer on site. At least 6 cores	
		must be terminated for each side of a cable	
		(i.e. 12 terminations).	
4.	Tools &	The contractor must have all the tools and	
	accessories	accessories required to install and test	
L		Local Area Networks (LANs).	
5.	Quality of	The contractor is required to provide high	
	works	standard installation service and quality	
		workmanship. Cable management must	
		also be neatly done.	
		The trunking joints must flush and with no	
		gapes. Knockouts must be installed neatly	
	014	with no gapes or spaces.	
6.	Old cable/trunki	The contractor will be required to carefully	
	, , , , , , , , , , , , , , , , , , ,	uninstall old cabling and/or trunking in areas where the LAN is undergoing an	
	ng uninstallatio	overhaul. This should be done neatly to	
	n	avoid tampering with the wall painting and	
	12	cable/trunking to be reused.	
7.	Equipment	The contractor will be required to carefully	
	migration	uninstall equipment from the old cabinet	
		and migrate them to the newly installed	
		cabinet. This should be done carefully to	
		avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1)	
		year. The contractor will be required to	
		return to site and rectify any defects that may occur within the defect liability period	
		at no extra cost to the Authority.	
9.	Drawings	On completion of the works the contractor	
٦٠	and	MUST provide all the relevant	
	documentati	documentation and the LAN schematic	
	on	diagram for each site.	
10.	Labelling	All the data points and ports on the Patch	
	_	panels must be well labeled with Printed	
		labels. The patch cords must also be	
		labeled on both ends to match port	
<u> </u>	m. ut. 1	numbers.	
11.	Testing and	The Contractor is required to carry out	
	Commissioni	professional tests and provide results both in printed and in soft copy. This shall apply	
	ng	to both copper and fiber.	
		A joint test and commissioning will be	
		carried out by KRA and the contractor.	
	L	carried out by Rear and the contractor.	

#### IV. MINIMUM TECHNICAL SPECIFICATIONS FOR LODWAR

## 1 Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	<b>Minimum Requirements</b>	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years (bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

## 2 Minimum Technical Specifications for CAT 6A 48-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	48 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 3 Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs Should also be backward compatible	

	Feature	Minimum Requirements	Bidder's response
		to cat 5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

#### 4 Minimum Technical Specifications for 1M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

#### 5 Minimum Technical Specifications for 3M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 6 Minimum Technical Specifications for 5M CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	5 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

# 7 Minimum Technical Specifications for 32U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand	
2.	Form Factor	32 U floor standing standard data	
		cabinet	
3.	Dimension	600x800mm	

	Feature	Minimum Requirements	Bidder's response
4.	Construction	Front door: with glass window	
		Rear door: high-flow mesh	
		Both doors keyed locks for security	
		1.2mm solid sides	
		Installed axial fan kits	
5.	Power outlets in the	6-Way universal PDU 3A/220 - 240	
	cabinet	V AC earthed and fused with	
		shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic	
		horizontal Dual-sided cable	
		managers	

## 8 Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4 M	
4.	Gauge	1.2mm	

# 9 Minimum Technical Specifications for 75mmx50mm Curved Floor Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	75mm by 50mm, two compartments	
3.	Form	Curved	
4.	Length	2.4 M	
5.	Gauge	1.2mm	

## 10 Minimum Technical Specifications for 100mm Pedestal Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	<ul> <li>Powder coated metal trunking with pre-punched fixing holes for permanent floor structures.</li> <li>Rounded corners.</li> </ul>	
2.	Size	100mm	
3.	Outlets	<ul><li>4 single gang data outlet</li><li>4 dual gang power outlet</li></ul>	
4.	Height	400mm	
5.	Gauge	1.2mm	

## 11 Minimum Technical Specifications for 100mmx50mm Perforated cable trays

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Perforated galvanized tray	
2.	Length	2.4 M	

	Feature	Minimum Requirements	Bidder's Response
3.	Size	100mm by 50mm	
4.	Gauge	2mm thick	

## 12 Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	
5.	Gauge	1.2mm	

## 13 Minimum Technical Specifications for Single Gang Blank Faceplates

	Feature	Minimum Requirements	Bidder's Response
1.	Size	Single gang	
2.	Colour	White	
3.	Material	High impact plastic (ABS UL 94V-0	
		compliant)	
4.	Assembly	Blank single gang complete with	
		screws	

## 14 Minimum Technical Specifications for Double Gang Blank Faceplates

	Feature	Minimum Requirements	Bidder's Response
1.	Size	Double gang	
2.	Colour	White	
3.	Material	High impact plastic (ABS UL 94V-0	
		compliant)	
4.	Assembly	Blank double gang complete with	
		screws	

## 15 Minimum Technical Specifications for 1m Threaded Rods

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Steel threaded rods	
2.	Length	1m	
3.	Size	M10	

#### 16 Minimum Technical Specifications for 150mm Trapeze Hanger

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Galvanize steel	
2.	Rod hole size	12mm at the ends	
3.	Type	Flat	
4.	Length	150mm	
5.	Width	50mm	
6.	Thickness	3mm	

#### 17 Minimum Technical Specifications for Rawl Bolts M10 MM

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Steel threaded rods	
2.	Size	M10	
3.	Packaging	Packets of 100pcs	

#### 18 Minimum Technical Specifications for M10 Nuts with Washers

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Steel	
2.	Size	• Nuts M10 • Washers M10	
3.	Packaging	Packets of 100pcs	

#### 19 TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### **The Scope of Works**

The successful bidder shall be required to carry out the following works; Installation of new LAN for KRA Lodwar Station. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation.

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per	•
	8	the LAN design and the engineer's instructions.	
		All cables must run through the trunkings.	
2.	Horizontal	The horizontal cabling should be done neatly and	
	cabling	professionally as per the LAN design and the	
		engineer's instructions on site.	
3.	Vertical	The backbone is typically done using fibre.	
	cabling	Installation of fibre should be carried out according	
		to the instructions of the network engineer on site. At	
		least 6 cores must be terminated for each side of a	
		cable (i.e. 12 terminations).	
4.	Tools &	The contractor must have all the tools and accessories	
	accessories	required to install and test Local area Networks	
		(LANs).	
5.	Quality of	The contractor is required to provide high standard	
	works	installation service and quality workmanship. Cable	
		management must also be neatly done.	
		The trunking joints must flush and with no gapes.	
		Knockouts must be installed neatly with no gapes or	
		spaces.	
		The knockouts <b>MUST</b> be of the same shade as that of	
	01.1	the trunkings.	
6.	Old	The contractor will be required to carefully uninstall	
	cable/trunkin	old cabling and/or trunking in areas where the LAN	
	g	is undergoing an overhaul. This should be done	
	uninstallatio	neatly to avoid tampering with the wall painting and	
	n	cable/trunking to be reused.	
7.	Equipment	The contractor will be required to carefully	
	migration	uninstall equipment from the old cabinet and	
		migrate them to the newly installed cabinet. This	
		should be done carefully to avoid damaging the	
		equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The	
		contractor will be required to return to site and rectify	
		any defects that may occur within the defect liability	
	-	period at no extra cost to the Authority.	
9.	Drawings	On completion of the works the contractor <b>MUST</b>	
	and	provide all the relevant documentation and the LAN	
	documentati	schematic diagram for each site.	
	on		
10.	Labeling	All the data points and ports on the Patch panels must	
		be well labeled with Printed labels. The patch cords	
		must also be labeled on both ends to match port	
		numbers.	
11.	Testing and	The Contractor is required to carry out professional	
	Commissioni	tests and provide results both in printed and in soft	
	ng	copy. This shall apply to both copper and fibre.	
		A joint test and commissioning will be carried out by	
		KRA and the contractor.	

#### V. MINIMUM TECHNICAL SPECIFICATIONS FOR LOKICHOGIO

#### Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized,	
		matured brand, in existence for at	
		least 10 years (bidder must specify	
		brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

#### 2 Minimum Technical Specifications for CAT 6A 48-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	48 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

#### 3 Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8- position) plugs Should also be backward	

	Feature	Minimum Requirements	Bidder's response
		compatible to cat 5e	
10.	Shield	Hinged cable retention/	
		grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

#### 4 Minimum Technical Specifications for 1M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

#### 5 Minimum Technical Specifications for 3M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 6 Minimum Technical Specifications for 5M CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length		
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

#### 7 Minimum Technical Specifications for 18U Wall Mount Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	18 U wall-mount data cabinet with a <b>hinged back</b>	
3.	Dimension	600x800mm	

	Feature	Minimum Requirements	Bidder's response
4.	Construction	Front door: with glass window	
		Rear door: high-flow mesh	
		Both doors keyed locks for security	
		1.2mm solid sides	
		Installed axial fan kits	
5.	Power outlets in the	6-Way universal PDU 3A/220 -	
	cabinet	240 V AC earthed and fused with	
		shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic	
		horizontal Dual-sided cable	
		managers	

#### 8 Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4 M	
4.	Gauge	1.2mm	

#### 9 Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	
5.	Gauge	1.2mm	

#### 10 TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### **The Scope of Works**

The successful bidder shall be required to carry out the following works; Installation of new LAN for KRA Lokichoggio Station. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation.

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per the LAN design and the engineer's instructions. All cables must run through the trunkings.	
2.	Horizontal cabling	The horizontal cabling should be done neatly and professionally as per the LAN design and the engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre. Installation of fibre should be carried out according to the instructions of the network engineer on site. At least 6 cores must be terminated for each side of a cable (i.e. 12 terminations).	
4.	Tools & accessories	The contractor must have all the tools and accessories required to install and test Local area Networks (LANs).	
5.	Quality of works	The contractor is required to provide high standard installation service and quality workmanship. Cable management must also be neatly done.  The trunking joints must flush and with no gapes. Knockouts must be installed neatly with no gapes or spaces.  The knockouts <b>MUST</b> be of the same shade as that of the trunkings.	
6.	Old cable/trunkin g uninstallatio n	The contractor will be required to carefully uninstall old cabling and/or trunking in areas where the LAN is undergoing an overhaul. This should be done neatly to avoid tampering with the wall painting and cable/trunking to be reused.	
7.	Equipment migration	The contractor will be required to carefully uninstall equipment from the old cabinet and migrate them to the newly installed cabinet. This should be done carefully to avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The contractor will be required to return to site and rectify any defects that may occur within the defect liability period at no extra cost to the Authority.	
9.	Drawings and documentati on	On completion of the works the contractor <u>MUST</u> provide all the relevant documentation and the LAN schematic diagram for each site.	
10.	Labeling	All the data points and ports on the Patch panels must be well labeled with Printed labels. The patch cords must also be labeled on both ends to match port numbers.	
11.	Testing and Commissioni ng	The Contractor is required to carry out professional tests and provide results both in printed and in soft copy. This shall apply to both copper and fibre. A joint test and commissioning will be carried out by KRA and the contractor.	

#### VI. MINIMUM TECHNICAL SPECIFICATIONS FOR LOKICHOGIO AIRPORT

#### 1 Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized,	
		matured brand, in existence for at	
		least 10 years (bidder must specify	
		brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

#### 2 Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

#### 3 Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8- position) plugs Should also be backward	

	Feature	Minimum Requirements	Bidder's response
		compatible to cat 5e	
10.	Shield	Hinged cable retention/	
		grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

#### 4 Minimum Technical Specifications for 1M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length		
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

#### 5 Minimum Technical Specifications for 3M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length		
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 6 Minimum Technical Specifications for 5M CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length		
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

#### 7 Minimum Technical Specifications for 22U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	22 U floor standing standard data	
		cabinet	
3.	Dimension	600x800mm	

	Feature	Minimum Requirements	Bidder's response
4.	Construction	Front door: with glass window	
		Rear door: high-flow mesh	
		Both doors keyed locks for security	
		1.2mm solid sides	
		Installed axial fan kits	
5.	Power outlets in the	6-Way universal PDU 3A/220 -	
	cabinet	240 V AC earthed and fused with	
		shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic	
	_	horizontal Dual-sided cable	
		managers	

#### 8 Minimum Technical Specifications for 100mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	100mm by 50mm, two compartments	
3.	Length	2.4 M	
4.	Gauge	1.2mm	

#### 9 Minimum Technical Specifications for 100mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	100mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 100mm by 50mm trunking	
5.	Gauge	1.2mm	

#### 10 TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### **The Scope of Works**

The successful bidder shall be required to carry out the following works; Installation of new LAN for KRA Lokichoggio Airport Station. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation.

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per the LAN design and the engineer's instructions. All cables must run through the trunkings.	
2.	Horizontal cabling	The horizontal cabling should be done neatly and professionally as per the LAN design and the engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre. Installation of fibre should be carried out according to the instructions of the network engineer on site. At least 6 cores must be terminated for each side of a cable (i.e. 12 terminations).	
4.	Tools & accessories	The contractor must have all the tools and accessories required to install and test Local area Networks (LANs).	
5.	Quality of works	The contractor is required to provide high standard installation service and quality workmanship. Cable management must also be neatly done.  The trunking joints must flush and with no gapes. Knockouts must be installed neatly with no gapes or spaces.  The knockouts <b>MUST</b> be of the same shade as that of the trunkings.	
6.	Old cable/trunkin g uninstallatio n	The contractor will be required to carefully uninstall old cabling and/or trunking in areas where the LAN is undergoing an overhaul. This should be done neatly to avoid tampering with the wall painting and cable/trunking to be reused.	
7.	Equipment migration	The contractor will be required to carefully uninstall equipment from the old cabinet and migrate them to the newly installed cabinet. This should be done carefully to avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The contractor will be required to return to site and rectify any defects that may occur within the defect liability period at no extra cost to the Authority.	
9.	Drawings and documentati on	On completion of the works the contractor <u>MUST</u> provide all the relevant documentation and the LAN schematic diagram for each site.	
10.	Labeling	All the data points and ports on the Patch panels must be well labeled with Printed labels. The patch cords must also be labeled on both ends to match port numbers.	
11.	Testing and Commissioni ng	The Contractor is required to carry out professional tests and provide results both in printed and in soft copy. This shall apply to both copper and fibre. A joint test and commissioning will be carried out by KRA and the contractor.	

#### VII. MINIMUM TECHNICAL SPECIFICATIONS FOR KERICHO MAIN OFFICE

#### 1 Minimum Technical Specifications for 12 Core Multimode Armored Fiber Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized,	
		matured brand, in existence for at	
		least 10 years(bidder must specify	
		brand)	
2.	Jacket characteristics	Water Blocking Aramid Yarn	
	& Material	Armored	
		PVC	
3.	Mode of operation	Multimode	
4.	Core density	12 cores	
5.	Attenuation (Max)	3.50 dB/km @ 850nm	
6.	Standards	Optical and mechanical	
		performance: IEC 60794-2, IEC	
		60794-2-20, ISO 11801, EN 50173-	
		1	

## 2 Minimum Technical Specifications for 12 Port Multimode Modular Fiber ODF

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Mode of operation	Multimode	
3.	Port density	• 12 ports (24 cores) • Fully populated	
4.	Form Factor	3 1HU	
5.	Adapter	SC	
6.	Accessories	• 24 Pigtail connectors	
		• 24 core Splice tray	
		• 30 Heat shrink sleeves	

#### 4 Minimum Technical Specifications for 1G Multimode SFP Transceiver Modules

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand (bidder must specify brand )	
2.	Mode of operation	Multimode	
3.	Compatibility	Must be compatible with Cisco switches	
4.	Form Factor	Small pluggable form factor	
5.	Capacity	1 Gigabyte (1G)	

## 5 Minimum Technical Specifications for 1.5m SC-LC Multimode Fiber Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized,	
		matured brand, in existence for at	
		least 10 years.	
2.	Mode	Multimode <b>OM3 50/125</b>	
3.	Connector	Must be <b>SC-LC</b>	
4.	Length	1.5m	

# 6 Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	<b>Minimum Requirements</b>	Bidder's response
1.	Brand	Internationally recognized,	
		matured brand, in existence for	
		at least 10 years (bidder must	
		specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC	
		11801	
6.	Length	305m	

# 7 Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	<b>Minimum Requirements</b>	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 8 Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and	
		model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs	

	Feature	Minimum Requirements	Bidder's response
		Should also be backward compatible	
		to cat 5e	
10.	Shield	Hinged cable retention/ grounding	
		clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

# 9 Minimum Technical Specifications for 1M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 10 Minimum Technical Specifications for 3M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

# 11 Minimum Technical Specifications for 5M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	5 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 12 Minimum Technical Specifications for 22U Free Standing Data Cabinet

	Feature	<b>Minimum Requirements</b>	Bidder's response
1.	Brand	Internationally recognized,	
		matured brand	

	Feature	<b>Minimum Requirements</b>	Bidder's response
2.	Form Factor	22 U Free Standing data cabinet	
3.	Dimension	600x450mm	
4.	Construction	Front door: with glass window Rear door: high-flow mesh Both doors keyed locks for security 1.2mm solid sides	
5.	Power outlets in the cabinet	Installed axial fan kits 4-Way universal PDU 3A/220 - 240 V AC earthed and fused with	
	Capinet	shutters	
6.	Cable manager	Five (4) pieces of 1U black metallic horizontal Dual-sided cable managers	

# 13 Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	
5.	Gauge	1.2mm	

# 14 Minimum Technical Specifications for 1.5KVA Rack-Mounted UPS

	Feature	Minimum Requirement	Bidders Response
	Brand and Model	Internationally recognized brand (bidder must specify brand and model)	
		Output	
1.	Output Power Capacity	900 Watts / 1500 VA	
2.	Max Configurable Power	900 Watts / 1500 VA	
3.	Nominal Output Voltage	230V	
4.	Output Voltage Distortion	Less than 5% at full load	
5.	Output Frequency (sync to mains)	47 - 53 Hz for 50 Hz nominal, 57 - 63 Hz for 60 Hz nominal	
6.	Topology	Line interactive	
7.	Waveform Type	Stepped approximation to a Sine wave	
8.	Output Connections	Four (4) IEC 320 C13 Two (2) IEC jumpers	
		Input	
9.	Nominal Input Voltage	230V	
10.	Input Frequency	50/60 Hz +/- 3 Hz (auto sensing)	
11.	Input Connections	IEC-320 C14	
12.	Battery Type	Maintenance free sealed lead-acid with suspended electrolyte, leak proof	
13.	Input voltage range for main operations	180 - 287V	

	Feature	Minimum Requirement	Bidders Response
14.	Input voltage adjustable range for mains operation	170 - 300V	
15.	Typical recharge time	3 hour(s)	
16.	Typical Backup Time at Half Load	20.9 minutes (432.5 Watts)	
17.	Typical Backup Time at Full Load	7.6 minutes (865 Watts)	
		Communications & Managen	nent
18.	Interface Ports	RJ-45 Serial, USB	
19.	Control panel	Multi-function LCD status and control console	
20.	Audible Alarm	Alarm when on battery : distinctive low battery alarm : configurable delays	
		Surge Protection and Filter	ing
21.	Surge energy rating	459Joules	
22.	Filtering	Full time multi-pole noise filtering : 0.3% IEEE surge let-through : zero clamping response time : meets UL 1449	
23.	Data Line filtering	RJ-45 modem/Fax/DSL/10-100 Base-T protection	
24.	Standard Warranty	2 years repair or replace	
25.	Accessories	Power cords (at least 1.83M), CD with software, Documentation CD, Rack Mounting brackets, Smart UPS signaling RS-232 cable, USB cable, User Manual	

#### 15 TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### The Scope of Works

The successful bidder shall be required to carry out the following works; Installation of new LAN for KRA Kericho TSO station. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc. The fibre works entail the installation of indoor or outdoor fibre cables to interconnect floors within the same building or offices within the same campus. Fibre installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation.

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as	•
	8	per the LAN design and the engineer's	
		instructions.	
		All cables must run through the trunkings.	
2.	Horizontal	The horizontal cabling should be done neatly and	
	cabling	professionally as per the LAN design and the	
	8	engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre.	
	0	Installation of fibre should be carried out	
		according to the instructions of the network	
		engineer on site. At least 6 cores must be	
		terminated for each side of a cable (i.e. 12	
		terminations).	
4.	Tools &	The contractor must have all the tools and	
	accessories	accessories required to install and test Local area	
		Networks (LANs).	
5.	Quality of	The contractor is required to provide high	
	works	standard installation service and quality	
		workmanship. Cable management must also be	
		neatly done.	
		The trunking joints must flush and with no gapes.	
		Knockouts must be installed neatly with no gapes	
		or spaces.	
6.	Old	The contractor will be required to carefully	
	cable/trunking	uninstall old cabling and/or trunking in areas	
	uninstallation	where the LAN is undergoing an overhaul. This	
		should be done neatly to avoid tampering with the	
		wall painting and cable/trunking to be reused.	
7.	Equipment	The contractor will be required to carefully	
	migration	uninstall equipment from the old cabinet and	
		migrate them to the newly installed cabinet. This	
		should be done carefully to avoid damaging the	
	7.7	equipment.	
8.	Warranty	The defect liability period shall be one (1) year.	
		The contractor will be required to return to site	
		and rectify any defects that may occur within the	
		defect liability period at no extra cost to the	
-	Dwaren - 1	Authority.	
9.	Drawings and	On completion of the works the contractor <b>MUST</b>	
	documentation	provide all the relevant documentation and the	
10	Labalin =	LAN schematic diagram for each site.	
10	Labeling	All the data points and ports on the Patch panels	
		must be well labeled with Printed labels. The	
		patch cords must also be labeled on both ends to	
<u></u>	Togting	match port numbers.	
11.	Testing and	The Contractor is required to carry out	
	Commissioning	professional tests and provide results both in	
		printed and in soft copy. This shall apply to both	
		copper and fibre.	
		A joint test and commissioning will be carried out	
		by KRA and the contractor.	

#### VIII. MINIMUM TECHNICAL SPECIFICATIONS FOR NAKURU GENERATION HOUSE

#### 1. Minimum Technical Specifications for 12 Core Multimode Armored Fiber Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized,	
		matured brand, in existence for at	
		least 10 years(bidder must specify	
		brand)	
2.	Jacket characteristics &	Water Blocking Aramid Yarn	
	Material	Armored	
		PVC	
3.	Mode of operation	Multimode	
4.	Core density	12 cores	
5.	Attenuation (Max)	3.50 dB/km @ 850nm	
6.	Standards	Optical and mechanical	
		performance: IEC 60794-2, IEC	
		60794-2-20, ISO 11801, EN 50173-	
		1	

#### 2. Minimum Technical Specifications for 12 Port Multimode Modular Fiber ODF

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Mode of operation	Multimode	
3.	Port density	• 12 ports (24 cores) • Fully populated	
4.	Form Factor	1HU	
5.	Adapter	LC	
6.	Accessories	<ul><li>24 Pigtail connectors</li><li>24 core Splice tray</li><li>30 Heat shrink sleeves</li></ul>	

#### 3. Minimum Technical Specifications for 24 Port Multimode Modular Fiber ODF

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Mode of operation	Multimode	
3.	Port density	• 24 ports (48 cores) • Fully populated	
4.	Form Factor	1HU	
5.	Adapter	LC	
6.	Accessories	<ul><li>48 Pigtail connectors</li><li>48 core Splice tray</li><li>60 Heat shrink sleeves</li></ul>	

# 4. Minimum Technical Specifications for 1G Multimode SFP Transceiver Modules

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand (bidder must specify brand )	
2.	Mode of operation	Multimode	
3.	Compatibility	Must be compatible with Cisco switches	

	Feature	Minimum Requirements	Bidder's response
4.	Form Factor	Small pluggable form factor	
5.	Capacity	1 Gigabyte (1G)	

#### 5. Minimum Technical Specifications for 1M LC-LC Multimode Fiber Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years.	
2.	Mode	Multimode <b>OM3</b> 50/125	
3.	Connector	Must be <b>LC-LC</b>	
4.	Length	1m	

#### 6. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

## 7. Minimum Technical Specifications for CAT 6A 48-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	48 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 8. Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	

	Feature	Minimum Requirements	Bidder's response
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

# 9. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs Should also be backward compatible to cat 5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

# 10. Minimum Technical Specifications for 1M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 11. Minimum Technical Specifications for 3M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

# 12. Minimum Technical Specifications for 5M CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	5 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 13. Minimum Technical Specifications for 22U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	22 U floor standing standard data cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window Rear door: high-flow mesh Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

# 14. Minimum Technical Specifications for 32U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	32 U floor standing standard data cabinet	
3.	Dimension	600x800mm	

	Feature	Minimum Requirements	Bidder's response
4.	Construction	Front door: with glass window	
		Rear door: high-flow mesh	
		Both doors keyed locks for security	
		1.2mm solid sides	
		Installed axial fan kits	
5.	Power outlets in the	6-Way universal PDU 3A/220 -	
	cabinet	240 V AC earthed and fused with	
		shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic	
		horizontal Dual-sided cable	
		managers	

## 15.Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4 M	
4.	Gauge	1.2mm	

## 16. Minimum Technical Specifications for 100mmx50mm Curved Floor Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	100mm by 50mm, two compartments	
3.	Form	Curved	
4.	Length	2.4 M	
5.	Gauge	1.2mm	

# 17. Minimum Technical Specifications for 100mm Pedestal Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	<ul> <li>Powder coated metal trunking with pre-punched fixing holes for permanent floor structures.</li> <li>Rounded corners.</li> </ul>	
2.	Size	100mm	
3.	Outlets	<ul><li>4 single gang data outlet</li><li>4 dual gang power outlet</li></ul>	
4.	Height	400mm	
5.	Gauge	1.2mm	

# 18. Minimum Technical Specifications for 200mmx50mm Perforated cable trays

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Perforated galvanized tray	
2.	Length	2.4 M	
3.	Size	200mm by 50mm	
4.	Gauge	2mm thick	

## 19. Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	
5.	Gauge	1.2mm	

#### 20. Minimum Technical Specifications for 200mm Double Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Double Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	
5.	Gauge	1.2mm	

## 21. Minimum Technical Specifications for Single Gang Blank Faceplates

	Feature	Minimum Requirements	Bidder's Response
1.	Size	Single gang	
2.	Colour	White	
3.	Material	High impact plastic (ABS UL 94V- o compliant)	
4.	Assembly	Blank single gang complete with screws	

#### 22. Minimum Technical Specifications for Double Gang Blank Faceplates

	Feature	Minimum Requirements	Bidder's Response
1.	Size	Double gang	
2.	Colour	White	
3.	Material	High impact plastic (ABS UL 94V-	
		o compliant)	
4.	Assembly	Blank double gang complete with	
		screws	

#### 23. Minimum Technical Specifications for 1m Threaded Rods

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Steel threaded rods	
2.	Length	1m	
3.	Size	M10	

#### 24. Minimum Technical Specifications for 300mm Trapeze Hanger

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Galvanize steel	
2.	Rod hole size	12mm at the ends	
3.	Type	Flat	
4.	Length	300mm	

	Feature	<b>Minimum Requirements</b>	Bidder's Response
5.	Width	50mm	
6.	Thickness	3mm	

## 25. Minimum Technical Specifications for Rawl Bolts M10 MM

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Steel threaded rods	
2.	Size	M10	
3.	Packaging	Packets of 100pcs	

#### 26. Minimum Technical Specifications for M10 Nuts with Washers

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Steel	
2.	Size	• Nuts M10	
		• Washers M10	
3.	Packaging	Packets of 100pcs	

#### 27. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### The Scope of Works

The successful bidder shall be required to carry out the following works; Installation of new LAN for KRA Nakuru Generations House. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labelling etc. The fibre works entail the installation of indoor or outdoor fibre cables to interconnect floors within the same building or offices within the same campus. Fibre installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per the LAN design and the engineer's instructions. All cables must run through the trunkings.	
2.	Horizontal cabling	The horizontal cabling should be done neatly and professionally as per the LAN design and the engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre. Installation of fibre should be carried out according to the instructions of the network engineer on site. At least 6 cores must be terminated for each side of a cable (i.e. 12 terminations).	
4.	Tools & accessories	The contractor must have all the tools and accessories required to install and test Local area Networks (LANs).	
5.	Quality of works	The contractor is required to provide high standard installation service and quality workmanship. Cable management must also be neatly done.  The trunking joints must flush and with no gapes. Knockouts must be installed neatly with no gapes or spaces.  The knockouts <b>MUST</b> be of the same shade as that of the trunkings.	
6.	Old cable/trunkin g uninstallatio n	The contractor will be required to carefully uninstall old cabling and/or trunking in areas where the LAN is undergoing an overhaul. This should be done neatly to avoid tampering with the wall painting and cable/trunking to be reused.	
7.	Equipment migration	The contractor will be required to carefully uninstall equipment from the old cabinet and migrate them to the newly installed cabinet. This should be done carefully to avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The contractor will be required to return to site and rectify any defects that may occur within the defect liability period at no extra cost to the Authority.	
9.	Drawings and documentati on	On completion of the works the contractor <u>MUST</u> provide all the relevant documentation and the LAN schematic diagram for each site.	
10.	Labeling	All the data points and ports on the Patch panels must be well labeled with Printed labels. The patch cords must also be labeled on both ends to match port numbers.	
11.	Testing and Commissioni ng	The Contractor is required to carry out professional tests and provide results both in printed and in soft copy. This shall apply to both copper and fibre. A joint test and commissioning will be carried out by KRA and the contractor.	

#### IX. MINIMUM TECHNICAL SPECIFICATIONS FOR NAKURU KPC

## 1 Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years (bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

## 2 Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

# 3 Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs Should also be backward compatible to cat 5e	

	Feature	Minimum Requirements	Bidder's response
10.	Shield	Hinged cable retention/ grounding	
		clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

# 4 Minimum Technical Specifications for 1M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 5 Minimum Technical Specifications for 3M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 6 Minimum Technical Specifications for 18U Wall Mount Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand	
2.	Form Factor	18 U wall-mount data cabinet with	
		a hinged back	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window	
		Rear door: high-flow mesh	
		Both doors keyed locks for security	
		1.2mm solid sides	
		Installed axial fan kits	
5.	Power outlets in the		
	cabinet	V AC earthed and fused with	
		shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic	
		horizontal Dual-sided cable	
		managers	

## 7 Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for	

		permanent wall structures
2.	Size	200mm by 50mm, two compartments
3.	Length	2.4 M
4.	Gauge	1.2mm

#### 8 Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	
5.	Gauge	1.2mm	

#### 9 TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### **The Scope of Works**

The successful bidder shall be required to carry out the following works; Revamping of the existing LAN for KRA Nakuru KPC Station. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation.

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per the LAN design and the engineer's instructions. All cables must run through the trunkings.	
2.	Horizontal cabling	The horizontal cabling should be done neatly and professionally as per the LAN design and the engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre. Installation of fibre should be carried out according to the instructions of the network engineer on site. At least 6 cores must be terminated for each side of a cable (i.e. 12 terminations).	
4.	Tools & accessories	The contractor must have all the tools and accessories required to install and test Local area Networks (LANs).	
5.	Quality of works	The contractor is required to provide high standard installation service and quality workmanship. Cable management must also be neatly done.  The trunking joints must flush and with no gapes. Knockouts must be installed neatly with no gapes or spaces.  The knockouts <b>MUST</b> be of the same shade as that of the trunkings.	

6.	Old	The contractor will be required to carefully uninstall	
	cable/trunkin	old cabling and/or trunking in areas where the LAN	
	g	is undergoing an overhaul. This should be done	
	uninstallatio	neatly to avoid tampering with the wall painting and	
	n	cable/trunking to be reused.	
7.	Equipment	The contractor will be required to carefully uninstall	
	migration	equipment from the old cabinet and migrate them to	
		the newly installed cabinet. This should be done	
		carefully to avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The	
		contractor will be required to return to site and rectify	
		any defects that may occur within the defect liability	
		period at no extra cost to the Authority.	
9.	Drawings	On completion of the works the contractor <b>MUST</b>	
	and	provide all the relevant documentation and the LAN	
	documentati	schematic diagram for each site.	
	on		
10.	Labeling	All the data points and ports on the Patch panels must	
		be well labeled with Printed labels. The patch cords	
		must also be labeled on both ends to match port	
		numbers.	
11.	Testing and	The Contractor is required to carry out professional	
	Commissioni	tests and provide results both in printed and in soft	
	ng	copy. This shall apply to both copper and fibre.	
		A joint test and commissioning will be carried out by	
		KRA and the contractor.	

Bidder's Signature Date.	Stamp

# C. LOT III TECHNICAL SPECIFICATIONS

## I. MINIMUM TECHNICAL SPECIFICATIONS FOR KISUMU LAKE BASIN MALL

## 1. Minimum Technical Specifications for 12 Port Multimode Modular Fiber ODF

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Mode of operation	Multimode	
3.	Port density	• 12 ports (24 cores) • Fully populated	
4.	Form Factor	1HU	
5.	Adapter	SC	
6.	Accessories	<ul><li>24 Pigtail connectors</li><li>24 core Splice tray</li><li>30 Heat shrink sleeves</li></ul>	

#### 2. Minimum Technical Specifications for 1G Multimode SFP Transceiver Modules

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand (bidder must specify brand )	
2.	Mode of operation	Multimode	
3.	Compatibility	Must be compatible with Cisco switches	
4.	Form Factor	Small pluggable form factor	
5.	Capacity	1 Gigabyte (1G)	

#### 3. Minimum Technical Specifications for 1.5m SC-LC Multimode Fiber Patch Cords

	Feature	Minimum Requirements	Bidder's response
5.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years.	
6.	Mode	Multimode <b>OM3 50/125</b>	
7.	Connector	Must be <b>SC-LC</b>	
8.	Length	1.5m	

#### 4. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years (bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

#### 5. Minimum Technical Specifications for CAT 6A 48-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	48 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

# 6. Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

# 7. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	

	Feature	Minimum Requirements	Bidder's response
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs Should also be backward compatible to cat 5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

# 8. Minimum Technical Specifications for 1m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

# 9. Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	
5.	Gauge	1.2mm	

#### 10. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### i) The Scope of Works

The successful bidder shall be required to carry out the following works; Installation of new and revamping of the existing LAN for KRA Lake Basin Mall station. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc. The fibre works entail the installation of indoor or outdoor fibre cables to interconnect floors within the same building or offices within the same campus. Fibre installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per the LAN design and the engineer's instructions. All cables must run through the trunkings.	
2.	Horizontal cabling	The horizontal cabling should be done neatly and professionally as per the LAN design and the engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre. Installation of fibre should be carried out according to the instructions of the network engineer on site. At least 6 cores must be terminated for each side of a cable (i.e. 12 terminations).	
4.	Tools & accessories	The contractor must have all the tools and accessories required to install and test Local area Networks (LANs).	
5.	Quality of works	The contractor is required to provide high standard installation service and quality workmanship. Cable management must also be neatly done.  The trunking joints must flush and with no gapes. Knockouts must be installed neatly with no gapes or spaces.  The knockouts <b>MUST</b> be of the same shade as that of the trunkings.	
6.	Old cable/trunking uninstallation	The contractor will be required to carefully uninstall old cabling and/or trunking in areas where the LAN is undergoing an overhaul. This should be done neatly to avoid tampering with the wall painting and cable/trunking to be reused.	
7.	Equipment migration	The contractor will be required to carefully uninstall equipment from the old cabinet and migrate them to the newly installed cabinet. This should be done carefully to avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The contractor will be required to return to site and rectify any defects that may occur within the defect liability period at no extra cost to the Authority.	
9.	Drawings and documentation	On completion of the works the contractor <u>MUST</u> provide all the relevant documentation and the LAN schematic diagram for each site.	

10.	Labeling	All the data points and ports on the Patch panels must be well labeled with Printed labels. The patch cords must also be labeled on both ends to match port numbers.	
11.	Testing and Commissioning	The Contractor is required to carry out professional tests and provide results both in printed and in soft copy. This shall apply to both copper and fibre. A joint test and commissioning will be carried out by KRA and the contractor.	

#### II. MINIMUM TECHNICAL SPECIFICATIONS FOR KISUMU FORODHA HOUSE

#### 1. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years (bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

#### 2. Minimum Technical Specifications for CAT 6A Outdoor UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years (bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Sheath Thickness (mm)	$0.60 \pm 0.05$	
4.	Sheath Surface	Clean, Frap, Satiation	
5.	Sheath Material	LDPE (RoHS Compliant)	
6.	Insulation Material	HDPE	
7.	Size	4-Pair solid, Gauge: 23 AWG	
8.	Operating frequency	500 to 550 MHZ	
9.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	

## 3. Minimum Technical Specifications for CAT 6A 48-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	48 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 4. Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	

	Feature	Minimum Requirements	Bidder's response
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

# 5. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs Should also be backward compatible to cat 5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

# 6. Minimum Technical Specifications for 1m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

#### 7. Minimum Technical Specifications for 12U Wall Mount Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand	
2.	Form Factor	12 U wall-mount data cabinet with	
		a hinged back	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window	
		Rear: Hinged Back	
		Both doors keyed locks for security	
		1.2mm solid sides	
		Installed axial fan kits	
5.	Power outlets in the		
	cabinet	V AC earthed and fused with	
		shutters	
6.	Cable manager	Three (3) pieces of 1U black metallic	
		horizontal Dual-sided cable	
		managers	

#### 8. Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4m	
4.	Gauge	1.2mm	

#### 9. Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	
5.	Gauge	1.2mm	

#### 10. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### The Scope of Works

The successful bidder shall be required to carry out the following works; Installation of new LAN for KRA Kisumu Forodha House station. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation.

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per	
		the LAN design and the engineer's instructions. All cables must run through the trunkings.	
		All cables must run tinough the trunkings.	
2.	Horizontal	The horizontal cabling should be done neatly and	
	cabling	professionally as per the LAN design and the	
3.	Vertical	engineer's instructions on site.  The backbone is typically done using fibre.	
3.	cabling	Installation of fibre should be carried out according	
	8	to the instructions of the network engineer on site.	
		At least 6 cores must be terminated for each side of	
	m 1 0	a cable (i.e. 12 terminations).	
4.	Tools & accessories	The contractor must have all the tools and accessories required to install and test Local area	
	accessories	Networks (LANs).	
5.	Quality of	The contractor is required to provide high standard	
	works	installation service and quality workmanship.	
		Cable management must also be neatly done.	
		The trunking joints must flush and with no gapes.	
		Knockouts must be installed neatly with no gapes or spaces.	
		The knockouts <b>MUST</b> be of the same shade as that	
		of the trunkings.	
6.	Old	The contractor will be required to carefully	
	cable/trunki	uninstall old cabling and/or trunking in areas	
	ng	where the LAN is undergoing an overhaul. This	
	uninstallatio n	should be done neatly to avoid tampering with the wall painting and cable/trunking to be reused.	
7.	Equipment	The contractor will be required to carefully	
, .	migration	uninstall equipment from the old cabinet and	
		migrate them to the newly installed cabinet. This	
		should be done carefully to avoid damaging the	
8.	Warranty	equipment. The defect liability period shall be one (1) year. The	
0.	vvarranty	contractor will be required to return to site and	
		rectify any defects that may occur within the defect	
		liability period at no extra cost to the Authority.	
9.	Drawings	On completion of the works the contractor <b>MUST</b>	
	and	provide all the relevant documentation and the	
	documentati on	LAN schematic diagram for each site.	
10.	Labeling	All the data points and ports on the Patch panels	
		must be well labeled with Printed labels. The patch	
		cords must also be labeled on both ends to match	
	m · · ·	port numbers.	
11.	Testing and	The Contractor is required to carry out professional	
	Commissioni ng	tests and provide results both in printed and in soft copy. This shall apply to both copper and fibre.	
	8	A joint test and commissioning will be carried out	
		by KRA and the contractor.	
L	l	<u> </u>	

# III. MINIMUM TECHNICAL SPECIFICATIONS FOR KISUMU PIPELINE, PPO, AIRPORT, PIER

## 1. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years (bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

## 2. Minimum Technical Specifications for CAT 6A Outdoor UTP Ethernet Cable

	Feature	<b>Minimum Requirements</b>	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years (bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Sheath Thickness	$0.60 \pm 0.05$	
	(mm)	0.00 ± 0.05	
4.	Sheath Surface	Clean, Frap, Satiation	
5.	Sheath Material	LDPE (RoHS Compliant)	
6.	Insulation Material	HDPE	
7.	Size	4-Pair solid, Gauge: 23 AWG	
8.	Operating frequency	500 to 550 MHZ	
9.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
10.	Length	305m	

## 3. Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

#### 4. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs Should also be backward compatible to cat 5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

# 5. Minimum Technical Specifications for 1m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

# 6. Minimum Technical Specifications for 12U Wall Mount Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	12 U wall-mount data cabinet with a <b>hinged back</b>	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window  Rear: Hinged Back Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet		
6.	Cable manager	Three (3) pieces of 1U black metallic horizontal Dual-sided cable managers	

## 7. Minimum Technical Specifications for 22U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand	
2.	Form Factor	22 U floor standing standard data	
		cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window	
		Rear door: high-flow mesh	
		Both doors keyed locks for security	
		1.2mm solid sides	
		Installed axial fan kits	
5.	Power outlets in the	6-Way universal PDU 3A/220 - 240	
	cabinet	V AC earthed and fused with	
		shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic	
		horizontal Dual-sided cable	
		managers	

## 8. Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements Bidder's response	
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4m	
4.	Gauge	1.2mm	

## 9. Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	
5.	Gauge	1.2mm	

## 10. Minimum Technical Specifications for 1.5KVA Rack-Mounted UPS

	Feature	Minimum Requirement	Bidders Response
		Internationally recognized brand (bidder must specify brand and model)	
		Output	
1.	Output Power Capacity	900 Watts / 1500 VA	
2.	Max Configurable Power	900 Watts / 1500 VA	
3.	Nominal Output Voltage	230V	
4.	Output Voltage Distortion	Less than 5% at full load	
5.	Output Frequency (sync to mains)	47 - 53 Hz for 50 Hz nominal, 57 - 63 Hz for 60 Hz nominal	

	Feature	Minimum Requirement	Bidders Response
6.	Topology	Line interactive	
7.	Waveform Type	Stepped approximation to a Sine wave	
8.	Output Connections	Four (4) IEC 320 C13 Two (2) IEC jumpers	
		Input	
9.	Nominal Input Voltage	230V	
10.	Input Frequency	50/60 Hz +/- 3 Hz (auto sensing)	
11.	Input Connections	IEC-320 C14	
12.	Battery Type	Maintenance free sealed lead-acid with suspended electrolyte, leak proof	
13.	Input voltage range for main operations	180 - 287V	
14.	Input voltage adjustable range for mains operation	170 - 300V	
15.	Typical recharge time	3 hour(s)	
16.	Typical Backup Time at Half Load	20.9 minutes (432.5 Watts)	
17.	Typical Backup Time at Full Load	7.6 minutes (865 Watts)	
		Communications & Manage	ment
18.	Interface Ports	RJ-45 Serial, USB	
19.	Control panel	Multi-function LCD status and control console	
20.	Audible Alarm	Alarm when on battery : distinctive low battery alarm : configurable delays	
	1	Surge Protection and Filte	ring
21.	Surge energy rating	459Joules	
22.	Filtering	Full time multi-pole noise filtering : 0.3% IEEE surge let-through : zero clamping response time : meets UL 1449	
23.	Data Line filtering	RJ-45 modem/Fax/DSL/10-100 Base-T protection	
24.	Standard Warranty	2 years repair or replace	
25.	Accessories	Power cords (at least 1.83M), CD with software, Documentation CD, Rack Mounting brackets, Smart UPS signaling RS-232 cable, USB cable, User Manual	

#### 11. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### **The Scope of Works**

The successful bidder shall be required to carry out the following works; Installation of new and Revamping of existing LANs for KRA Kisumu Pipeline, PPO, Airport and Pier stations.

The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc. The fibre works entail the installation of indoor or outdoor fibre cables to interconnect floors within the same building or offices within the same campus. Fibre installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labelling, Drawings and Documentation

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per the LAN design and the engineer's instructions. All cables must run through the trunkings.	
2.	Horizontal cabling	The horizontal cabling should be done neatly and professionally as per the LAN design and the engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre. Installation of fibre should be carried out according to the instructions of the network engineer on site. At least 6 cores must be terminated for each side of a cable (i.e. 12 terminations).	
4.	Tools & accessories	The contractor must have all the tools and accessories required to install and test Local area Networks (LANs).	
5.	Quality of works	The contractor is required to provide high standard installation service and quality workmanship. Cable management must also be neatly done.  The trunking joints must flush and with no gapes. Knockouts must be installed neatly with no gapes or spaces.  The knockouts <b>MUST</b> be of the same shade as that of the trunkings.	
6.	Old cable/trunking uninstallation	The contractor will be required to carefully uninstall old cabling and/or trunking in areas where the LAN is undergoing an overhaul. This should be done neatly to avoid tampering with the wall painting and cable/trunking to be reused.	
7.	Equipment migration	The contractor will be required to carefully uninstall equipment from the old cabinet and migrate them to the newly installed cabinet. This should be done carefully to avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The contractor will be required to return to site and rectify any defects that may occur within the defect liability period at no extra cost to the Authority.	
9.	Drawings and documentation	On completion of the works the contractor <u>MUST</u> provide all the relevant documentation and the LAN schematic diagram for each site.	

10.	Labeling	All the data points and ports on the Patch panels must be well labeled with Printed labels. The patch cords must also be labeled on both ends to match port numbers.	
11.	Testing and Commissioning	The Contractor is required to carry out professional tests and provide results both in printed and in soft copy. This shall apply to both copper and fibre. A joint test and commissioning will be carried out by KRA and the contractor.	

#### IV. MINIMUM TECHNICAL SPECIFICATIONS FOR KISII (DC & POSTA OFFICES)

#### 1. Minimum Technical Specifications for 12 Core Multimode Armored Fiber Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years(bidder must specify brand)	
2.	Jacket characteristics	Water Blocking Aramid Yarn	
	& Material	Armored	
		PVC	
3.	Mode of operation	Multimode	
4.	Core density	12 cores	
5.	Attenuation (Max)	3.50 dB/km @ 850nm	
6.	Standards	Optical and mechanical	
		performance: IEC 60794-2, IEC	
		60794-2-20, ISO 11801, EN 50173-1	

#### 2. Minimum Technical Specifications for 12 Port Multimode Modular Fiber ODF

	Feature	<b>Minimum Requirements</b>	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Mode of operation	Multimode	
3.	Port density	• 12 ports (24 cores) • Fully populated	
4.	Form Factor	1HU	
5.	Adapter	SC	
6.	Accessories	<ul><li>24 Pigtail connectors</li><li>24 core Splice tray</li><li>30 Heat shrink sleeves</li></ul>	

## 3. Minimum Technical Specifications for 1G Multimode SFP Transceiver Modules

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand (bidder must specify brand )	
2.	Mode of operation	Multimode	
3.	Compatibility	Must be compatible with Cisco switches	
4.	Form Factor	Small pluggable form factor	
5.	Capacity	1 Gigabyte (1G)	

## 4. Minimum Technical Specifications for 1.5m SC-LC Multimode Fiber Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10	
		years.	
2.	Mode	Multimode <b>OM3 50/125</b>	
3.	Connector	Must be <b>SC-LC</b>	
4.	Length	1.5m	

#### 5. Minimum Technical Specifications for CAT 6A Outdoor UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years (bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Sheath Thickness (mm)	$0.60 \pm 0.05$	
4.	Sheath Surface	Clean, Frap, Satiation	
5.	Sheath Material	LDPE (RoHS Compliant)	
6.	Insulation Material	HDPE	
7.	Size	4-Pair solid, Gauge: 23 AWG	
8.	Operating frequency	500 to 550 MHZ	
9.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
10.	Length	305m	

## **6.** Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years (bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

## 7. Minimum Technical Specifications for CAT 6A 48-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	48 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 8. Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	

	Feature	Minimum Requirements	Bidder's response
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

# 9. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs Should also be backward compatible to cat 5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

# 10. Minimum Technical Specifications for 1m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	

	Feature	Minimum Requirements	Bidder's response
4.	Boot Color	With colour matching jacket/ boot	
		to labelling on the faceplates	

## 11. Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4m	
4.	Gauge	1.2mm	

## 12. Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	
5.	Gauge	1.2mm	

## 13. Minimum Technical Specifications for 22U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand	
2.	Form Factor	22 U floor standing standard data	
		cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window	
		Rear door: high-flow mesh	
		Both doors keyed locks for security	
		1.2mm solid sides	
		Installed axial fan kits	
5.	Power outlets in the	6-Way universal PDU 3A/220 - 240	
	cabinet	V AC earthed and fused with	
		shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic	
		horizontal Dual-sided cable	
		managers	

## 14. Minimum Technical Specifications for 12U Wall Mount Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand	
2.	Form Factor	12 U wall-mount data cabinet with	
		a hinged back	
3.	Dimension	600x800mm	

	Feature	Minimum Requirements	Bidder's response
4.	Construction	Front door: with glass window	
		Rear: Hinged Back Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet		
	Cabinet	shutters	
6.	Cable manager	Three (3) pieces of 1U black metallic horizontal Dual-sided cable managers	

#### 15. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### **The Scope of Works**

The successful bidder shall be required to carry out the following works; Installation of new LAN for KRA Kisii (DC & Posta Offices). The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labelling etc. The fibre works entail the installation of indoor or outdoor fibre cables to interconnect floors within the same building or offices within the same campus. Fibre installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

## Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labelling, Drawings and Documentation

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per the LAN design and the engineer's instructions. All cables must run through the trunkings.	
2.	Horizontal cabling	The horizontal cabling should be done neatly and professionally as per the LAN design and the engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre. Installation of fibre should be carried out according to the instructions of the network engineer on site. At least 6 cores must be terminated for each side of a cable (i.e. 12 terminations).	
4.	Tools & accessories	The contractor must have all the tools and accessories required to install and test Local area Networks (LANs).	
5.	Quality of works	The contractor is required to provide high standard installation service and quality workmanship. Cable management must also be neatly done.  The trunking joints must flush and with no gapes. Knockouts must be installed neatly with no gapes or spaces.	
6.	Old cable/trunki ng uninstallatio n	The contractor will be required to carefully uninstall old cabling and/or trunking in areas where the LAN is undergoing an overhaul. This should be done neatly to avoid tampering with the wall painting and cable/trunking to be reused.	

7.	Equipment migration	The contractor will be required to carefully uninstall equipment from the old cabinet and migrate them to the newly installed cabinet. This should be done carefully to avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The contractor will be required to return to site and rectify any defects that may occur within the defect liability period at no extra cost to the Authority.	
9.	Drawings and documentati on	On completion of the works the contractor <u>MUST</u> provide all the relevant documentation and the LAN schematic diagram for each site.	
10.	Labeling	All the data points and ports on the Patch panels must be well labeled with Printed labels. The patch cords must also be labeled on both ends to match port numbers.	
11.	Testing and Commissioni ng	The Contractor is required to carry out professional tests and provide results both in printed and in soft copy. This shall apply to both copper and fibre. A joint test and commissioning will be carried out by KRA and the contractor.	

## V. MINIMUM TECHNICAL SPECIFICATIONS FOR BUNGOMA

## 1. Minimum Technical Specifications for 12 Core Multimode Armored Fiber Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years(bidder must specify brand)	
2.	Jacket characteristics	Water Blocking Aramid Yarn	
	& Material	Armored	
		PVC	
3.	Mode of operation	Multimode	
4.	Core density	12 cores	
5.	Attenuation (Max)	3.50 dB/km @ 850nm	
6.	Standards	Optical and mechanical	
		performance: IEC 60794-2, IEC	
		60794-2-20, ISO 11801, EN 50173-1	

## 2. Minimum Technical Specifications for 12 Port Multimode Modular Fiber ODF

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand	
2.	Mode of operation	Multimode	
3.	Port density	• 12 ports (24 cores)	
		• Fully populated	
4.	Form Factor	1HU	
5.	Adapter	SC	
6.	Accessories	• 24 Pigtail connectors	
		• 24 core Splice tray	
		• 30 Heat shrink sleeves	

## 3. Minimum Technical Specifications for 1G Multimode SFP Transceiver Modules

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand (bidder must specify brand )	
2.	Mode of operation	Multimode	
3.	Compatibility	Must be compatible with Cisco switches	
4.	Form Factor	Small pluggable form factor	
5.	Capacity	1 Gigabyte (1G)	

## 4. Minimum Technical Specifications for 1.5m SC-LC Multimode Fiber Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years.	
2.	Mode	Multimode <b>OM3 50/125</b>	
3.	Connector	Must be <b>SC-LC</b>	
4.	Length	1.5m	

## 5. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years (bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

## 6. Minimum Technical Specifications for CAT 6A 48-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	48 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 7. Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 8. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1,	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs Should also be backward compatible to cat 5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

## 9. Minimum Technical Specifications for 1m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 10. Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4m	
4.	Gauge	1.2mm	

## 11. Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
--	---------	----------------------	-------------------

1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 200mm by 50mm	
		trunking	
5.	Gauge	1.2mm	

#### 12. Minimum Technical Specifications for 22U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand	
2.	Form Factor	22 U floor standing standard data	
		cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window	
		Rear door: high-flow mesh	
		Both doors keyed locks for security	
		1.2mm solid sides	
		Installed axial fan kits	
5.	Power outlets in the	6-Way universal PDU 3A/220 - 240 V	
	cabinet	AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic	
		horizontal Dual-sided cable managers	

#### 13. Minimum Technical Specifications for 12U Wall Mount Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	12 U wall-mount data cabinet with a <b>hinged back</b>	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window  Rear: Hinged Back Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Three (3) pieces of 1U black metallic horizontal Dual-sided cable managers	

#### 14. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### **The Scope of Works**

The successful bidder shall be required to carry out the following works; Installation of new and revamping of the existing LAN for KRA Bungoma station. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labelling etc. The fibre works entail the installation of indoor or outdoor fibre cables to interconnect floors within the same building or offices within the same campus. Fibre installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within

## Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation.

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per the LAN design and the engineer's instructions. All cables must run through the trunkings.	
2.	Horizontal cabling	The horizontal cabling should be done neatly and professionally as per the LAN design and the engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre. Installation of fibre should be carried out according to the instructions of the network engineer on site. At least 6 cores must be terminated for each side of a cable (i.e. 12 terminations).	
4.	Tools & accessories	The contractor must have all the tools and accessories required to install and test Local area Networks (LANs).	
5.	Quality of works	The contractor is required to provide high standard installation service and quality workmanship. Cable management must also be neatly done.  The trunking joints must flush and with no gapes. Knockouts must be installed neatly with no gapes or spaces.	
6.	Old cable/trunking uninstallation	The contractor will be required to carefully uninstall old cabling and/or trunking in areas where the LAN is undergoing an overhaul. This should be done neatly to avoid tampering with the wall painting and cable/trunking to be reused.	
7.	Equipment migration	The contractor will be required to carefully uninstall equipment from the old cabinet and migrate them to the newly installed cabinet. This should be done carefully to avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The contractor will be required to return to site and rectify any defects that may occur within the defect liability period at no extra cost to the Authority.	
9.	Drawings and documentation	On completion of the works the contractor <u>MUST</u> provide all the relevant documentation and the LAN schematic diagram for each site.	
10.	Labeling	All the data points and ports on the Patch panels must be well labeled with Printed labels. The patch cords must also be labeled on both ends to match port numbers.	
11.	Testing and Commissionin g	The Contractor is required to carry out professional tests and provide results both in printed and in soft copy. This shall apply to both copper and fibre.  A joint test and commissioning will be carried out by KRA and the contractor.	

#### VI. MINIMUM TECHNICAL SPECIFICATIONS FOR KAKAMEGA

## 1. Minimum Technical Specifications for 12 Core Multimode Armored Fiber Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years(bidder must specify brand)	
2.	Jacket	Water Blocking Aramid Yarn	
	characteristics &	Armored	
	Material	PVC	
3.	Mode of operation	Multimode	
4.	Core density	12 cores	
5.	Attenuation (Max)	3.50 dB/km @ 850nm	
6.	Standards	Optical and mechanical performance:	
		IEC 60794-2, IEC 60794-2-20, ISO	
		11801, EN 50173-1	

## 2. Minimum Technical Specifications for 12 Port Multimode Modular Fiber ODF

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand	
2.	Mode of operation	Multimode	
3.	Port density	• 12 ports (24 cores)	
		Fully populated	
4.	Form Factor	1HU	
5.	Adapter	SC	
6.	Accessories	• 24 Pigtail connectors	
		• 24 core Splice tray	
		• 30 Heat shrink sleeves	

## 3. Minimum Technical Specifications for 1G Multimode SFP Transceiver Modules

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand (bidder must specify brand )	
2.	Mode of operation	Multimode	
3.	Compatibility	Must be compatible with Cisco switches	
4.	Form Factor	Small pluggable form factor	
5.	Capacity	1 Gigabyte (1G)	

## 4. Minimum Technical Specifications for 1.5m SC-LC Multimode Fiber Patch Cords

	Feature	<b>Minimum Requirements</b>	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10	
		years.	
2.	Mode	Multimode <b>OM3 50/125</b>	
3.	Connector	Must be <b>SC-LC</b>	
4.	Length	1.5m	

## 5. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years (bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

## 6. Minimum Technical Specifications for CAT 6A 48-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	48 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e-coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 7. Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 8. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs Should also be backward compatible to cat 5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

## 9. Minimum Technical Specifications for 1m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 10. Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4m	
4.	Gauge	1.2mm	

## 11. Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	

5.	Gauge	1.2mm	
----	-------	-------	--

#### 12. Minimum Technical Specifications for 22U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	22 U floor standing standard data cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window Rear door: high-flow mesh Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

#### 13. Minimum Technical Specifications for 12U Wall Mount Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand	
2.	Form Factor	12 U wall-mount data cabinet with a	
		hinged back	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window	
		Rear: Hinged Back	
		Both doors keyed locks for security	
		1.2mm solid sides	
		Installed axial fan kits	
5.	Power outlets in the	6-Way universal PDU 3A/220 - 240 V	
	cabinet	AC earthed and fused with shutters	
	~ 11		
6.	Cable manager	Three (3) pieces of 1U black metallic	
		horizontal Dual-sided cable managers	

#### 14. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### **The Scope of Works**

The successful bidder shall be required to carry out the following works; Installation of new LAN for KRA Kakamega station. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labelling etc. The fibre works entail the installation of indoor or outdoor fibre cables to interconnect floors within the same building or offices within the same campus. Fibre installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

## ${\bf Minimum\ Technical\ Specifications\ for\ LAN\ Installation,\ Testing,\ Commissioning,\ Labeling,\ Drawings\ and\ Documentation.}$

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per the LAN design and the engineer's instructions. All cables must run through the trunkings.	
2.	Horizontal cabling	The horizontal cabling should be done neatly and professionally as per the LAN design and the engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre. Installation of fibre should be carried out according to the instructions of the network engineer on site. At least 6 cores must be terminated for each side of a cable (i.e. 12 terminations).	
4.	Tools & accessories	The contractor must have all the tools and accessories required to install and test Local area Networks (LANs).	
5.	Quality of works	The contractor is required to provide high standard installation service and quality workmanship. Cable management must also be neatly done. The trunking joints must flush and with no gapes. Knockouts must be installed neatly with no gapes or spaces.	
6.	Old cable/trunking uninstallation	The contractor will be required to carefully uninstall old cabling and/or trunking in areas where the LAN is undergoing an overhaul. This should be done neatly to avoid tampering with the wall painting and cable/trunking to be reused.	
7.	Equipment migration	The contractor will be required to carefully uninstall equipment from the old cabinet and migrate them to the newly installed cabinet. This should be done carefully to avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The contractor will be required to return to site and rectify any defects that may occur within the defect liability period at no extra cost to the Authority.	
9.	Drawings and documentation	On completion of the works the contractor <u>MUST</u> provide all the relevant documentation and the LAN schematic diagram for each site.	
10.	Labeling	All the data points and ports on the Patch panels must be well labeled with Printed labels. The patch cords must also be labeled on both ends to match port numbers.	
11.	Testing and Commissionin g	The Contractor is required to carry out professional tests and provide results both in printed and in soft copy. This shall apply to both copper and fibre. A joint test and commissioning will be carried out by KRA and the contractor.	

#### VII. MINIMUM TECHNICAL SPECIFICATIONS FOR SIAYA

## 1. Minimum Technical Specifications for 12 Core Multimode Armored Fiber Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years(bidder must specify brand)	
2.	Jacket	Water Blocking Aramid Yarn	
	characteristics &	Armored	
	Material	PVC	
3.	Mode of operation	Multimode	
4.	Core density	12 cores	
5.	Attenuation (Max)	3.50 dB/km @ 850nm	
6.	Standards	Optical and mechanical performance:	
		IEC 60794-2, IEC 60794-2-20, ISO	
		11801, EN 50173-1	

## 2. Minimum Technical Specifications for 12 Port Multimode Modular Fiber ODF

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Mode of operation	Multimode	
3.	Port density	• 12 ports (24 cores) • Fully populated	
4.	Form Factor	1HU	
5.	Adapter	SC	
6.	Accessories	<ul><li>24 Pigtail connectors</li><li>24 core Splice tray</li><li>30 Heat shrink sleeves</li></ul>	

## 3. Minimum Technical Specifications for 1G Multimode SFP Transceiver Modules

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand (bidder must specify brand )	
2.	Mode of operation	Multimode	
3.	Compatibility	Must be compatible with Cisco switches	
4.	Form Factor	Small pluggable form factor	
5.	Capacity	1 Gigabyte (1G)	

## 4. Minimum Technical Specifications for 1.5m SC-LC Multimode Fiber Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years.	
2.	Mode	Multimode <b>OM3 50/125</b>	
3.	Connector	Must be <b>SC-LC</b>	
4.	Length	1.5m	

## 5. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years (bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	

## 6. Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 7. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs Should also be backward compatible to cat 5e	
10.	Shield	Hinged cable retention/ grounding clip	

	Feature	<b>Minimum Requirements</b>	Bidder's response
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

## 8. Minimum Technical Specifications for 1m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 9. Minimum Technical Specifications for 3m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 10. Minimum Technical Specifications for 22U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	22 U floor standing standard data cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window Rear door: high-flow mesh Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

## 11. Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements Bidd	ler's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two	

		compartments	
3.	Length	2.4m	
4.	Gauge	1.2mm	

## 12. Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	
5.	Gauge	1.2mm	

## 1. Minimum Technical Specifications for 12U Wall Mount Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	12 U wall-mount data cabinet with a <b>hinged back</b>	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window Rear: Hinged Back Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Three (3) pieces of 1U black metallic horizontal Dual-sided cable managers	

## 13. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### **The Scope of Works**

The successful bidder shall be required to carry out the following works; Installation of new LAN for upcoming KRA Siaya TSO station. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc. The fibre works entail the installation of indoor or outdoor fibre cables to interconnect floors within the same building or offices within the same campus. Fibre installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation.

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per	•
	O O	the LAN design and the engineer's instructions.	
		All cables must run through the trunkings.	
2.	Horizontal	The horizontal cabling should be done neatly and	
	cabling	professionally as per the LAN design and the	
		engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre.	
		Installation of fibre should be carried out	
		according to the instructions of the network	
		engineer on site. At least 6 cores must be	
		terminated for each side of a cable (i.e. 12	
	_	terminations).	
4.	Tools &	The contractor must have all the tools and	
	accessories	accessories required to install and test Local area	
		Networks (LANs).	
5.	Quality of works	The contractor is required to provide high standard	
		installation service and quality workmanship.	
		Cable management must also be neatly done.	
		The trunking joints must flush and with no gapes.	
		Knockouts must be installed neatly with no gapes	
		or spaces.	
		The knockouts <b>MUST</b> be of the same shade as that	
	01.1	of the trunkings.	
6.	Old	The contractor will be required to carefully	
	cable/trunking	uninstall old cabling and/or trunking in areas	
	uninstallation	where the LAN is undergoing an overhaul. This	
		should be done neatly to avoid tampering with the wall painting and cable/trunking to be reused.	
	Equipment	The contractor will be required to carefully	
7.	migration	uninstall equipment from the old cabinet and	
	inigration	migrate them to the newly installed cabinet. This	
		should be done carefully to avoid damaging the	
		equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The	
0.	, , arrancy	contractor will be required to return to site and	
		rectify any defects that may occur within the defect	
		liability period at no extra cost to the Authority.	
9.	Drawings and	On completion of the works the contractor <b>MUST</b>	
	documentation	provide all the relevant documentation and the	
		LAN schematic diagram for each site.	
10.	Labeling	All the data points and ports on the Patch panels	
		must be well labeled with Printed labels. The patch	
		cords must also be labeled on both ends to match	
		port numbers.	
11.	Testing and	The Contractor is required to carry out	
	Commissioning	professional tests and provide results both in	
		printed and in soft copy. This shall apply to both	
		copper and fibre.	
		A joint test and commissioning will be carried out	
		by KRA and the contractor.	

#### VIII. MINIMUM TECHNICAL SPECIFICATIONS FOR BUSIA

## 1. Minimum Technical Specifications for 12 Core Multimode Armored Fiber Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years(bidder must specify brand)	
2.	Jacket	Water Blocking Aramid Yarn	
	characteristics &	Armored	
	Material	PVC	
3.	Mode of operation	Multimode	
4.	Core density	12 cores	
5.	Attenuation (Max)	3.50 dB/km @ 850nm	
6.	Standards	Optical and mechanical performance:	
		IEC 60794-2, IEC 60794-2-20, ISO	
		11801, EN 50173-1	

## 2. Minimum Technical Specifications for 12 Port Multimode Modular Fiber ODF

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Mode of operation	Multimode	
3.	Port density	• 12 ports (24 cores) • Fully populated	
4.	Form Factor	1HU	
5.	Adapter	SC	
6.	Accessories	<ul><li>24 Pigtail connectors</li><li>24 core Splice tray</li><li>30 Heat shrink sleeves</li></ul>	

## 3. Minimum Technical Specifications for 1G Multimode SFP Transceiver Modules

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand (bidder must specify brand )	
2.	Mode of operation	Multimode	
3.	Compatibility	Must be compatible with Cisco switches	
4.	Form Factor	Small pluggable form factor	
5.	Capacity	1 Gigabyte (1G)	

## 4. Minimum Technical Specifications for 1.5m SC-LC Multimode Fiber Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years.	
2.	Mode	Multimode <b>OM3 50/125</b>	
3.	Connector	Must be <b>SC-LC</b>	
4.	Length	1.5m	

## 5. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years (bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

## 6. Minimum Technical Specifications for CAT 6A 48-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	48 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 7. Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 8. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs Should also be backward compatible to cat 5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

## 9. Minimum Technical Specifications for 1m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 10. Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4m	
4.	Gauge	1.2mm	

## 11. Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Single Gang	

4.	Compatibility	Compatible with 200mm by 50mm	
		trunking	
5.	Gauge	1.2mm	

## 12. Minimum Technical Specifications for 100mmx50mm Curved Floor Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	100mm by 50mm, two compartments	
3.	Form	Curved	
4.	Length	2.4m	
5.	Gauge	1.2mm	

#### 13. Minimum Technical Specifications for 100mm Pedestal Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	<ul> <li>Powder coated metal trunking with pre-punched fixing holes for permanent floor structures.</li> <li>Rounded corners.</li> </ul>	
2.	Size	100mm	
3.	Outlets	<ul><li>4 single gang data outlet</li><li>4 dual gang power outlet</li></ul>	
4.	Height	400mm	
5.	Gauge	1.2mm	

## 14. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### **The Scope of Works**

The successful bidder shall be required to carry out the following works; Installation of new and revamping of the existing LAN for KRA Busia station. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labelling etc. The fibre works entail the installation of indoor or outdoor fibre cables to interconnect floors within the same building or offices within the same campus. Fibre installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation.

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as	
1.	Trummig	per the LAN design and the engineer's	
		instructions.	
		All cables must run through the trunkings.	
2.	Horizontal	The horizontal cabling should be done neatly	
۷.	cabling	and professionally as per the LAN design and the	
	cabining	engineer's instructions on site.	
0	Vertical	The backbone is typically done using fibre.	
3.	cabling	Installation of fibre should be carried out	
	Cabillig	according to the instructions of the network	
		engineer on site. At least 6 cores must be	
		terminated for each side of a cable (i.e. 12	
		terminated for each side of a cable (i.e. 12 terminations).	
	T1-0	,	
4.	Tools &	The contractor must have all the tools and	
	accessories	accessories required to install and test Local	
	0 1': 6	area Networks (LANs).	
5⋅	Quality of	The contractor is required to provide high	
	works	standard installation service and quality	
		workmanship. Cable management must also be	
		neatly done.	
		The trunking joints must flush and with no	
		gapes. Knockouts must be installed neatly with	
		no gapes or spaces.	
6.	Old	The contractor will be required to carefully	
	cable/trunking	uninstall old cabling and/or trunking in areas	
	uninstallation	where the LAN is undergoing an overhaul. This	
		should be done neatly to avoid tampering with	
		the wall painting and cable/trunking to be	
		reused.	
7.	Equipment	The contractor will be required to carefully	
	migration	uninstall equipment from the old cabinet and	
		migrate them to the newly installed cabinet. This	
		should be done carefully to avoid damaging the	
		equipment.	
8.	Warranty	The defect liability period shall be one (1) year.	
		The contractor will be required to return to site	
		and rectify any defects that may occur within the	
		defect liability period at no extra cost to the	
		Authority.	
9.	Drawings and	On completion of the works the contractor	
	documentation	<b>MUST</b> provide all the relevant documentation	
		and the LAN schematic diagram for each site.	
10.	Labeling	All the data points and ports on the Patch panels	
		must be well labeled with Printed labels. The	
		patch cords must also be labeled on both ends to	
		match port numbers.	
11.	Testing and	The Contractor is required to carry out	
	Commissionin	professional tests and provide results both in	
	g	printed and in soft copy. This shall apply to both	
		copper and fibre.	
		A joint test and commissioning will be carried	
		out by KRA and the contractor.	

## IX. MINIMUM TECHNICAL SPECIFICATIONS FOR MALABA

## 1. Minimum Technical Specifications for 12 Core Multimode Armored Fiber Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years(bidder must specify brand)	
2.	Jacket	Water Blocking Aramid Yarn	
	characteristics &	Armored	
	Material	PVC	
3.	Mode of operation	Multimode	
4.	Core density	12 cores	
5.	Attenuation (Max)	3.50 dB/km @ 850nm	
6.	Standards	Optical and mechanical performance:	
		IEC 60794-2, IEC 60794-2-20, ISO	
		11801, EN 50173-1	

## 2. Minimum Technical Specifications for 12 Port Multimode Modular Fiber ODF

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Mode of operation	Multimode	
3.	Port density	• 12 ports (24 cores) • Fully populated	
4.	Form Factor	1HU	
5.	Adapter	SC	
6.	Accessories	<ul><li>24 Pigtail connectors</li><li>24 core Splice tray</li><li>30 Heat shrink sleeves</li></ul>	

## 3. Minimum Technical Specifications for 1G Multimode SFP Transceiver Modules

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand (bidder must specify brand )	
2.	Mode of operation	Multimode	
3.	Compatibility	Must be compatible with Cisco switches	
4.	Form Factor	Small pluggable form factor	
5.	Capacity	1 Gigabyte (1G)	

## 4. Minimum Technical Specifications for 1.5m SC-LC Multimode Fiber Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years.	
2.	Mode	Multimode <b>OM3 50/125</b>	
3.	Connector	Must be <b>SC-LC</b>	
4.	Length	1.5m	

## 5. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years (bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

## 6. Minimum Technical Specifications for CAT 6A 48-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	48 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 7. Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 8. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs Should also be backward compatible to cat 5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

## 9. Minimum Technical Specifications for 1m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 10. Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4m	
4.	Gauge	1.2mm	

## 11. Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	

3.	Width	Single Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	
5.	Gauge	1.2mm	

#### 12. Minimum Technical Specifications for 100mmx50mm Curved Floor Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	100mm by 50mm, two compartments	
3.	Form	Curved	
4.	Length	2.4m	
5.	Gauge	1.2mm	

#### 13. Minimum Technical Specifications for 100mm Pedestal Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	<ul> <li>Powder coated metal trunking with pre-punched fixing holes for permanent floor structures.</li> <li>Rounded corners.</li> </ul>	
2.	Size	100mm	
3.	Outlets	<ul><li>4 single gang data outlet</li><li>4 dual gang power outlet</li></ul>	
4.	Height	400mm	
5.	Gauge	1.2mm	

#### 14. Minimum Technical Specifications for Single Gang Blank Faceplates

	Feature	Minimum Requirements	Bidder's response
1.	Size	Single gang	
2.	Colour	White	
3.	Material	High impact plastic (ABS UL 94V-0 compliant)	
4.	Assembly	Blank single gang complete with screws	

#### 15. Minimum Technical Specifications for Double Gang Blank Faceplates

	Feature	Minimum Requirements	Bidder's response
1.	Size	Double gang	
2.	Colour	White	
3.	Material	High impact plastic (ABS UL 94V-0 compliant)	
4.	Assembly	Blank double gang complete with screws	

#### 16. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### **The Scope of Works**

The successful bidder shall be required to carry out the following works; Installation of new and revamping of the existing LAN for KRA Malaba OSBP station. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc. The fibre

works entail the installation of indoor or outdoor fibre cables to interconnect floors within the same building or offices within the same campus. Fibre installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

## Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation.

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per the LAN design and the engineer's instructions. All cables must run through the trunkings.	
2.	Horizontal cabling	The horizontal cabling should be done neatly and professionally as per the LAN design and the engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre. Installation of fibre should be carried out according to the instructions of the network engineer on site. At least 6 cores must be terminated for each side of a cable (i.e. 12 terminations).	
4.	Tools & accessories	The contractor must have all the tools and accessories required to install and test Local area Networks (LANs).	
5.	Quality of works	The contractor is required to provide high standard installation service and quality workmanship. Cable management must also be neatly done.  The trunking joints must flush and with no gapes. Knockouts must be installed neatly with no gapes or spaces.  The knockouts <b>MUST</b> be of the same shade as that of the trunkings.	
6.	Old cable/trunking uninstallation	The contractor will be required to carefully uninstall old cabling and/or trunking in areas where the LAN is undergoing an overhaul. This should be done neatly to avoid tampering with the wall painting and cable/trunking to be reused.	
7.	Equipment migration	The contractor will be required to carefully uninstall equipment from the old cabinet and migrate them to the newly installed cabinet. This should be done carefully to avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The contractor will be required to return to site and rectify any defects that may occur within the defect liability period at no extra cost to the Authority.	
9.	Drawings and documentation	On completion of the works the contractor <u>MUST</u> provide all the relevant documentation and the LAN schematic diagram for each site.	
10.	Labeling	All the data points and ports on the Patch panels must be well labeled with Printed labels. The patch cords must also be labeled on both ends to match port numbers.	
11.	Testing and Commissioning	The Contractor is required to carry out professional tests and provide results both in printed and in soft copy. This shall apply to both copper and fibre.  A joint test and commissioning will be carried out by KRA and the contractor.	

#### X. MINIMUM TECHNICAL SPECIFICATIONS FOR ISEBANIA

## 1. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years (bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	

## 2. Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 3. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs Should also be backward compatible to cat 5e	
10.	Shield	Hinged cable retention/ grounding	

	Feature	Minimum Requirements	Bidder's response
		clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

## 4. Minimum Technical Specifications for 1m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 5. Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures
2.	Size	200mm by 50mm, two compartments
3.	Length	2.4m
4.	Gauge	1.2mm

## 6. Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	
5.	Gauge	1.2mm	

## 7. Minimum Technical Specifications for 100mmx50mm Curved Floor Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	100mm by 50mm, two compartments	
3.	Form	Curved	
4.	Length	2.4m	
5.	Gauge	1.2mm	

## 8. Minimum Technical Specifications for 22U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand	

	Feature	Minimum Requirements	Bidder's response
2.	Form Factor	22 U floor standing standard data cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window Rear door: high-flow mesh Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

#### 9. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### The Scope of Works

The successful bidder shall be required to carry out the following works; Installation of new and revamping of the existing LAN for KRA Isebania station. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labelling etc. The fibre works entail the installation of indoor or outdoor fibre cables to interconnect floors within the same building or offices within the same campus. Fibre installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation.

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly	
		as per the LAN design and the engineer's	
		instructions.	
		All cables must run through the trunkings.	
2.	Horizontal	The horizontal cabling should be done neatly	
	cabling	and professionally as per the LAN design and	
		the engineer's instructions on site.	
3.	Vertical	The backbone is typically done using fibre.	
	cabling	Installation of fibre should be carried out	
		according to the instructions of the network	
		engineer on site. At least 6 cores must be	
		terminated for each side of a cable (i.e. 12	
		terminations).	
4.	Tools &	The contractor must have all the tools and	
	accessories	accessories required to install and test Local	
		area Networks (LANs).	
5.	Quality of	The contractor is required to provide high	
	works	standard installation service and quality	
		workmanship. Cable management must also	
		be neatly done.	
		The trunking joints must flush and with no	
		gapes. Knockouts must be installed neatly	
		with no gapes or spaces.	
6.	Old	The contractor will be required to carefully	
	cable/trunking	uninstall old cabling and/or trunking in areas	
	uninstallation	where the LAN is undergoing an overhaul.	
		This should be done neatly to avoid tampering	
		with the wall painting and cable/trunking to	
		be reused.	
7.	Equipment	The contractor will be required to carefully	
/	migration	uninstall equipment from the old cabinet and	
	0	migrate them to the newly installed cabinet.	
		This should be done carefully to avoid	
		damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year.	
	, variancy	The contractor will be required to return to	
		site and rectify any defects that may occur	
		within the defect liability period at no extra	
		cost to the Authority.	
9.	Drawings and	On completion of the works the contractor	
'	documentation	MUST provide all the relevant	
		documentation and the LAN schematic	
		diagram for each site.	
10.	Labeling	All the data points and ports on the Patch	
10.		panels must be well labeled with Printed	
		labels. The patch cords must also be labeled on	
		both ends to match port numbers.	
11	Testing and	The Contractor is required to carry out	
	Commissionin	professional tests and provide results both in	
	g	printed and in soft copy. This shall apply to	
	0	both copper and fibre.	
		A joint test and commissioning will be carried	
		out by KRA and the contractor.	
	L	1 cat 2 marana me contractor.	I .

	A joint test and commissioning w out by KRA and the contractor.	ill be carried		
Bidder's Signatu	re	Date	Stamp	

## D. LOT IV TECHNICAL SPECIFICATIONS

## I. MINIMUM TECHNICAL SPECIFICATIONS FOR LAMU TSO

## 1. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand,	
		in existence for at least 10 years (bidder	
		must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

## $\textbf{2.} \ \ \textbf{Minimum Technical Specifications for CAT 6A 48-Port Ethernet Patch Panel}$

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	48 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e-coated	
13.	Category and	CAT6A and downward compatible with	
	compatibility	CAT5e/CAT5	
14.	Termination	By Z-tool	

## 3. Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
15.	Brand	Internationally recognized brand	
16.	Port Density	24 port (Fully populated)	
17.	Application	Quick snap	
18.	Cable Management	Rear Cable management bar installed	
19.	Labels	Printable labels MUST be available	
20.	Wiring	T568A/T568B compliant and easy to read	
21.	Contact materials	Plated phosphor bronze, stainless steel	
22.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
23.	Current rating	1.5 A	
24.	Contact resistance	20 mΩ	
25.	Insulation resistance	500 ΜΩ	
26.	Panel material	18 gauge cold rolled steel, black e-coated	
27.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
28.	Termination	By Z-tool	

## 4. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	<b>Minimum Requirements</b>	Bidder's response
1.	Brand	Internationally recognized, matured brand,	
		in existence for at least 10 years (bidder	
		must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed	
		on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both	
		angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs	
		Should also be backward compatible to cat	
		5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

## 5. Minimum Technical Specifications for 1m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 6. Minimum Technical Specifications for 3m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 7. Minimum Technical Specifications for 32U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	32 U floor standing standard data cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window Rear door: high-flow mesh Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	

	Feature	Minimum Requirements	Bidder's response
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

## 8. Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre- punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4m	
4.	Gauge	1.2mm	

## 9. Minimum Technical Specifications for 200mm Single Gang Service Plates/ Knockouts

	Feature	Minimum Requirements	Bidder's response
	Material	Metallic and same color as trunking	
2.	Height	250mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 250mm by 50mm trunking	
5.	Gauge	1.2mm	

## 10.Minimum Technical Specifications for 1.5KVA Rack-Mounted UPS

	Feature	Minimum Requirement	Bidders Response			
	Brand and Model	Internationally recognized brand (bidder must specify brand and model)				
		Output				
1.	Output Power Capacity	900 Watts / 1500 VA				
2.	Max Configurable Power	900 Watts / 1500 VA				
3.	Nominal Output Voltage	230V				
4.	Output Voltage Distortion	Less than 5% at full load				
5.	Output Frequency (sync to mains)	47 - 53 Hz for 50 Hz nominal, 57 - 63 Hz for 60 Hz nominal				
6.	Topology	Line interactive				
7.	Waveform Type	Stepped approximation to a Sine wave				
8.	Output Connections	Four (4) IEC 320 C13 Two (2) IEC jumpers				
Input						
9.	Nominal Input Voltage	230V				
10.	Input Frequency	50/60 Hz +/- 3 Hz (auto sensing)				
11.	Input Connections	IEC-320 C14				
12.	Battery Type	Maintenance free sealed lead-acid with suspended electrolyte, leak proof				

	reature	William Requirement	bidders Response
13.	Input voltage range for main operations	180 - 287V	
14.	Input voltage adjustable range for mains operation	170 - 300V	
15.	Typical recharge time	3 hour(s)	
16.	Typical Backup Time at Half Load	20.9 minutes (432.5 Watts)	
17.	Typical Backup Time at Full Load	7.6 minutes (865 Watts)	
	-	Communications & Management	
18.	Interface Ports	RJ-45 Serial, USB	
19.	Control panel	Multi-function LCD status and control console	
20.	Audible Alarm	Alarm when on battery : distinctive low battery alarm : configurable delays	
	1	Surge Protection and Filtering	
21.	Surge energy rating	459Joules	
22.	Filtering	Full time multi-pole noise filtering : 0.3% IEEE surge let-through : zero clamping response time : meets UL 1449	
23.	Data Line filtering	RJ-45 modem/Fax/DSL/10-100 Base-T protection	
24.	Standard Warranty	2 years repair or replace	
25.	Accessories	Power cords (at least 1.83M), CD with software, Documentation CD, Rack Mounting brackets, Smart UPS signaling RS-232 cable, USB cable, User Manual	

**Minimum Requirement** 

**Bidders Response** 

#### 11. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### The Scope of Works

Feature

The successful bidder shall be required to carry out the following works; Installation of a new LAN for KRA Lamu TSO. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc. The fiber works entail the installation of indoor or outdoor fiber cables to interconnect floors within the same building or offices within the same campus. Fiber installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before the commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per the	
		LAN design and the engineer's instructions.	
		All cables must run through the trunkings.	
2.	Horizontal	The horizontal cabling should be done neatly and	
	cabling	professionally as per the LAN design and the engineer's	
		instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre. Installation of	
		fibre should be carried out according to the instructions of	
		the network engineer on site. At least 6 cores must be	
	m 1 0	terminated for each side of a cable (i.e. 12 terminations).	
4.	Tools &	The contractor must have all the tools and accessories	
	accessories	required to install and test Local area Networks (LANs).	
5.	Quality of works	The contractor is required to provide high standard	
		installation service and quality workmanship. Cable	
		management must also be neatly done.	
		The trunking joints must flush and with no gapes.	
		Knockouts must be installed neatly with no gapes or spaces.	
		The knockouts <b>MUST</b> be of the same shade as that of the trunkings.	
6.	Old cable	The contractor will be required to carefully uninstall old	
0.	/trunking	cabling and/or trunking in areas where the LAN is	
	uninstallation	undergoing an overhaul. This should be done neatly to	
		avoid tampering with the wall painting and cable/trunking	
		to be reused.	
7.	Equipment	The contractor will be required to carefully uninstall	
	migration	equipment from the old cabinet and migrate them to the	
		newly installed cabinet. This should be done carefully to	
	TAT .	avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The	
		contractor will be required to return to site and rectify any defects that may occur within the defect liability period at	
		no extra cost to the Authority.	
9.	Drawings and	On completion of the works the contractor <b>MUST</b> provide	
	documentation	all the relevant documentation and the LAN schematic	
		diagram for each site.	
10.	Labeling	All the data points and ports on the Patch panels must be	
		well labeled with Printed labels. The patch cords must also	
11	Togting and	be labeled on both ends to match port numbers.	
11.	Testing and	The Contractor is required to carry out professional tests	
	Commissioning	and provide results both in printed and in soft copy. This shall apply to both copper and fibre.	
		A joint test and commissioning will be carried out by KRA	
		and the contractor.	
<u> </u>	1	una inc contractor.	

#### II. MINIMUM TECHNICAL SPECIFICATIONS FOR LAMU AIRPORT

## 1. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand,	
		in existence for at least 10 years (bidder	
		must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	

	Feature	Minimum Requirements	Bidder's response
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

## 2. Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e-coated	
13.	Category and	CAT6A and downward compatible with	
	compatibility	CAT5e/CAT5	
14.	Termination	By Z-tool	

# 3. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand,	
		in existence for at least 10 years (bidder	
		must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed	
		on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both	
		angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs	
		Should also be backward compatible to cat	
		5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

## 4. Minimum Technical Specifications for 1m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

#### 5. Minimum Technical Specifications for 3m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 6. Minimum Technical Specifications for 12U Wall Mount Data Cabinet

	Feature	Minimum Requirements	Bidder's response
7.	Brand	Internationally recognized, matured brand	
8.	Form Factor	12 U wall-mount data cabinet with a hinged back	
9.	Dimension	600x800mm	
10.	Construction	Front door: with glass window Rear: Hinged Back Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
11.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
12.	Cable manager	Three (3) pieces of 1U black metallic horizontal Dual-sided cable managers	

#### 7. Minimum Technical Specifications for 100mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre- punched fixing holes for permanent wall structures	
2.	Size	100mm by 50mm, two compartments	
3.	Length	2.4m	
4.	Gauge	1.2mm	

### 8. Minimum Technical Specifications for 100mm Single Gang Service Plates/ Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	250mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 100mm by 50mm trunking	
5.	Gauge	1.2mm	

## 9. Minimum Technical Specifications for 100mm Double Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	100mm	
3.	Width	Double Gang	

4.	Compatibility	Compatible	with	100mm	by	50mm	
		trunking					
5.	Gauge	1.2mm					

# 10.Minimum Technical Specifications for 1.5KVA Rack-Mounted UPS

	Feature	Minimum Requirement	Bidders Response				
	Brand and Model	Internationally recognized brand (bidder must specify brand and model)					
	Output						
1.	Output Power Capacity	900 Watts / 1500 VA					
2.	Max Configurable Power	900 Watts / 1500 VA					
3.	Nominal Output Voltage	230V					
4.	Output Voltage Distortion	Less than 5% at full load					
5.	Output Frequency (sync to mains)	47 - 53 Hz for 50 Hz nominal, 57 - 63 Hz for 60 Hz nominal					
6.	Topology	Line interactive					
7.	Waveform Type	Stepped approximation to a Sine wave					
8.	Output Connections	Four (4) IEC 320 C13 Two (2) IEC jumpers					
		Input					
9.	Nominal Input Voltage	230V					
10.	Input Frequency	50/60 Hz +/- 3 Hz (auto sensing)					
11.	Input Connections	IEC-320 C14					
12.	Battery Type	Maintenance free sealed lead-acid with suspended electrolyte, leak proof					
13.	Input voltage range for main operations	180 - 287V					
14.	Input voltage adjustable range for mains operation	170 - 300V					
15.	Typical recharge time	3 hour(s)					
16.	Typical Backup Time at Half Load	20.9 minutes (432.5 Watts)					
17.	Typical Backup Time at Full Load	7.6 minutes (865 Watts)					
		Communications & Management					
18.	Interface Ports	RJ-45 Serial, USB					
19.	Control panel	Multi-function LCD status and control console					
20.	Audible Alarm	Alarm when on battery : distinctive low battery alarm : configurable delays					
		Surge Protection and Filtering					
21.	Surge energy rating	459Joules					
22.	Filtering	Full time multi-pole noise filtering : 0.3% IEEE surge let-through : zero clamping response time : meets UL 1449					

	Feature	Minimum Requirement	<b>Bidders Response</b>
23.	Data Line filtering	RJ-45 modem/Fax/DSL/10-100 Base-T protection	
24.	Standard Warranty	2 years repair or replace	
25.	Accessories	Power cords (at least 1.83M), CD with software, Documentation CD, Rack Mounting brackets, Smart UPS signaling RS-232 cable, USB cable, User Manual	

#### 11. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### **The Scope of Works**

The successful bidder shall be required to carry out the following works; Installation of a new LAN for KRA Lamu Airport. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc. The fiber works entail the installation of indoor or outdoor fiber cables to interconnect floors within the same building or offices within the same campus. Fiber installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before the commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation

No	Feature	Minimum Requirements	Bidder's Response
12.	Trunking	The metal trunkings must be installed neatly as per the LAN design and the engineer's instructions. All cables must run through the trunkings.	
13.	Horizontal cabling	The horizontal cabling should be done neatly and professionally as per the LAN design and the engineer's instructions on site.	
14.	Vertical cabling	The backbone is typically done using fibre. Installation of fibre should be carried out according to the instructions of the network engineer on site. At least 6 cores must be terminated for each side of a cable (i.e. 12 terminations).	
15.	Tools & accessories	The contractor must have all the tools and accessories required to install and test Local area Networks (LANs).	
16.	Quality of works	The contractor is required to provide high standard installation service and quality workmanship. Cable management must also be neatly done.  The trunking joints must flush and with no gapes. Knockouts must be installed neatly with no gapes or spaces. The knockouts <b>MUST</b> be of the same shade as that of the trunkings.	
17.	Old cable /trunking uninstallation	The contractor will be required to carefully uninstall old cabling and/or trunking in areas where the LAN is undergoing an overhaul. This should be done neatly to avoid tampering with the wall painting and cable/trunking to be reused.	

18.	Equipment migration	The contractor will be required to carefully uninstall equipment from the old cabinet and migrate them to the newly installed cabinet. This should be done carefully to	
		avoid damaging the equipment.	
19.	Warranty	The defect liability period shall be one (1) year. The contractor will be required to return to site and rectify any defects that may occur within the defect liability period at no extra cost to the Authority.	
20.	Drawings and documentation	On completion of the works the contractor <u>MUST</u> provide all the relevant documentation and the LAN schematic diagram for each site.	
21.	Labeling	All the data points and ports on the Patch panels must be well labeled with Printed labels. The patch cords must also be labeled on both ends to match port numbers.	
22.	Testing and Commissioning	The Contractor is required to carry out professional tests and provide results both in printed and in soft copy. This shall apply to both copper and fibre.  A joint test and commissioning will be carried out by KRA and the contractor.	

#### III. MINIMUM TECHNICAL SPECIFICATIONS FOR VOI

## 1. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

## 2. Minimum Technical Specifications for CAT 6A 48-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	48 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e-coated	
13.	Category and	CAT6A and downward compatible with	
	compatibility	CAT5e/CAT5	
14.	Termination	By Z-tool	

## 3. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand,	
		in existence for at least 10 years (bidder	
		must specify brand and model)	

	Feature	Minimum Requirements	Bidder's response
2.	Assembly	CAT 6A dual RJ45 outlet module installed	
		on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs Should also be backward compatible to cat 5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

## 4. Minimum Technical Specifications for 1m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 5. Minimum Technical Specifications for 3m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

# 6. Minimum Technical Specifications for 5m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	5 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 7. Minimum Technical Specifications for 32U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	

	Feature	Minimum Requirements	Bidder's response
2.	Form Factor	32 U floor standing standard data cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window Rear door: high-flow mesh Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

#### 8. Minimum Technical Specifications for 100mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre- punched fixing holes for permanent wall structures	
2.	Size	100mm by 50mm, two compartments	
3.	Length	2.4m	
4.	Gauge	1.2mm	

#### 9. Minimum Technical Specifications for 250mm Single Gang Service Plates/ Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	250mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 250mm by 50mm trunking	
5.	Gauge	1.2mm	

#### 10. Minimum Technical Specifications for 200mm Double Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Double Gang	
4.	Compatibility	Compatible with 250mm by 50mm trunking	
5.	Gauge	1.2mm	

#### 11. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### The Scope of Works

The successful bidder shall be required to carry out the following works; Installation of a new LAN to replace the old existing LAN for KRA Voi. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc. The fiber works entail the installation of indoor or outdoor fiber cables to interconnect floors within the same building or offices within the same campus. Fiber installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before the commencement

of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

**NB**: KRA will provide **65 pieces** of 250mmx50mm partitioned trunkings, and bidders are expected to include the installation cost of associated accessories. Additionally, a sample of the sleeves required for installing the trunkings will be made available for reference.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per the LAN design and the engineer's instructions. All cables must run through the trunkings.	
2.	Horizontal cabling	The horizontal cabling should be done neatly and professionally as per the LAN design and the engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre. Installation of fibre should be carried out according to the instructions of the network engineer on site. At least 6 cores must be terminated for each side of a cable (i.e. 12 terminations).	
4.	Tools & accessories	The contractor must have all the tools and accessories required to install and test Local area Networks (LANs).	
5.	Quality of works	The contractor is required to provide high standard installation service and quality workmanship. Cable management must also be neatly done.  The trunking joints must flush and with no gapes. Knockouts must be installed neatly with no gapes or spaces. The knockouts <b>MUST</b> be of the same shade as that of the trunkings.	
6.	Old cable /trunking uninstallation	The contractor will be required to carefully uninstall old cabling and/or trunking in areas where the LAN is undergoing an overhaul. This should be done neatly to avoid tampering with the wall painting and cable/trunking to be reused.	
7.	Equipment migration	The contractor will be required to carefully uninstall equipment from the old cabinet and migrate them to the newly installed cabinet. This should be done carefully to avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The contractor will be required to return to site and rectify any defects that may occur within the defect liability period at no extra cost to the Authority.	
9.	Drawings and documentation	On completion of the works the contractor <u>MUST</u> provide all the relevant documentation and the LAN schematic diagram for each site.	
10.	Labeling	All the data points and ports on the Patch panels must be well labeled with Printed labels. The patch cords must also be labeled on both ends to match port numbers.	
11.	Testing and Commissioning	The Contractor is required to carry out professional tests and provide results both in printed and in soft copy. This shall apply to both copper and fibre.  A joint test and commissioning will be carried out by KRA and the contractor.	

#### IV. MINIMUM TECHNICAL SPECIFICATIONS FOR DIANI

#### 1. Minimum Technical Specifications for 12 Core Multimode Armored Fiber Cable

	Feature	<b>Minimum Requirements</b>	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years(bidder must specify brand)	
2.	Jacket characteristics	Water Blocking Aramid Yarn	
	& Material	Armored	
		PVC	
3.	Mode of operation	Multimode	
4.	Core density	12 cores	
5.	Attenuation (Max)	3.50 dB/km @ 850nm	
6.	Standards	Optical and mechanical performance:	
		IEC 60794-2, IEC 60794-2-20, ISO	
		11801, EN 50173-1	

## 2. Minimum Technical Specifications for 12 Port Multimode Modular Fiber ODF

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Mode of operation	Multimode	
3.	Port density	• 12 ports (24 cores) • Fully populated	
4.	Form Factor	1HU	
5.	Adapter	LC	
6.	Accessories	<ul><li>24 Pigtail connectors</li><li>24 core Splice tray</li><li>30 Heat shrink sleeves</li></ul>	

## 3. Minimum Technical Specifications for 24 Port Multimode Modular Fiber ODF

	Feature	Minimum Requirements	Bidder's response
7.	Brand	Internationally recognized, matured brand	
8.	Mode of operation	Multimode	
9.	Port density	• 24 ports (48 cores) • Fully populated	
10.	Form Factor	1HU	
11.	Adapter	LC	
12.	Accessories	<ul><li>48 Pigtail connectors</li><li>48 core Splice tray</li><li>60 Heat shrink sleeves</li></ul>	

## 4. Minimum Technical Specifications for 1G Multimode SFP Transceiver Modules

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand (bidder must specify brand )	
2.	Mode of operation	Multimode	
3.	Compatibility	Must be compatible with Cisco switches	
4.	Form Factor	Small pluggable form factor	
5.	Capacity	1 Gigabyte (1G)	

## 5. Minimum Technical Specifications for 1.5M LC-LC Multimode Fiber Patch Cords

	Feature	Minimum Requirements	Bidder's response
5.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10 years.	
6.	Mode	Multimode <b>OM3 50/125</b>	
7.	Connector	Must be <b>LC-LC</b>	
8.	Length	1.5m	

## 6. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand,	
		in existence for at least 10 years (bidder	
		must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

## 7. Minimum Technical Specifications for CAT 6A 48-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	48 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e-coated	
13.	Category and	CAT6A and downward compatible with	
	compatibility	CAT5e/CAT5	
14.	Termination	By Z-tool	

## 8. Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e-coated	
13.	Category and	CAT6A and downward compatible with	
	compatibility	CAT5e/CAT5	
14.	Termination	By Z-tool	

## 9. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	<b>Minimum Requirements</b>	Bidder's response
1.	Brand	Internationally recognized, matured brand,	
		in existence for at least 10 years (bidder	
		must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed	
		on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both	
		angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs	
		Should also be backward compatible to cat	
		5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

# 10.Minimum Technical Specifications for 1m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 11. Minimum Technical Specifications for 3m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

# 12. Minimum Technical Specifications for 5m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	5 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

# 13. Minimum Technical Specifications for 12U Wall Mount Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	12 U wall-mount data cabinet with a hinged back	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window Rear: Hinged Back Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Three (3) pieces of 1U black metallic horizontal Dual-sided cable managers	

# 14. Minimum Technical Specifications for 32U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	32 U floor standing standard data cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window Rear door: high-flow mesh Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

## 15. Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre- punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4m	
4.	Gauge	1.2mm	

# 16. Minimum Technical Specifications for 200mm Single Gang Service Plates/ Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	250mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 250mm by 50mm trunking	
5.	Gauge	1.2mm	

# 17. Minimum Technical Specifications for 1.5KVA Rack-Mounted UPS

	Feature	Minimum Requirement	<b>Bidders Response</b>		
	Brand and Model	Internationally recognized brand (bidder must specify brand and model)			
		Output			
1.	Output Power Capacity	900 Watts / 1500 VA			
2.	Max Configurable Power	900 Watts / 1500 VA			
3.	Nominal Output Voltage	230V			
4.	Output Voltage Distortion	Less than 5% at full load			
5.	Output Frequency (sync to mains)	47 - 53 Hz for 50 Hz nominal, 57 - 63 Hz for 60 Hz nominal			
6.	Topology	Line interactive			
7.	Waveform Type	Stepped approximation to a Sine wave			
8.	Output Connections	Four (4) IEC 320 C13 Two (2) IEC jumpers			
		Input			
9.	Nominal Input Voltage	230V			
10.	Input Frequency	50/60 Hz +/- 3 Hz (auto sensing)			
11.	Input Connections	IEC-320 C14			
12.	Battery Type	Maintenance free sealed lead-acid with suspended electrolyte, leak proof			
13.	Input voltage range for main operations	180 - 287V			
14.	Input voltage adjustable range for mains operation	170 - 300V			
15.	Typical recharge time	3 hour(s)			
16.	Typical Backup Time at Half Load	20.9 minutes (432.5 Watts)			
17.	Typical Backup Time at Full Load	7.6 minutes (865 Watts)			
		Communications & Management			
18.	Interface Ports	RJ-45 Serial, USB			
19.	Control panel	Multi-function LCD status and control console			
20.	Audible Alarm	Alarm when on battery : distinctive low battery alarm : configurable delays			
	Surge Protection and Filtering				
21.	Surge energy rating	459Joules			
22.	Filtering	Full time multi-pole noise filtering : 0.3% IEEE surge let-through : zero clamping response time : meets UL 1449			
23.	Data Line filtering	RJ-45 modem/Fax/DSL/10-100 Base-T protection			
24.	Standard Warranty	2 years repair or replace			
25.	Accessories	Power cords (at least 1.83M), CD with software, Documentation CD, Rack			

Feature	Minimum Requirement	Bidders Response
	Mounting brackets, Smart UPS signaling	
	RS-232 cable, USB cable, User Manual	

#### 18.TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### The Scope of Works

The successful bidder shall be required to carry out the following works; Installation of a new LAN for KRA Diani. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc. The fiber works entail the installation of indoor or outdoor fiber cables to interconnect floors within the same building or offices within the same campus. Fiber installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before the commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per the LAN design and the engineer's instructions. All cables must run through the trunkings.	
2.	Horizontal cabling	The horizontal cabling should be done neatly and professionally as per the LAN design and the engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre. Installation of fibre should be carried out according to the instructions of the network engineer on site. At least 6 cores must be terminated for each side of a cable (i.e. 12 terminations).	
4.	Tools & accessories	The contractor must have all the tools and accessories required to install and test Local area Networks (LANs).	
5.	Quality of works	The contractor is required to provide high standard installation service and quality workmanship. Cable management must also be neatly done.  The trunking joints must flush and with no gapes. Knockouts must be installed neatly with no gapes or spaces. The knockouts <b>MUST</b> be of the same shade as that of the trunkings.	
6.	Old cable /trunking uninstallation	The contractor will be required to carefully uninstall old cabling and/or trunking in areas where the LAN is undergoing an overhaul. This should be done neatly to avoid tampering with the wall painting and cable/trunking to be reused.	
7-	Equipment migration	The contractor will be required to carefully uninstall equipment from the old cabinet and migrate them to the newly installed cabinet. This should be done carefully to avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The contractor will be required to return to site and rectify any defects that may occur within the defect liability period at no extra cost to the Authority.	
9.	Drawings and documentation	On completion of the works the contractor <u>MUST</u> provide all the relevant documentation and the LAN schematic	

		diagram for each site.	
10.	Labeling	All the data points and ports on the Patch panels must be	
		well labeled with Printed labels. The patch cords must also	
		be labeled on both ends to match port numbers.	
11.	Testing and	The Contractor is required to carry out professional tests	
	Commissioning	and provide results both in printed and in soft copy. This	
		shall apply to both copper and fibre.	
		A joint test and commissioning will be carried out by KRA	
		and the contractor.	

## V. MINIMUM TECHNICAL SPECIFICATIONS FOR KILIFI

## 1. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand,	
		in existence for at least 10 years (bidder	
		must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

# 2. Minimum Technical Specifications for CAT 6A 48-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	48 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e-coated	
13.	Category and	CAT6A and downward compatible with	
	compatibility	CAT5e/CAT5	
14.	Termination	By Z-tool	

## 3. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs	

	Feature	Minimum Requirements	Bidder's response
		Should also be backward compatible to cat	
		5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

#### 4. Minimum Technical Specifications for 1m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

#### 5. Minimum Technical Specifications for 3m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 6. Minimum Technical Specifications for 5m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
4.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
5.	Category	CAT 6A 4-pair Ethernet cable	
6.	Length	5 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 7. Minimum Technical Specifications for 32U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	32 U floor standing standard data cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window Rear door: high-flow mesh Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	

	Feature	Minimum Requirements	Bidder's response
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

# 8. Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre- punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4m	
4.	Gauge	1.2mm	

# 9. Minimum Technical Specifications for 200mm Single Gang Service Plates/ Knockouts

	Feature	Minimum Requirements	Bidder's response
	Material	Metallic and same color as trunking	
	Height	200mm	
2.	Width	Single Gang	
3.	Compatibility	Compatible with 200mm by 50mm trunking	
4.	Gauge	1.2mm	

# 10.Minimum Technical Specifications for 1.5KVA Rack-Mounted UPS

	Feature	Minimum Requirement	Bidders Response
	Brand and Model	Internationally recognized brand (bidder must specify brand and model)	
		Output	
1.	Output Power Capacity	900 Watts / 1500 VA	
2.	Max Configurable Power	900 Watts / 1500 VA	
3.	Nominal Output Voltage	230V	
4.	Output Voltage Distortion	Less than 5% at full load	
5.	Output Frequency (sync to mains)	47 - 53 Hz for 50 Hz nominal, 57 - 63 Hz for 60 Hz nominal	
6.	Topology	Line interactive	
7.	Waveform Type	Stepped approximation to a Sine wave	
8.	Output Connections	Four (4) IEC 320 C13 Two (2) IEC jumpers	
		Input	
9.	Nominal Input Voltage	230V	
10.	Input Frequency	50/60 Hz +/- 3 Hz (auto sensing)	
11.	Input Connections	IEC-320 C14	
12.	Battery Type	Maintenance free sealed lead-acid with suspended electrolyte, leak proof	
13.	Input voltage range for main operations	180 - 287V	

	Feature	Minimum Requirement	Bidders Response
14.	Input voltage adjustable range for mains operation	170 - 300V	
15.	Typical recharge time	3 hour(s)	
16.	Typical Backup Time at Half Load	20.9 minutes (432.5 Watts)	
17.	Typical Backup Time at Full Load	7.6 minutes (865 Watts)	
	1	Communications & Management	l
18.	Interface Ports	RJ-45 Serial, USB	
19.	Control panel	Multi-function LCD status and control console	
20.	Audible Alarm	Alarm when on battery : distinctive low battery alarm : configurable delays	
		Surge Protection and Filtering	
21.	Surge energy rating	459Joules	
22.	Filtering	Full time multi-pole noise filtering : 0.3% IEEE surge let-through : zero clamping response time : meets UL 1449	
23.	Data Line filtering	RJ-45 modem/Fax/DSL/10-100 Base-T protection	
24.	Standard Warranty	2 years repair or replace	
25.	Accessories	Power cords (at least 1.83M), CD with software, Documentation CD, Rack Mounting brackets, Smart UPS signaling RS-232 cable, USB cable, User Manual	

#### 11. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### The Scope of Works

The successful bidder shall be required to carry out the following works; Installation of a new LAN for KRA Lamu TSO. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc. The fiber works entail the installation of indoor or outdoor fiber cables to interconnect floors within the same building or offices within the same campus. Fiber installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before the commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per the	
		LAN design and the engineer's instructions.	
		All cables must run through the trunkings.	

2.	Horizontal cabling	The horizontal cabling should be done neatly and professionally as per the LAN design and the engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre. Installation of fibre should be carried out according to the instructions of the network engineer on site. At least 6 cores must be terminated for each side of a cable (i.e. 12 terminations).	
4.	Tools & accessories	The contractor must have all the tools and accessories required to install and test Local area Networks (LANs).	
5.	Quality of works	The contractor is required to provide high standard installation service and quality workmanship. Cable management must also be neatly done.  The trunking joints must flush and with no gapes. Knockouts must be installed neatly with no gapes or spaces. The knockouts <b>MUST</b> be of the same shade as that of the trunkings.	
6.	Old cable /trunking uninstallation	The contractor will be required to carefully uninstall old cabling and/or trunking in areas where the LAN is undergoing an overhaul. This should be done neatly to avoid tampering with the wall painting and cable/trunking to be reused.	
7-	Equipment migration	The contractor will be required to carefully uninstall equipment from the old cabinet and migrate them to the newly installed cabinet. This should be done carefully to avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The contractor will be required to return to site and rectify any defects that may occur within the defect liability period at no extra cost to the Authority.	
9.	Drawings and documentation	On completion of the works the contractor <u>MUST</u> provide all the relevant documentation and the LAN schematic diagram for each site.	
10.	Labeling	All the data points and ports on the Patch panels must be well labeled with Printed labels. The patch cords must also be labeled on both ends to match port numbers.	
11.	Testing and Commissioning	The Contractor is required to carry out professional tests and provide results both in printed and in soft copy. This shall apply to both copper and fibre.  A joint test and commissioning will be carried out by KRA and the contractor.	

# VI. MINIMUM TECHNICAL SPECIFICATIONS FOR TAVETA OSBP

# 1. Minimum Technical Specifications for 12 Core Multimode Armored Fiber Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years(bidder must specify brand)	
2.	Jacket characteristics	Water Blocking Aramid Yarn	
	& Material	Armored PVC	
3.	Mode of operation	Multimode	
4.	Core density	12 cores	
5.	Attenuation (Max)	3.50 dB/km @ 850nm	
6.	Standards	Optical and mechanical performance:	
		IEC 60794-2, IEC 60794-2-20, ISO	
		11801, EN 50173-1	

#### 2. Minimum Technical Specifications for 12 Port Multimode Modular Fiber ODF

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Mode of operation	Multimode	
3.	Port density	• 12 ports (24 cores) • Fully populated	
4.	Form Factor	1HU	
5.	Adapter	LC	
6.	Accessories	<ul><li>24 Pigtail connectors</li><li>24 core Splice tray</li><li>30 Heat shrink sleeves</li></ul>	

## 3. Minimum Technical Specifications for 1G Multimode SFP Transceiver Modules

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand (bidder must specify brand )	
2.	Mode of operation	Multimode	
3.	Compatibility	Must be compatible with Cisco switches	
4.	Form Factor	Small pluggable form factor	
5.	Capacity	1 Gigabyte (1G)	

## 4. Minimum Technical Specifications for 1.5M LC-LC Multimode Fiber Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10 years.	
2.	Mode	Multimode <b>OM3 50/125</b>	
3.	Connector	Must be <b>LC-LC</b>	
4.	Length	1.5m	

#### 5. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand,	
		in existence for at least 10 years (bidder	
		must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

## 6. Minimum Technical Specifications for CAT 6A 48-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	48 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	

	Feature	Minimum Requirements	Bidder's response
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e-coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

### 7. Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e-coated	
13.	Category and	CAT6A and downward compatible with	
	compatibility	CAT5e/CAT5	
14.	Termination	By Z-tool	

# 8. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand,	
		in existence for at least 10 years (bidder	
		must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed	
		on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both	
		angled and flat mounting orientations	
5.	Contact resistance	$20~\mathrm{m}\Omega$	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs	
		Should also be backward compatible to cat	
		5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

## 9. Minimum Technical Specifications for 1m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	

	Feature	Minimum Requirements	Bidder's response
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

#### 10.Minimum Technical Specifications for 3m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 11. Minimum Technical Specifications for 5m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	5 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 12. Minimum Technical Specifications for 32U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	32 U floor standing standard data cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window Rear door: high-flow mesh Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

# 13. Minimum Technical Specifications for 100mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
5.	Material	Powder coated metal trunking with pre- punched fixing holes for permanent wall structures	
6.	Size	100mm by 50mm, two compartments	
7.	Length	2.4m	
8.	Gauge	1.2mm	

## 14. Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre- punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4m	
4.	Gauge	1.2mm	

## 15. Minimum Technical Specifications for 20mm Single Gang Service Plates/ Knockouts5

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	250mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 250mm by 50mm trunking	
5.	Gauge	1.2mm	

## 16. Minimum Technical Specifications for 2m Threaded Rods

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Steel threaded rods	
2.	Length	2m	
3.	Size	M10	

#### 17. Minimum Technical Specifications for 300mm Trapeze Hanger

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Galvanize steel	
2.	Rod hole size	12mm at the ends	
3.	Type	Flat	
4.	Length	300mm	
5.	Width	50mm	
6.	Thickness	3mm	

### 18. Minimum Technical Specifications for Rawl Bolts M10 Mm

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Steel threaded rods	
2.	Size	M10	
3.	Packaging	Packets of 100pcs	

#### 19. Minimum Technical Specifications for M10 Nuts with Washers

	Feature	Minimum Requirements	Bidder's Response
1.	Material	Steel	
2.	Size	• Nuts M10	
		• Washers M10	
3.	Packaging	Packets of 100pcs	

#### The Scope of Works

The successful bidder shall be required to carry out the following works; Installation of a new LAN for KRA Taveta OSBP. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc. The fiber works entail the installation of indoor or outdoor fiber cables to interconnect floors within the same building or offices within the same campus. Fiber installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before the commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

**NB**: KRA will provide **pieces** of 250mmx50mm partitioned trunkings, and bidders are expected to include the installation cost of associated accessories. Additionally, a sample of the sleeves required for installing the trunkings will be made available for reference.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per the LAN design and the engineer's instructions. All cables must run through the trunkings.	
2.	Horizontal cabling	The horizontal cabling should be done neatly and professionally as per the LAN design and the engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre. Installation of fibre should be carried out according to the instructions of the network engineer on site. At least 6 cores must be terminated for each side of a cable (i.e. 12 terminations).	
4.	Tools & accessories	The contractor must have all the tools and accessories required to install and test Local area Networks (LANs).	
5.	Quality of works	The contractor is required to provide high standard installation service and quality workmanship. Cable management must also be neatly done.  The trunking joints must flush and with no gapes. Knockouts must be installed neatly with no gapes or spaces. The knockouts <b>MUST</b> be of the same shade as that of the trunkings.	
6.	Old cable /trunking uninstallation	The contractor will be required to carefully uninstall old cabling and/or trunking in areas where the LAN is undergoing an overhaul. This should be done neatly to avoid tampering with the wall painting and cable/trunking to be reused.	
7.	Equipment migration	The contractor will be required to carefully uninstall equipment from the old cabinet and migrate them to the newly installed cabinet. This should be done carefully to avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The contractor will be required to return to site and rectify any defects that may occur within the defect liability period at no extra cost to the Authority.	
9.	Drawings and documentation	On completion of the works the contractor <u>MUST</u> provide all the relevant documentation and the LAN schematic	

		diagram for each site.	
10.	Labeling	All the data points and ports on the Patch panels must be	
		well labeled with Printed labels. The patch cords must also	
		be labeled on both ends to match port numbers.	
11.	Testing and	The Contractor is required to carry out professional tests	
	Commissioning	and provide results both in printed and in soft copy. This	
		shall apply to both copper and fibre.	
		A joint test and commissioning will be carried out by KRA	
		and the contractor.	

#### VII. MINIMUM TECHNICAL SPECIFICATIONS FOR KWALE

#### 1. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand,	
		in existence for at least 10 years (bidder	
		must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

## 2. Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e-coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 3. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand,	
		in existence for at least 10 years (bidder	
		must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed	
		on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both	
		angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs	
	-	Should also be backward compatible to cat	

	Feature	Minimum Requirements	Bidder's response
		5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

## 4. Minimum Technical Specifications for 1m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	1 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 5. Minimum Technical Specifications for 3m CAT 6A Ethernet Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length	3 M	
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 6. Minimum Technical Specifications for 22U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	22 U floor standing standard data cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window Rear door: high-flow mesh Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

## 7. Minimum Technical Specifications for 100mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre- punched fixing holes for permanent wall structures	
2.	Size	100mm by 50mm, two compartments	
3.	Length	2.4m	
4.	Gauge	1.2mm	

# 8. Minimum Technical Specifications for 100mm Single Gang Service Plates/ Knockouts

	Feature	Minimum Requirements Bidder's response
1.	Material	Metallic and same color as trunking
2.	Height	100mm
3⋅	Width	Single Gang
4.	Compatibility	Compatible with 100mm by 50mm trunking
5.	Gauge	1.2mm

# 9. Minimum Technical Specifications for 1.5KVA Rack-Mounted UPS

	Feature	Minimum Requirement	<b>Bidders Response</b>
	Brand and Model	Internationally recognized brand (bidder must specify brand and model)	
		Output	
1.	Output Power Capacity	900 Watts / 1500 VA	
2.	Max Configurable Power	900 Watts / 1500 VA	
3.	Nominal Output Voltage	230V	
4.	Output Voltage Distortion	Less than 5% at full load	
5.	Output Frequency (sync to mains)	47 - 53 Hz for 50 Hz nominal, 57 - 63 Hz for 60 Hz nominal	
6.	Topology	Line interactive	
7.	Waveform Type	Stepped approximation to a Sine wave	
8.	Output Connections	Four (4) IEC 320 C13 Two (2) IEC jumpers	
		Input	
9.	Nominal Input Voltage	230V	
10.	Input Frequency	50/60 Hz +/- 3 Hz (auto sensing)	
11.	Input Connections	IEC-320 C14	
12.	Battery Type	Maintenance free sealed lead-acid with suspended electrolyte, leak proof	
13.	Input voltage range for main operations	180 - 287V	
14.	Input voltage adjustable range for mains operation	170 - 300V	
15.	Typical recharge time	3 hour(s)	
16.	Typical Backup Time at Half Load	20.9 minutes (432.5 Watts)	
17.	Typical Backup Time at Full Load	7.6 minutes (865 Watts)	
		Communications & Management	
18.	Interface Ports	RJ-45 Serial, USB	
19.	Control panel	Multi-function LCD status and control console	
20.	Audible Alarm	Alarm when on battery : distinctive low battery alarm : configurable delays	

	Feature	Minimum Requirement	<b>Bidders Response</b>		
	Surge Protection and Filtering				
21.	Surge energy rating	459Joules			
22.	Filtering	Full time multi-pole noise filtering : 0.3% IEEE surge let-through : zero clamping response time : meets UL 1449			
23.	Data Line filtering	RJ-45 modem/Fax/DSL/10-100 Base-T protection			
24.	Standard Warranty	2 years repair or replace			
25.	Accessories	Power cords (at least 1.83M), CD with software, Documentation CD, Rack Mounting brackets, Smart UPS signaling RS-232 cable, USB cable, User Manual			

#### 10.TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### The Scope of Works

The successful bidder shall be required to carry out the following works; Installation of a new LAN for KRA Kwale station. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc. The fiber works entail the installation of indoor or outdoor fiber cables to interconnect floors within the same building or offices within the same campus. Fiber installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before the commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per the LAN design and the engineer's instructions. All cables must run through the trunkings.	
2.	Horizontal cabling	The horizontal cabling should be done neatly and professionally as per the LAN design and the engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre. Installation of fibre should be carried out according to the instructions of the network engineer on site. At least 6 cores must be terminated for each side of a cable (i.e. 12 terminations).	
4.	Tools & accessories	The contractor must have all the tools and accessories required to install and test Local area Networks (LANs).	
5.	Quality of works	The contractor is required to provide high standard installation service and quality workmanship. Cable management must also be neatly done.  The trunking joints must flush and with no gapes. Knockouts must be installed neatly with no gapes or spaces. The knockouts <b>MUST</b> be of the same shade as that of the trunkings.	

6.	Old cable /trunking uninstallation	The contractor will be required to carefully uninstall old cabling and/or trunking in areas where the LAN is undergoing an overhaul. This should be done neatly to avoid tampering with the wall painting and cable/trunking to be reused.	
7-	Equipment migration	The contractor will be required to carefully uninstall equipment from the old cabinet and migrate them to the newly installed cabinet. This should be done carefully to avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The contractor will be required to return to site and rectify any defects that may occur within the defect liability period at no extra cost to the Authority.	
9.	Drawings and documentation	On completion of the works the contractor <u>MUST</u> provide all the relevant documentation and the LAN schematic diagram for each site.	
10.	Labeling	All the data points and ports on the Patch panels must be well labeled with Printed labels. The patch cords must also be labeled on both ends to match port numbers.	
11.	Testing and Commissioning	The Contractor is required to carry out professional tests and provide results both in printed and in soft copy. This shall apply to both copper and fibre.  A joint test and commissioning will be carried out by KRA and the contractor.	

Bidder's Signature Date	e Stamp
-------------------------	---------

# E. LOT V TECHNICAL SPECIFICATIONS

#### I. MINIMUM TECHNICAL SPECIFICATIONS FOR JKIA FORODHA HOUSE

#### 1. Minimum Technical Specifications for 12 Core Single Mode Armored Fiber Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years(bidder must specify brand)	
2.	Jacket characteristics	Water Blocking Aramid Yarn	
	& Material	Armored	
		PVC	
3.	Mode of operation	Single mode	
4.	Core density	12 cores	
5.	Attenuation (Max)	3.50 dB/km @ 850nm	
6.	Standards	Optical and mechanical performance:	
		IEC 60794-2, IEC 60794-2-20, ISO	
		11801, EN 50173-1	

#### 2. Minimum Technical Specifications for 12 Port Single-Mode Modular Fiber ODF

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand	
2.	Mode of operation	Single-Mode	
3.	Port density	• 12 ports (24 cores)	
		Fully populated	
4.	Form Factor	1HU	
5.	Adapter	LC	
6.	Accessories	• 24 Pigtail connectors	
		• 24 core Splice tray	
		• 30 Heat shrink sleeves	

#### 3. Minimum Technical Specifications for 1G Single-Mode SFP Transceiver Modules

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand (bidder must specify brand )	
2.	Mode of operation	Single-Mode	
3.	Compatibility	Must be compatible with Cisco switches	
4.	Form Factor	Small pluggable form factor	
5.	Capacity	1 Gigabyte (1G)	

## 4. Minimum Technical Specifications for 1.5M LC-LC Single-Mode Fiber Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10	
		years.	
2.	Mode	Single mode OS1/OS2	
3.	Connector	Must be <b>LC-LC</b>	
4.	Length	1.5m	

# 5. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10 years	
		(bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

## 6. Minimum Technical Specifications for CAT 6A 48-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	48 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

# 7. Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

## 8. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and	
		model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs Should also be backward compatible to cat 5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

## 9. Minimum Technical Specifications for 1M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length		
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 10. Minimum Technical Specifications for 3M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length		
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

## 11. Minimum Technical Specifications for 22U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	

	Feature	Minimum Requirements	Bidder's response
		brand	
2.	Form Factor	22 U floor standing standard data	
		cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window	
		Rear door: high-flow mesh	
		Both doors keyed locks for security	
		1.2mm solid sides	
		Installed axial fan kits	
5.	Power outlets in the	6-Way universal PDU 3A/220 - 240 V	
	cabinet	AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic	
		horizontal Dual-sided cable managers	

## 12. Minimum Technical Specifications for 32U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	32 U floor standing standard data cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window Rear door: high-flow mesh Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

## 13. Minimum Technical Specifications for 100mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	100mm by 50mm, two compartments	
3.	Length	2.4 M	
4.	Gauge	1.2mm	

## 14. Minimum Technical Specifications for 150mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	150mm by 50mm, two compartments	
3.	Length	2.4 M	
4.	Gauge	1.2mm	

## 15. Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for	

		permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4 M	
4.	Gauge	1.2mm	

## 16. Minimum Technical Specifications for 100mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	100mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 100mm by 50mm trunking	
5.	Gauge	1.2mm	

## 17. Minimum Technical Specifications for 150mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	150mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 150mm by 50mm trunking	
5.	Gauge	1.2mm	

## 18. Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	
5.	Gauge	1.2mm	

# 19. Minimum Technical Specifications for 1.5KVA Rack-Mounted UPS

	Feature	Minimum Requirement	Bidders Response				
		Internationally recognized brand (bidder must specify brand and model)					
	Output						
1.	Output Power Capacity	900 Watts / 1500 VA					
2.	Max Configurable Power	900 Watts / 1500 VA					
3.	Nominal Output Voltage	230V					
4.	Output Voltage Distortion	Less than 5% at full load					
5.		47 - 53 Hz for 50 Hz nominal, 57 - 63 Hz for 60 Hz nominal					
6.	Topology	Line interactive					

	Feature	Minimum Requirement	Bidders Response
7.	Waveform Type	Stepped approximation to a Sine wave	
8.	Output Connections	Four (4) IEC 320 C13 Two (2) IEC jumpers	
		Input	
9.	Nominal Input Voltage	230V	
10.	Input Frequency	50/60 Hz +/- 3 Hz (auto sensing)	
11.	Input Connections	IEC-320 C14	
12.	Battery Type	Maintenance free sealed lead-acid with suspended electrolyte, leak proof	
13.	Input voltage range for main operations	180 - 287V	
14.	Input voltage adjustable range for mains operation	170 - 300V	
15.	Typical recharge time	3 hour(s)	
16.	Typical Backup Time at Half Load	20.9 minutes (432.5 Watts)	
17.	Typical Backup Time at Full Load	7.6 minutes (865 Watts)	
		Communications & Manage	ement
18.	Interface Ports	RJ-45 Serial, USB	
19.	Control panel	Multi-function LCD status and control console	
20.	Audible Alarm	Alarm when on battery : distinctive low battery alarm : configurable delays	
	-	Surge Protection and Filte	ering
21.	Surge energy rating	459Joules	
22.	Filtering	Full time multi-pole noise filtering : 0.3% IEEE surge let-through : zero clamping response time : meets UL 1449	
23.	Data Line filtering	RJ-45 modem/Fax/DSL/10-100 Base-T protection	
24.	Standard Warranty	2 years repair or replace	
25.	Accessories	Power cords (at least 1.83M), CD with software, Documentation CD, Rack Mounting brackets, Smart UPS signalling RS-232 cable, USB cable, User Manual	

#### 20. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

#### **The Scope of Works**

The successful bidder shall be required to carry out the following works; Installation of new LAN for KRA JKIA Forodha House. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labelling etc. The fibre works entail the installation of indoor or outdoor fibre cables to interconnect floors within the same building or offices within the same campus. Fibre installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labelling, Drawings and Documentation

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as per the	
		LAN design and the engineer's instructions.	
		All cables must run through the trunkings.	
2.	Horizontal	The horizontal cabling should be done neatly and	
2.	cabling	professionally as per the LAN design and the engineer's	
	- custing	instructions on site.	
3.	Vertical	The backbone is typically done using fibre. Installation of	
	cabling	fibre should be carried out according to the instructions of	
		the network engineer on site. At least 6 cores must be	
		terminated for each side of a cable (i.e. 12 terminations).	
4.	Tools &	The contractor must have all the tools and accessories	
	accessories	required to install and test Local area Networks (LANs).	
5.	Quality of	The contractor is required to provide high standard	
	works	installation service and quality workmanship. Cable	
		management must also be neatly done.	
		The trunking joints must flush and with no gapes.	
		Knockouts must be installed neatly with no gapes or	
		spaces. The knockouts <b>MUST</b> be of the same shade as that of the	
		trunkings.	
6.	Old	The contractor will be required to carefully uninstall old	
	cable/trunkin	cabling and/or trunking in areas where the LAN is	
	g	undergoing an overhaul. This should be done neatly to	
	uninstallatio	avoid tampering with the wall painting and cable/trunking	
	n	to be reused.	
7.	Equipment	The contractor will be required to carefully uninstall	
	migration	equipment from the old cabinet and migrate them to the newly installed cabinet. This should be done carefully to	
		avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year. The	
		contractor will be required to return to site and rectify any	
		defects that may occur within the defect liability period at	
		no extra cost to the Authority.	
9.	Drawings	On completion of the works the contractor <b>MUST</b> provide	
	and	all the relevant documentation and the LAN schematic	
	documentati	diagram for each site.	
10.	on Labelling	All the data points and ports on the Patch panels must be	
10.		well labelled with Printed labels. The patch cords must	
		also be labelled on both ends to match port numbers.	
11.	Testing and	The Contractor is required to carry out professional tests	
	Commissioni	and provide results both in printed and in soft copy. This	
	ng	shall apply to both copper and fibre.	
		A joint test and commissioning will be carried out by KRA	
		and the contractor.	

# II. MINIMUM TECHNICAL SPECIFICATIONS FOR 5TH FLOOR TIMES TOWER

# 1. Minimum Technical Specifications for 12 Core Multimode Armored Fiber Cable

	Feature	<b>Minimum Requirements</b>	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10	
		years(bidder must specify brand)	
2.	Jacket characteristics	Water Blocking Aramid Yarn	
	& Material	Armored	
		PVC	
3.	Mode of operation	Multimode	
4.	Core density	12 cores	
5.	Attenuation (Max)	3.50 dB/km @ 850nm	
6.	Standards	Optical and mechanical performance:	
		IEC 60794-2, IEC 60794-2-20, ISO	
		11801, EN 50173-1	

# 2. Minimum Technical Specifications for 12 Port Multimode Modular Fiber ODF

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
2.	Mode of operation	brand Multimode	
3.	Port density	• 12 ports (24 cores) • Fully populated	
4.	Form Factor	1HU	
5.	Adapter	SC	
6.	Accessories	<ul><li>24 Pigtail connectors</li><li>24 core Splice tray</li><li>30 Heat shrink sleeves</li></ul>	

# 3. Minimum Technical Specifications for 1G Multimode SFP Transceiver Modules

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand (bidder must specify brand )	
2.	Mode of operation	Multimode	
3.	Compatibility	Must be compatible with Cisco switches	
4.	Form Factor	Small pluggable form factor	
5.	Capacity	1 Gigabyte (1G)	

# 4. Minimum Technical Specifications for 1M SC-LC Multimode Fiber Patch Cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10	
		years.	
2.	Mode	Multimode <b>OM3 50/125</b>	
3.	Connector	Must be <b>SC-LC</b>	
4.	Length	1m	

# 5. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10 years	
		(bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

# 6. Minimum Technical Specifications for CAT 6A 48-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	48 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

# 7. Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

# 8. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs Should also be backward compatible to cat 5e	
10.	Shield	Hinged cable retention/ grounding clip	
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

# 9. Minimum Technical Specifications for 1M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length		
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

# 10. Minimum Technical Specifications for 3M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length		
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

# 11. Minimum Technical Specifications for 22U Free Standing Data Cabinet

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand	
2.	Form Factor	22 U floor standing standard data	

	Feature	Minimum Requirements	Bidder's response
		cabinet	
3.	Dimension	600x800mm	
4.	Construction	Front door: with glass window Rear door: high-flow mesh Both doors keyed locks for security 1.2mm solid sides Installed axial fan kits	
5.	Power outlets in the cabinet	6-Way universal PDU 3A/220 - 240 V AC earthed and fused with shutters	
6.	Cable manager	Five (5) pieces of 1U black metallic horizontal Dual-sided cable managers	

# 12. Minimum Technical Specifications for 50mmx25mm Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	50mm by 25mm	
3.	Length	2.4m	
4.	Gauge	1.2mm	

# 13. Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4 M	
4.	Gauge	1.2mm	

# ${\bf 14.\ Minimum\ Technical\ Specifications\ for\ 75mmx50mm\ Curved\ Floor\ Partitioned\ Trunking}$

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	75mm by 50mm, two compartments	
3.	Form	Curved	
4.	Length	2.4 M	
5.	Gauge	1.2mm	

# 15. Minimum Technical Specifications for 150mm Pedestal Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	<ul> <li>Powder coated metal trunking with pre-punched fixing holes for permanent floor structures.</li> <li>Rounded corners.</li> </ul>	
2.	Size	150mm	
3.	Outlets	<ul><li>4 single gang data outlet</li><li>4 dual gang power outlet</li></ul>	

4.	Height	400mm	
5.	Gauge	1.2mm	

## 16. Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	
5.	Gauge	1.2mm	

#### 17. Minimum Technical Specifications for Single Gang Blank Faceplates

	Feature	Minimum Requirements	Bidder's Response
1.	Size	Single gang	
2.	Colour	White	
3.	Material	High impact plastic (ABS UL 94V-0 compliant)	
4.	Assembly	Blank single gang complete with screws	

#### 18. Minimum Technical Specifications for Double Gang Blank Faceplates

	Feature	<b>Minimum Requirements</b>	Bidder's Response
1.	Size	Double gang	
2.	Colour	White	
3.	Material	High impact plastic (ABS UL 94V-0 compliant)	
4.	Assembly	Blank double gang complete with screws	

#### 19. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

## **The Scope of Works**

The successful bidder shall be required to carry out the following works; Installation of new LAN for KRA Times Tower 5<sup>th</sup> Floor Convention Center. The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labelling etc. The fibre works entail the installation of indoor or outdoor fibre cables to interconnect floors within the same building or offices within the same campus. Fibre installation may use existing conduits or new ones may be installed where required.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# ${\bf Minimum\,Technical\,Specifications\,for\,LAN\,Installation, Testing,\,Commissioning,\,Labeling,\,Drawings\,and\,Documentation}$

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as	
	_	per the LAN design and the engineer's	
		instructions.	
		All cables must run through the trunkings.	
2.	Horizontal	The horizontal cabling should be done neatly and	
	cabling	professionally as per the LAN design and the	
	77	engineer's instructions on site.	
3.	Vertical cabling	The backbone is typically done using fibre. Installation of fibre should be carried out	
	Cabillig	according to the instructions of the network	
		engineer on site. At least 6 cores must be	
		terminated for each side of a cable (i.e. 12	
		terminations).	
4.	Tools &	The contractor must have all the tools and	
·	accessories	accessories required to install and test Local area	
		Networks (LANs).	
5.	Quality of	The contractor is required to provide high	
	works	standard installation service and quality	
		workmanship. Cable management must also be	
		neatly done.	
		The trunking joints must flush and with no gapes.	
		Knockouts must be installed neatly with no gapes	
		or spaces. The knockouts <b>MUST</b> be of the same shade as	
		that of the trunkings.	
6.	Old	The contractor will be required to carefully	
	cable/trunkin	uninstall old cabling and/or trunking in areas	
	g	where the LAN is undergoing an overhaul. This	
	uninstallatio	should be done neatly to avoid tampering with the	
	n	wall painting and cable/trunking to be reused.	
7.	Equipment	The contractor will be required to carefully	
	migration	uninstall equipment from the old cabinet and	
		migrate them to the newly installed cabinet. This	
		should be done carefully to avoid damaging the	
8.	Warranty	equipment.  The defect liability period shall be one (1) year.	
0.	vvarranty	The contractor will be required to return to site	
		and rectify any defects that may occur within the	
		defect liability period at no extra cost to the	
		Authority.	
9.	Drawings	On completion of the works the contractor <b>MUST</b>	
	and	provide all the relevant documentation and the	
	documentati	LAN schematic diagram for each site.	
	on		
10.	Labeling	All the data points and ports on the Patch panels	
		must be well labeled with Printed labels. The	
		patch cords must also be labeled on both ends to	
11.	Testing and	match port numbers.  The Contractor is required to carry out	
11,	Commissioni	professional tests and provide results both in	
	ng	printed and in soft copy. This shall apply to both	
	0	copper and fibre.	
		A joint test and commissioning will be carried out	
		by KRA and the contractor.	

# III. MINIMUM TECHNICAL SPECIFICATIONS FOR NAMANGA

# 1. Minimum Technical Specifications for CAT 6A UTP Ethernet Cable

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured	
		brand, in existence for at least 10 years	
		(bidder must specify brand)	
2.	Category	CAT 6A UTP	
3.	Size	4-Pair solid, Gauge: 23 AWG	
4.	Operating frequency	500 to 550 MHZ	
5.	Standards	TIA/EIA 568 A/B, ISO/IEC 11801	
6.	Length	305m	

## 2. Minimum Technical Specifications for CAT 6A 24-Port Ethernet Patch Panel

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized brand	
2.	Port Density	24 port (Fully populated)	
3.	Application	Quick snap	
4.	Cable Management	Rear Cable management bar installed	
5.	Labels	Printable labels MUST be available	
6.	Wiring	T568A/T568B compliant and easy to read	
7.	Contact materials	Plated phosphor bronze, stainless steel	
8.	Mounting	CEA-310-E 19-inch (482.6 mm) rack	
9.	Current rating	1.5 A	
10.	Contact resistance	20 mΩ	
11.	Insulation resistance	500 ΜΩ	
12.	Panel material	18 gauge cold rolled steel, black e- coated	
13.	Category and compatibility	CAT6A and downward compatible with CAT5e/CAT5	
14.	Termination	By Z-tool	

# 3. Minimum Technical Specifications for CAT 6A Dual Data Outlets

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years (bidder must specify brand and model)	
2.	Assembly	CAT 6A dual RJ45 outlet module installed on a single gang face plate	
3.	Built	Jack to jack plastic insulation	
4.	Application	A single hybrid outlet that supports both angled and flat mounting orientations	
5.	Contact resistance	20 mΩ	
6.	Insulation Resistance	500 ΜΩ	
7.	Current rating	1.5 A PoE , PoE+	
8.	Contact Materials	Plated phospher bronze, stainless steel	
9.	Plug compatibility	Compatible with RJ45 (8-position) plugs Should also be backward compatible to cat 5e	
10.	Shield	Hinged cable retention/ grounding clip	

	Feature	Minimum Requirements	Bidder's response
11.	Grounding	Single step termination	
12.	Front protection	Spring door	
13.	Termination	By Z-tool	

# 4. Minimum Technical Specifications for 1M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length		
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

# 5. Minimum Technical Specifications for 3M CAT 6A Ethernet Patch cords

	Feature	Minimum Requirements	Bidder's response
1.	Brand	Internationally recognized, matured brand, in existence for at least 10 years, must be of the same specifications with the Ethernet cable (bidder must specify brand)	
2.	Category	CAT 6A 4-pair Ethernet cable	
3.	Length		
4.	Boot Color	With colour matching jacket/ boot to labelling on the faceplates	

# 6. Minimum Technical Specifications for 200mmx50mm Partitioned Trunking

	Feature	Minimum Requirements	Bidder's response
1.	Material	Powder coated metal trunking with pre-punched fixing holes for permanent wall structures	
2.	Size	200mm by 50mm, two compartments	
3.	Length	2.4 M	
4.	Gauge	1.2mm	

# 7. Minimum Technical Specifications for 200mm Single Gang Service Plates/Knockouts

	Feature	Minimum Requirements	Bidder's response
1.	Material	Metallic and same color as trunking	
2.	Height	200mm	
3.	Width	Single Gang	
4.	Compatibility	Compatible with 200mm by 50mm trunking	
5.	Gauge	1.2mm	

#### 8. TECHNICAL SPECIFICATIONS FOR THE LAN INSTALLATION SERVICES

## **The Scope of Works**

The successful bidder shall be required to carry out the following works; Installation of new LAN for KRA Namanga Station (Lower Ground Floor). The structured cabling activities include, but not limited to, the installation of metal trunkings, pulling and termination of UTP cables, cable management, labeling etc.

Once the procurement process has been completed, the successful bidder will be awarded the contract. The successful bidder will be required to deliver all the LAN materials on site before commencement of the LAN installation. A technical inspection will be carried out on the LAN materials to ascertain that they meet the pre-order specifications. This will be followed by a pre-installation survey between KRA and the successful bidder and thereafter a work plan will be developed. The successful bidder will be required to install the LAN professionally in accordance with the provided designs and/or as per the instructions of the KRA Network Engineer on site within the stipulated timelines in the work plan.

# Minimum Technical Specifications for LAN Installation, Testing, Commissioning, Labeling, Drawings and Documentation.

No	Feature	Minimum Requirements	Bidder's Response
1.	Trunking	The metal trunkings must be installed neatly as	
		per the LAN design and the engineer's	
		instructions.	
		All cables must run through the trunkings.	
2.	Horizontal	The horizontal cabling should be done neatly	
	cabling	and professionally as per the LAN design and	
		the engineer's instructions on site.	
3.	Vertical	The backbone is typically done using fibre.	
	cabling	Installation of fibre should be carried out	
		according to the instructions of the network	
		engineer on site. At least 6 cores must be	
		terminated for each side of a cable (i.e. 12	
		terminations).	
4.	Tools &	The contractor must have all the tools and	
	accessories	accessories required to install and test Local	
		area Networks (LANs).	
5.	Quality of	The contractor is required to provide high	
	works	standard installation service and quality	
		workmanship. Cable management must also	
		be neatly done.	
		The trunking joints must flush and with no	
		gapes. Knockouts must be installed neatly with	
		no gapes or spaces.	
		The knockouts <b>MUST</b> be of the same shade as	
	01.1	that of the trunkings.	
6.	Old	The contractor will be required to carefully	
	cable/trunking	uninstall old cabling and/or trunking in areas	
	uninstallation	where the LAN is undergoing an overhaul. This	
		should be done neatly to avoid tampering with	
		the wall painting and cable/trunking to be	
<u> </u>	E marine and	reused.	
7.	Equipment migration	The contractor will be required to carefully	
	ingration	uninstall equipment from the old cabinet and	
		migrate them to the newly installed cabinet.	
		This should be done carefully to avoid damaging the equipment.	
8.	Warranty	The defect liability period shall be one (1) year.	
0.	vvarranty	The contractor will be required to return to site	
		and rectify any defects that may occur within	
		the defect liability period at no extra cost to the	
		Authority.	
9.	Drawings	On completion of the works the contractor	
9.	and	MUST provide all the relevant documentation	
	anu	MICOI provide an the relevant documentation	

	documentati	and the LAN schematic diagram for each site.	
	on		
10.	Labeling	All the data points and ports on the Patch	
	_	panels must be well labeled with Printed labels.	
		The patch cords must also be labeled on both	
		ends to match port numbers.	
11.	Testing and	The Contractor is required to carry out	
	Commissioni	professional tests and provide results both in	
	ng	printed and in soft copy. This shall apply to	
		both copper and fibre.	
		A joint test and commissioning will be carried	
		out by KRA and the contractor.	

Bidder's Signature	Date	Stamp
214441		~

# 1. List of Goods and Delivery Schedule

[The Procuring Entity shall fill in this table, with the exception of the column "Tenderer's offered Delivery date" to be filled by the tenderer]

Line	<b>Description of Goods</b>	ription of Goods Quantity I	Physical Final	Delivery (as per Incoterms) Date			
Item N°			unit	Destination as specified in TDS	Earliest Delivery Date	Latest Delivery Date	Tenderer's offered Delivery date [to be provided by the tenderer]
[insert item No]	[insert description of Goods]	[insert quantity of item to be supplied]	[insert physical unit for the quantity]	[insert place of Delivery]	[insert the number of days following the date of effectiveness the Contract]	[insert the number of days following the date of effectiveness the Contract]	[insert the number of days following the date of effectiveness the Contract]

# 2. List of Related Services and Completion Schedule

[This table shall be filled in by the KENYA REVENUE AUTHORITY. The Required Completion Dates should be realistic, and consistent with the required Goods Delivery Dates (as per Incoterms)].

Service	Description of Service	Quantity <sup>1</sup>	Physical Unit	Place where Services shall be performed	Final Completion Date(s) of Services
[insert Service No]	[insert description of Related Services]	[insert quantity of items to be supplied]	[insert physical unit for the items]	[insert name of the Place]	[insert required Completion Date(s)]

<sup>&</sup>lt;sup>1</sup>If applicable

## 3. Technical Specifications

- 3.1 The purpose of the Technical Specifications (TS), is to define the technical characteristics of the Goods and Related Services required by the Procuring Entity. The Procuring Entity shall prepare the detailed TS consider that:
  - i) The TS constitute the benchmarks against which the Procuring Entity will verify the technical responsiveness of Tenders and subsequently evaluate the Tenders. Therefore, well-defined TS will facilitate preparation of responsive Tenders by tenderers, as well as examination, evaluation, and comparison of the Tenders by the Procuring Entity.
  - ii) The TS shall require that all goods and materials to be incorporated in the goods be new, unused, and of the most recent or current models, and that they incorporate all recent improvements in design and materials, unless provided for otherwise in the contract.
  - iii) The TS shall make use of best practices. Samples of specifications from successful similar procurements in the same country or sector may provide a sound basis for drafting the TS.
  - iv) The PPRA encourages the use of metric units.
  - v) Standardizing technical specifications may be advantageous, depending on the complexity of the goods and the repetitiveness of the type of procurement. Technical Specifications should be broad enough to avoid restrictions on workmanship, materials, and equipment commonly used in manufacturing similar kinds of goods.
  - vi) Standards for equipment, materials, and workmanship specified in the Tendering document shall not be restrictive. Recognized international standards should be specified as much as possible. Reference to brand names, catalogue numbers, or other details that limit any materials or items to a specific manufacturer should be avoided as far as possible. Where unavoidable, such item description should always be followed by the words "or substantially equivalent." When other particular standards or codes of practice are referred to in the TS, whether from the Procuring Entity's or from other eligible countries, a statement should follow other authoritative standards that ensure at least a substantially equal quality, then the standards mentioned in the TS will also be acceptable.
  - vii) Reference to brand names and catalogue numbers should be avoided as far as possible; where unavoidable the words "or at least equivalent" shall always follow such references.
  - viii) Technical Specifications shall be fully descriptive of the requirements in respect of, but not limited to, the following:
    - a) Standards of materials and workmanship required for the production and manufacturing of the Goods.
    - b) Any sustainable procurement technical requirements shall be clearly specified.
- 3.2 To encourage tenderers' innovation in addressing sustainable procurement requirements, as long as the Tender evaluation criteria specify the mechanism for monetary adjustments for the purpose of Tender comparisons, tenderers may be invited to offer Goods that exceeds the specified minimum sustainable procurement requirements.
  - i) Detailed tests required (type and number).
  - ii) Other additional work and/or Related Services required to achieve full delivery/completion.
  - iii) Detailed activities to be performed by the Supplier, and participation of the Procuring Entity thereon.
  - iv) List of detailed functional guarantees covered by the Warranty and the specification of the liquidated damages to be applied in the event that such guarantees are not met.
- 3.3 The TS shall specify all essential technical and performance characteristics and requirements, including guaranteed or acceptable maximum or minimum values, as appropriate. Whenever necessary, the Procuring Entity shall include an additional ad-hoc Tendering form (to be an Attachment to the

Letter of Tender), where the tenderer shall provide detailed information on such technical performance characteristics in respect to the corresponding acceptable or guaranteed values.

- 3.4 When the Procuring Entity requests that the tenderer provides in its Tender a part or all of the Technical Specifications, technical schedules, or other technical information, the Procuring Entity shall specify in detail the nature and extent of the required information and the manner in which it has to be presented by the tenderer in its Tender.
- 3.5 If a summary of the Technical Specifications(TS) has to be provided, the Procuring Entity shall insert information in the table below. The tenderer shall prepare a similar table to justify compliance with the requirements.

**Summary of Technical Specifications:** The Goods and Related Services shall comply with following Technical Specifications and Standards:

Item No	Name of Goods or Related Service	Technical Specifications and Standards
[insert item No]	[insert name]	[insert TS and Standards]

**Detailed Technical Specifications and Standards** [insert whenever necessary]. [Insert detailed description of TS]

4	T)	•
4.	- Dra	wings
-10	Diu	W 11180

This Tendering document includes					[Insert	"the	following"	or	"no"]		
drawings.	[If documents	shall be	included,	insert 1	the following	List o	f Drawii	ngs].			

List of Drawings				
Drawing No.	Drawing Name	Purpose		

5. Inspections and Tes
------------------------

The following inspections and tests shall be performed:..... [Insert list of inspections and tests]

# PART 3 - CONDITIONS OF CONTRACT AND CONTRACT FORMS

## SECTION VI - GENERAL CONDITIONS OF CONTRACT

#### 1. Definitions

In the Conditions of Contract ("these Conditions"), which include Special Conditions, Parts A and B, and these General Conditions, the following words and expressions shall have the meanings stated. Words indicating persons or parties include corporations and other legal entities, except where the context requires otherwise.

- a) "Contract" means the Contract Agreement entered into between the Procuring Entity and the Supplier, together with the Contract Documents referred to therein, including all attachments, appendices, and all documents incorporated by reference therein.
- b) "Contract Documents" means the documents listed in the Contract Agreement, including any amendments thereto.
- c) "Contract Price" means the price payable to the Supplier as specified in the Contract Agreement, subject to such additions and adjustments thereto or deductions therefrom, as may be made pursuant to the Contract.
- d) "Day" means calendar day.
- e) "Completion" means the fulfilment of the Related Services by the Supplier in accordance with the terms and conditions set forth in the Contract.
- f) "GCC" means the General Conditions of Contract.
- g) "Goods" means all of the commodities, raw material, machinery and equipment, and/or other materials that the Supplier is required to supply to the Procuring Entity under the Contract.
- h) "Procuring Entity" means the Procuring Entity purchasing the Goods and Related Services, as specified in the SCC.
- i) "Related Services" means the services incidental to the supply of the goods, such as insurance, delivery, installation, commissioning, training and initial maintenance and other such obligations of the Supplier under the Contract.
- i) "SCC" means the Special Conditions of Contract.
- k) "Subcontractor" means any person, private or government entity, or a combination of the above, to whom any part of the Goods to be supplied or execution of any part of the Related Services is subcontracted by the Supplier.
- 1) "Supplier" means the person, private or government entity, or a combination of the above, whose Tender to perform the Contract has been accepted by the Procuring Entity and is named as such in the Contract Agreement.
- m) "Base Date" means a date 30 day prior to the submission of tenders.
- n) "Laws" means all national legislation, statutes, ordinances, and regulations and by-laws of any legally constituted public authority.
- o) "Letter of Acceptance" means the letter of formal acceptance, signed by the contractor. Procuring Entity, including any annexed memoranda comprising agreements between and signed by both Parties.
- p) "Procuring Entity" means the Entity named in the Special Conditions of Contract.

#### 2. Interpretation

2.1. If the context so requires it, singular means plural and vice versa.

#### 2.2. Incoterms

- a) Unless inconsistent with any provision of the Contract, the meaning of any trade term and the rights and obligations of parties thereunder shall be as prescribed by Incoterms **specified** in the SCC.
- b) The terms EXW and CIP and other similar terms, when used, shall be governed by the rules prescribed in the current edition of Incoterms specified in the SCC and published by the International Chamber of Commerce in Paris, France.

#### 3. Contract Documents

Subject to the order of precedence set forth in the Contract Agreement, all documents forming the Contract (and all parts thereof) are intended to be correlative, complementary, and mutually explanatory. The Contract Agreement shall be read as a whole. The documents forming the Contract shall be interpreted in the following order of priority:

- a) the Contract Agreement,
- b) the Letter of Acceptance,
- c) the General Conditions of Contract
- d) Special Conditions of Contract
- e) the Form of Tender,
- f) the Specifications and Schedules of the Drawings (if any), and
- g) the Schedules of Requirements, Price Schedule and any other documents forming part of the Contract.

## 4. Fraud and Corruption

- 3.1 The supplier shall comply with anti-corruption laws and guidelines and the prevailing sanctions, policies and procedures as set forth in the Laws of Kenya.
- 32 The Supplier shall disclose any commissions, gratuity or fees that may have been paid or are to be paid to agents or any other person with respect to the Tendering process or execution of the Contract. The information disclosed must include at least the name and address of the agent or other party, the amount and currency, and the purpose of the commission, gratuity or fee.

#### 4.1 Entire Agreement

4.3.1 The Contract constitutes the entire agreement between the Procuring Entity and the Supplier and supersedes all communications, negotiations and agreements (whether written or oral) of the parties with respect thereto made prior to the date of Contract.

#### 4.2 Amendment

No amendment or other variation of the Contract shall be valid unless it is in writing, is dated, expressly refers to the Contract, and is signed by a duly authorized representative of each party thereto.

#### 4.3 Non-waiver

- a) Subject to GCC Sub-Clause 4.5(b) below, no relaxation, forbearance, delay, or indulgence by either party in enforcing any of the terms and conditions of the Contract or the granting of time by either party to the other shall prejudice, affect, or restrict the rights of that party under the Contract, neither shall any waiver by either party of any breach of Contract operate as waiver of any subsequent or continuing breach of Contract.
- b) Any waiver of a party's rights, powers, or remedies under the Contract must be in writing, dated, and signed by an authorized representative of the party granting such waiver, and must specify the right and the extent to which it is being waived.

#### 4.4 Severability

If any provision or condition of the Contract is prohibited or rendered invalid or unenforceable, such prohibition, invalidity or unenforceability shall not affect the validity or enforceability of any other provisions and conditions of the Contract.

#### 5. Language

- 5.1 The Contract as well as all correspondence and documents relating to the Contract exchanged by the Supplier and the Procuring Entity, shall be written in the **English Language**. Supporting documents and printed literature that are part of the Contract may be in another language provided they are accompanied by an accurate and certified translation of the relevant passages in the **English Language**, in which case, for purposes of interpretation of the Contract, the English language is translation shall govern.
- 5.2 The Supplier shall bear all costs of translation to the governing language and all risks of the accuracy of such translation, for documents provided by the Supplier.

#### 6. Joint Venture, Consortium or Association

6.1 If the Supplier is a joint venture, consortium, or association, all of the parties shall be jointly and severally liable to the Procuring Entity for the fulfilment of the provisions of the Contract and shall designate one member of the joint venture, consortium, or association to act as a leader with authority to bind the joint venture, consortium, or association. The composition or the constitution of the joint venture, consortium, or association shall not be altered without the prior written consent of the Procuring Entity.

## 7. Eligibility

- 7.1 The Supplier and its Subcontractors shall have the nationality of an eligible country. A Supplier or Sub- contractor shall be deemed to have the nationality of a country if it is a citizen or constituted, incorporated, or registered, and operates in conformity with the provisions of the laws of that country.
- All Goods and Related Services to be supplied under the Contract shall have their origin in Eligible Countries. For the purpose of this Clause, origin means the country where the goods have been grown, mined, cultivated, produced, manufactured, or processed; or through manufacture, processing, or assembly, another commercially recognized article results that differs substantially in its basic characteristics from its components.
- 73 The Tenderer, if a Kenyan firm, must submit with its tender a valid tax compliance certificate from the Kenya Revenue Authority.

#### 8. Notices

- Any notice given by one party to the other pursuant to the Contract shall be in writing to the address specified in the **SCC**. The term "in writing" means communicated in written form with proof of receipt.
- 82 A notice shall be effective when delivered or on the notice's effective date, whichever is later.

## 9. Governing Law

- 9.1 The Contract shall be governed by and interpreted in accordance with the laws of Kenya.
- Throughout the execution of the Contract, the Supplier shall comply with the import of goods and services prohibitions in Kenya:
  - a) where, as a matter of law, compliance or official regulations, Kenya prohibits commercial relations with that country or any import of goods from that country or any payments to any country, person, or entity in that country; or
  - b) by an act of compliance with a decision of the United Nations Security Council taken under Chapter VII of the Charter of the United Nations, Kenya prohibits any import of goods from that country or any payments to any country, person, or entity.

#### 10. Settlement of Disputes

10.1 The Procuring Entity and the Supplier shall make every effort to resolve amicably by direct negotiation any disagreement or dispute arising between them under or in connection with the Contract.

10.2 If, after thirty (30) days, the parties have failed to resolve their dispute or difference by such mutual consultation, then either the Procuring Entity or the Supplier may give notice to the other party of its intention to commence arbitration, as hereinafter provided, as to the matter in dispute, and no arbitration in respect of this matter may be commenced unless such notice is given. Any dispute or difference in respect of which a notice of intention to commence arbitration has been given in accordance with this Clause shall be finally settled by arbitration. Arbitration may be commenced prior to or after delivery of the Goods under the Contract.

#### 102 Arbitration proceedings shall be conducted as follows:

- 1021 Any claim or dispute between the Parties arising out of or in connection with the Contract not settled amicably in accordance with Sub-Clause 10.1 shall be finally settled by arbitration.
- 1022 No arbitration proceedings shall be commenced on any claim or dispute where notice of a claim or dispute has not been given by the applying party within thirty days of the occurrence or discovery of the matter or issue giving rise to the dispute.
- 1023 Notwithstanding the issue of a notice as stated above, the arbitration of such a claim or dispute shall not commence unless an attempt has in the first instance been made by the parties to settle such claim or dispute amicably with or without the assistance of third parties. Proof of such attempt shall be required.
- 1024 The Arbitrator shall, without prejudice to the generality of his powers, have powers to direct such measurements, computations, or valuations as may in his opinion be desirable in order to determine the rights of the parties and assess and award any sums which ought to have been the subject of or included in any due payments.
- 1025 Neither Party shall be limited in the proceedings before the arbitrators to the evidence, or to the reasons for the dispute given in its notice of a claim or dispute.
- 1026 Arbitration may be commenced prior to or after delivery of the goods. The obligations of the Parties shall not be altered by reason of any arbitration being conducted during the progress of the delivery of goods.
- 1027 The terms of the remuneration of each or all the members of Arbitration shall be mutually agreed upon by the Parties when agreeing the terms of appointment. Each Party shall be responsible for paying one-half of this remuneration.

#### 103 Arbitration Proceedings

- 103.1 Arbitration proceedings with national suppliers will be conducted in accordance with the Arbitration Laws of Kenya. In case of any claim or dispute, such claim or dispute shall be notified in writing by either party to the other with a request to submit it to arbitration and to concur in the appointment of an Arbitrator within thirty days of the notice. The dispute shall be referred to the arbitration and final decision of a person or persons to be agreed between the parties. Failing agreement to concur in the appointment of an Arbitrator, the Arbitrator shall be appointed, on the request of the applying party, by the Chairman or Vice Chairman of any of the following professional institutions;
  - i) Kenya National Chamber of Commerce
  - ii) Chartered Institute of Arbitrators (Kenya Branch)
  - iii) The Law Society of Kenya
- 1032 The institution written to first by the aggrieved party shall take precedence over all other institutions.

#### 1033 Alternative Arbitration Proceedings

Alternatively, the Parties may refer the matter to the Nairobi Centre for International Arbitration (NCIA) which offers a neutral venue for the conduct of national and international arbitration with commitment to providing institutional support to the arbitral process.

**10.4 Arbitration with Foreign Suppliers :** Arbitration with foreign suppliers shall be conducted in accordance with the arbitration rules of the United Nations Commission on International Trade Law (UNCITRAL); or with proceedings administered by the International Chamber of Commerce (ICC) and conducted under the ICC Rules of Arbitration; by one or more arbitrators appointed in accordance with said arbitration rules.

1041 The place of arbitration shall be a location specified in the SCC; and the arbitration shall be conducted in the language for communications defined in Sub-Clause 1.4 [Law and Language].

#### 105 Alternative Arbitration Proceedings

Alternatively, the Parties may refer the matter to the Nairobi Centre for International Arbitration (NCIA) which offers a neutral venue for the conduct of national and international arbitration with commitment to providing institutional support to the arbitral process.

#### 10.6 Failure to Comply with Arbitrator's Decision

- 1061 The award of such Arbitrator shall be final and binding upon the parties.
- 10.6.1 In the event that a Party fails to comply with a final and binding Arbitrator's decision, then the other Party may, without prejudice to any other rights it may have, refer the matter to a competent court of law.

#### 10.7 Contract operations continue

Notwithstanding any reference to arbitration herein,

- a) the parties shall continue to perform their respective obligations under the Contract unless they otherwise agree; and
- b) the Procuring Entity shall pay the Supplier any monies due the Supplier.

## 11. Inspections and Audit by the KENYA REVENUE AUTHORITY

- 11.1 The Supplier shall keep, and shall cause its Subcontractors to keep, accurate and systematic accounts and records in respect of the Goods in such form and details as will clearly identify relevant time, changes and costs.
- Pursuant to paragraph 2.2 of Instruction to Tenderers, the Supplier shall permit and shall cause its subcontractors to permit, the Procuring Entity and/or persons appointed by the Procuring Entity or by other statutory bodies of the Government to inspect the Site and/or the accounts and records relating to the procurement process, selection and/or contract execution, and to have such accounts and records audited by auditors appointed by the Procuring Entity. The Supplier's and its Subcontractors' attention is drawn to Sub- Clause 3.1 which provides, inter alia, that acts intended to materially impede the exercise of the Procuring Entity's inspection and audit rights constitute a prohibited practice subject to contract termination, as well as to a determination of ineligibility.

## 12. Scope of Supply

12.1 The Goods and Related Services to be supplied shall be as specified in the Schedule of Requirements.

#### 13. Delivery and Documents

13.1 Subject to GCC Sub-Clause 33.1, the delivery of the Goods and completion of the Related Services shall be in accordance with the List of Goods and Delivery Schedule specified in the Supply Requirements. The details of shipping and other documents to be furnished by the Supplier are specified in the SCC.

#### 14. Supplier's Responsibilities

14.1 The Supplier shall supply all the Goods and Related Services included in the Scope of Supply in accordance with GCC Clause 12, and the Delivery and Completion Schedule, as per GCC Clause 13.

#### 15. Contract Price

15.1 Prices charged by the Supplier for the Goods supplied and the Related Services performed under

- the Contract shall not vary from the prices quoted by the Supplier in its Tender, with the exception of any price adjustments authorized in the SCC.
- Where the contract price is different from the corrected tender price, in order to ensure the supplier is not paid less or more relative to the contract price (*which would be the tender price*), any partial payment valuation based on rates in the schedule of prices in the Tender, will be adjusted by a <u>plus or minus</u> percentage. The percentage already worked out during tender evaluation is worked out as follows: (*corrected tender price tender price*)/tender price X 100.

#### 16. Terms of Payment

- 16.1 The Supplier shall request for payment by submitting invoice(s), delivery note(s) and any other relevant documents as specified in the SCC to the Procuring Entity.
- Payments shall be made promptly by the Procuring Entity, but not later than thirty (30) days after submission of an invoice by the Supplier, and after the Procuring Entity has accepted it.
- Where a Procuring Entity rejects Goods and Related Services, in part or wholly, the procuring Entity shall promptly inform the Supplier to collect, replace or rectify as appropriate and give reasons for rejection. The Supplier shall submit a fresh invoice, delivery note and any other relevant documents as specified in the SCC.
- The currencies in which payments shall be made to the Supplier under this Contract shall be those in which the Tender price is expressed.
- In the event that the Procuring Entity fails to pay the Supplier any payment by its due date or within the period set forth in the SCC, the Procuring Entity may pay to the Supplier interest on the amount of such delayed payment at the rate shown in the SCC, for the period of delay until payment has been made in full, whether before or after judgment or arbitrage award.

#### 17. Taxes and Duties

- 17.1 The Supplier shall be entirely responsible for all taxes, duties, license fees, and other such levies incurred to deliver the Goods and Related Services to the Procuring Entity at the final delivery point.
- 17.3 If any tax exemptions, reductions, allowances or privileges may be available to the Supplier in Kenya, the Supplier shall inform the Procuring Entity and the Procuring Entity shall use its best efforts to enable the Supplier to benefit from any such tax savings to the maximum allowable extent.

## 18. Performance Security

- 18.1 If required as specified in the SCC, the Supplier shall, within twenty-eight (28) days of the notification of contract award, provide a performance security for the performance of the Contract in the amount specified in the SCC.
- The proceeds of the Performance Security shall be payable to the Procuring Entity as compensation for any loss resulting from the Supplier's failure to complete its obligations under the Contract.
- As specified in **the SCC**, the Performance Security, if required, shall be denominated in the currency(ies) of the Contract, or in a freely convertible currency acceptable to the Procuring Entity; and shall be in one of the formats stipulated by the Procuring Entity in **the SCC**, or in another format acceptable to the Procuring Entity.
- 18.4 The Performance Security shall be discharged by the Procuring Entity and returned to the Supplier not later than thirty (30) days following the date of Completion of the Supplier's performance obligations under the Contract, including any warranty obligations, unless specified otherwise in the SCC.

# 19. Copyright

19.1 The copyright in all drawings, documents, and other materials containing data and information furnished to the Procuring Entity by the Supplier herein shall remain vested in the Supplier, or, if

they are furnished to the Procuring Entity directly or through the Supplier by any third party, including suppliers of materials, the copyright in such materials shall remain vested in such third party.

#### 20. Confidential Information

- 20.1 The Procuring Entity and the Supplier shall keep confidential and shall not, without the written consent of the other party hereto, divulge to any third party any documents, data, or other information furnished directly or indirectly by the other party hereto in connection with the Contract, whether such information has been furnished prior to, during or following completion or termination of the Contract. Notwithstanding the above, the Supplier may furnish to its Sub-Supplier such documents, data, and other information it receives from the Procuring Entity to the extent required for the Sub Supplier to perform its work under the Contract, in which event the Supplier shall obtain from such Sub Supplier undertaking of confidentiality similar to that imposed on the Supplier under GCC Clause 20.
- 20.2 The Procuring Entity shall not use such documents, data, and other information received from the Supplier for any purposes unrelated to the contract. Similarly, the Supplier shall not use such documents, data, and other information received from the Procuring Entity for any purpose other than the performance of the Contract.
- 20.3 The obligation of a party under GCC Sub-Clauses 20.1 and 20.2 above, however, shall not apply to information that:
  - a) the Procuring Entity or Supplier need to share with other arms of Government or other bodies participating in the financing of the Contract; such parties shall de disclosed in **the SCC**;
  - b) now or hereafter enters the public domain through no fault of that party;
  - c) can be proven to have been possessed by that party at the time of disclosure and which was not previously obtained, directly or indirectly, from the other party; or
  - d) otherwise lawfully becomes available to that party from a third party that has no obligation of confidentiality.
- 20.4 The above provisions of GCC Clause 20 shall not in any way modify any undertaking of confidentiality given by either of the parties hereto prior to the date of the Contract in respect of the Supply or any part thereof.
- 20.5 The provisions of GCC Clause 20 shall survive completion or termination, for whatever reason, of the Contract.

#### 21. Subcontracting

- 21.1 The Supplier shall notify the Procuring Entity in writing of all subcontracts awarded under the Contract if not already specified in the Tender. Such notification, in the original Tender or later shall not relieve the Supplier from any of its obligations, duties, responsibilities, or liability under the Contract.
- 212 Subcontracts shall comply with the provisions of GCC Clauses 3 and 7.

## 22. Specifications and Standards

- 22.1 Technical Specifications and Drawings
  - a) The Goods and Related Services supplied under this Contract shall conform to the technical specifications and standards mentioned in Section VI, Schedule of Requirements and, when no applicable standard is mentioned, the standard shall be equivalent or superior to the official standards whose application is appropriate to the Goods' country of origin.
  - b) The Supplier shall be entitled to disclaim responsibility for any design, data, drawing, specification or other document, or any modification thereof provided or designed by or on behalf of the Procuring Entity, by giving a notice of such disclaimer to the Procuring Entity.
  - c) Wherever references are made in the Contract to codes and standards in accordance with which it shall be executed, the edition or the revised version of such codes and standards

shall be those specified in the Schedule of Requirements. During Contract execution, any changes in any such codes and standards shall be applied only after approval by the Procuring Entity and shall be treated in accordance with GCC Clause 33.

## 23. Packing and Documents

- 23.1 The Supplier shall provide such packing of the Goods as is required to prevent their damage or deterioration during transit to their final destination, as indicated in the Contract. During transit, the packing shall be sufficient to withstand, without limitation, rough handling and exposure to extreme temperatures, salt and precipitation, and open storage. Packing case size and weights shall take into consideration, where appropriate, the remoteness of the goods' final destination and the absence of heavy handling facilities at all points in transit.
- The packing, marking, and documentation within and outside the packages shall comply strictly with such special requirements as shall be expressly provided for in the Contract, including additional requirements, if any, specified **in the SCC**, and in any other instructions ordered by the Procuring Entity.

#### 24. Insurance

24.1 Unless otherwise specified in the **SCC**, the Goods supplied under the Contract shall be fully insured—in a freely convertible currency from an eligible country—against loss or damage incidental to manufacture or acquisition, transportation, storage, and delivery, in accordance with the applicable Incoterms or in the manner specified in the **SCC**.

#### 25. Transportation and Incidental Services

- 25.1 Unless otherwise specified in the **SCC**, responsibility for arranging transportation of the Goods shall be in accordance with the specified Incoterms.
- 252 The Supplier may be required to provide any or all of the following services, including additional services, if any, specified in SCC:
  - a) performance or supervision of on-site assembly and/or start-up of the supplied Goods;
  - b) furnishing of tools required for assembly and/or maintenance of the supplied Goods;
  - c) furnishing of a detailed operations and maintenance manual for each appropriate unit of the supplied Goods;
  - d) performance or supervision or maintenance and/or repair of the supplied Goods, for a period of time agreed by the parties, provided that this service shall not relieve the Supplier of any warranty obligations under this Contract; and
  - e) training of the Procuring Entity's personnel, at the Supplier's plant and/or on-site, in assembly, start-up, operation, maintenance, and/or repair of the supplied Goods.
- Prices charged by the Supplier for incidental services, if not included in the Contract Price for the Goods, shall be agreed upon in advance by the parties and shall not exceed the prevailing rates charged to other parties by the Supplier for similar services

## **26.** Inspections and Tests

- The Supplier shall at its own expense and at no cost to the Procuring Entity carry out all such tests and/or inspections of the Goods and Related Services as are specified in the SCC.
- The inspections and tests may be conducted on the premises of the Supplier or its Subcontractor, at point of delivery, and/or at the Goods' final destination, or in another place in Kenya as specified in the SCC. Subject to GCC Sub-Clause 26.3, if conducted on the premises of the Supplier or its Subcontractor, all reasonable facilities and assistance, including access to drawings and production data, shall be furnished to the inspectors at no charge to the Procuring Entity.
- 26.3 The Procuring Entity or its designated representative shall be entitled to attend the tests and/or inspections referred to in GCC Sub-Clause 26.2, provided that the Procuring Entity bear all of its own costs and expenses incurred in connection with such attendance including, but not limited to,

all travelling and board and lodging expenses.

- Whenever the Supplier is ready to carry out any such test and inspection, it shall give a reasonable advance notice, including the place and time, to the Procuring Entity. The Supplier shall obtain from any relevant third party or manufacturer any necessary permission or consent to enable the Procuring Entity or its designated representative to attend the test and/or inspection.
- The Procuring Entity may require the Supplier to carry out any test and/or inspection not required by the Contract but deemed necessary to verify that the characteristics and performance of the Goods comply with the technical specifications codes and standards under the Contract, provided that the Supplier's reasonable costs and expenses incurred in the carrying out of such test and/or inspection shall be added to the Contract Price. Further, if such test and/or inspection impedes the progress of manufacturing and/or the Supplier's performance of its other obligations under the Contract, due allowance will be made in respect of the Delivery Dates and Completion Dates and the other obligations so affected.
- 26.6 The Supplier shall provide the Procuring Entity with a report of the results of any such test and/or inspection.
- 26.7 The Procuring Entity may reject any Goods or any part thereof that fail to pass any test and/or inspection or do not conform to the specifications. The Supplier shall either rectify or replace such rejected Goods or parts thereof or make alterations necessary to meet the specifications at no cost to the Procuring Entity, and shall repeat the test and/or inspection, at no cost to the Procuring Entity, upon giving a notice pursuant to GCC Sub- Clause 26.4.
- The Supplier agrees that neither the execution of a test and/or inspection of the Goods or any part thereof, nor the attendance by the Procuring Entity or its representative, nor the issue of any report pursuant to GCC Sub-Clause 26.6, shall release the Supplier from any warranties or other obligations under the Contract.

#### 27. Liquidated Damages

27.1 Except as provided under GCC Clause 32, if the Supplier fails to deliver any or all of the Goods by the Date(s) of delivery or perform the Related Services within the period specified in the Contract, the Procuring Entity may without prejudice to all its other remedies under the Contract, deduct from the Contract Price, as liquidated damages, a sum equivalent to the percentage specified in the SCC of the delivered price of the delayed Goods or unperformed Services for each week or part thereof of delay until actual delivery or performance, up to a maximum deduction of the percentage specified in those SCC. Once the maximum is reached, the Procuring Entity may terminate the Contract pursuant to GCC Clause 35.

#### 28. Warranty

- 28.1 The Supplier warrants that all the Goods are new, unused, and of the most recent or current models, and that they incorporate all recent improvements in design and materials, unless provided otherwise in the Contract.
- Subject to GCC Sub-Clause 22.1(b), the Supplier further warrants that the Goods shall be free from defects arising from any act or omission of the Supplier or arising from design, materials, and workmanship, under normal use in the conditions prevailing in the country of final destination.
- Unless otherwise specified in the **SCC**, the warranty shall remain valid for twelve (12) months after the Goods, or any portion thereof as the case may be, have been delivered to and accepted at the final destination indicated in the **SCC**, or for eighteen (18) months after the date of shipment from the port or place of loading in the country of origin, whichever period concludes earlier.
- 28.4 The Procuring Entity shall give notice to the Supplier stating the nature of any such defects together with all available evidence thereof, promptly following the discovery thereof. The Procuring Entity shall afford all reasonable opportunity for the Supplier to inspect such defects.
- Upon receipt of such notice, the Supplier shall, within the period specified in the SCC, expeditiously repair or replace the defective Goods or parts thereof, at no cost to the Procuring Entity.

28.6 If having been notified, the Supplier fails to remedy the defect within the period specified in the SCC, the Procuring Entity may proceed to take within a reasonable period such remedial action as may be necessary, at the Supplier's risk and expense and without prejudice to any other rights which the Procuring Entity may have against the Supplier under the Contract.

#### 29. Patent Indemnity

- 29.1 The Supplier shall, subject to the Procuring Entity's compliance with GCC Sub-Clause 29.2, indemnify and hold harmless the Procuring Entity and its employees and officers from and against any and all suits, actions or administrative proceedings, claims, demands, losses, damages, costs, and expenses of any nature, including attorney's fees and expenses, which the Procuring Entity may suffer as a result of any infringement or alleged infringement of any patent, utility model, registered design, trademark, copyright, or other intellectual property right registered or otherwise existing at the date of the Contract by reason of:
  - a) the installation of the Goods by the Supplier or the use of the Goods in the country where the Site is located; and
  - b) the sale in any country of the products produced by the Goods.

Such indemnity shall not cover any use of the Goods or any part thereof other than for the purpose indicated by or to be reasonably inferred from the Contract, neither any infringement resulting from the use of the Goods or any part thereof, or any products produced thereby in association or combination with any other equipment, plant, or materials not supplied by the Supplier, pursuant to the Contract.

- 292 If any proceedings are brought or any claim is made against the Procuring Entity arising out of the matters referred to in GCC Sub-Clause 29.1, the Procuring Entity shall promptly give the Supplier a notice thereof, and the Supplier may at its own expense and in the Procuring Entity's name conduct such proceedings or claim and any negotiations for the settlement of any such proceedings or claim.
- If the Supplier fails to notify the Procuring Entity within twenty-eight (28) days after receipt of such notice that it intends to conduct any such proceedings or claim, then the Procuring Entity shall be free to conduct the same on its own behalf.
- 29.4 The Procuring Entity shall, at the Supplier's request, afford all available assistance to the Supplier in conducting such proceedings or claim, and shall be reimbursed by the Supplier for all reasonable expenses incurred in so doing.
- The Procuring Entity shall indemnify and hold harmless the Supplier and its employees, officers, and Subcontractors from and against any and all suits, actions or administrative proceedings, claims, demands, losses, damages, costs, and expenses of any nature, including attorney's fees and expenses, which the Supplier may suffer as a result of any infringement or alleged infringement of any patent, utility model, registered design, trademark, copyright, or other intellectual property right registered or otherwise existing at the date of the Contract arising out of or in connection with any design, data, drawing, specification, or other documents or materials provided or designed by or on behalf of the Procuring Entity.

#### 30. Limitation of Liability

- 30.1 Except in cases of criminal negligence or willful misconduct,
  - a) the Supplier shall not be liable to the Procuring Entity, whether in contract, tort, or otherwise, for any indirect or consequential loss or damage, loss of use, loss of production, or loss of profits or interest costs, provided that this exclusion shall not apply to any obligation of the Supplier to pay liquidated damages to the Procuring Entity, and
  - b) the aggregate liability of the Supplier to the Procuring Entity, whether under the Contract, in tort or otherwise, shall not exceed the total Contract Price, provided that this limitation shall not apply to the cost of repairing or replacing defective equipment, or to any obligation of the supplier to indemnify the Procuring Entity with respect to patent infringement.

#### 31. Change in Laws and Regulations

31.1 Unless otherwise specified in the Contract, if after the date of 30 days prior to date of Tender submission, any law, regulation, ordinance, order or bylaw having the force of law is enacted, promulgated, abrogated, or changed in Kenya (which shall be deemed to include any change in interpretation or application by the competent authorities) that subsequently affects the Delivery Date and/or the Contract Price, then such Delivery Date and/or Contract Price shall be correspondingly increased or decreased, to the extent that the Supplier has thereby been affected in the performance of any of its obligations under the Contract. Notwithstanding the foregoing, such additional or reduced cost shall not be separately paid or credited if the same has already been accounted for in the price adjustment provisions where applicable, in accordance with GCC Clause 15.

## 32. Force Majeure

- 32.1 The Supplier shall not be liable for forfeiture of its Performance Security, liquidated damages, or termination for default if and to the extent that its delay in performance or other failure to perform its obligations under the Contract is the result of an event of Force Majeure.
- For purposes of this Clause, "Force Majeure" means an event or situation beyond the control of the Supplier that is not foreseeable, is unavoidable, and its origin is not due to negligence or lack of care on the part of the Supplier. Such events may include, but not be limited to, acts of the Procuring Entity in its sovereign capacity, wars or revolutions, fires, floods, epidemics, quarantine restrictions, and freight embargoes.
- 323 If a Force Majeure situation arises, the Supplier shall promptly notify the Procuring Entity in writing of such condition and the cause thereof. Unless otherwise directed by the Procuring Entity in writing, the Supplier shall continue to perform its obligations under the Contract as far as is reasonably practical, and shall seek all reasonable alternative means for performance not prevented by the Force Majeure event.

## 33. Change Orders and Contract Amendments

- 33.1 The Procuring Entity may at any time order the Supplier through notice in accordance GCC Clause 8, to make changes within the general scope of the Contract in any one or more of the following:
  - a) drawings, designs, or specifications, where Goods to be furnished under the Contract are to be specifically manufactured for the Procuring Entity;
  - b) the method of shipment or packing;
  - c) the place of delivery; and
  - d) the Related Services to be provided by the Supplier.
- 33.2 If any such change causes an increase or decrease in the cost of, or the time required for, the Supplier's performance of any provisions under the Contract, an equitable adjustment shall be made in the Contract Price or in the Delivery/Completion Schedule, or both, and the Contract shall accordingly be amended. Any claims by the Supplier for adjustment under this Clause must be asserted within twenty-eight (28) days from the date of the Supplier's receipt of the Procuring Entity's change order.
- Prices to be charged by the Supplier for any Related Services that might be needed but which were not included in the Contract shall be agreed upon in advance by the parties and shall not exceed the prevailing rates charged to other parties by the Supplier for similar services.
- Value Engineering: The Supplier may prepare, at its own cost, a value engineering proposal at any time during the performance of the contract. The value engineering proposal shall, at a minimum, include the following;
  - a) the proposed change(s), and a description of the difference to the existing contract requirements;
  - b) a full cost/benefit analysis of the proposed change(s) including a description and estimate of costs (including life cycle costs) the Procuring Entity may incur in implementing the value engineering proposal; and
  - c) a description of any effect(s) of the change on performance/functionality.

- The Procuring Entity may accept the value engineering proposal if the proposal demonstrates benefits that:
  - a) accelerates the delivery period; or
  - b) reduces the Contract Price or the life cycle costs to the Procuring Entity; or
  - c) improves the quality, efficiency or sustainability of the Goods; or
  - d) yields any other benefits to the Procuring Entity, without compromising the necessary functions of the Facilities.
- 33.6 If the value engineering proposal is approved by the Procuring Entity and results in:
  - a) a reduction of the Contract Price; the amount to be paid to the Supplier shall be the percentage specified **in the SCC** of the reduction in the Contract Price; or
  - b) an increase in the Contract Price; but results in a reduction in life cycle costs due to any benefit described in
    - (a) to (d) above, the amount to be paid to the Supplier shall be the full increase in the Contract Price.
- 33.7 Subject to the above, no variation in or modification of the terms of the Contract shall be made except by written amendment signed by the parties.

#### 34. Extensions of Time

- 34.1 If at any time during performance of the Contract, the Supplier or its subcontractors should encounter conditions impeding timely delivery of the Goods or completion of Related Services pursuant to GCC Clause 13, the Supplier shall promptly notify the Procuring Entity in writing of the delay, its likely duration, and its cause. As soon as practicable after receipt of the Supplier's notice, the Procuring Entity shall evaluate the situation and may at its discretion extend the Supplier's time for performance, in which case the extension shall be ratified by the parties by amendment of the Contract.
- Except in case of Force Majeure, as provided under GCC Clause 32, a delay by the Supplier in the performance of its Delivery and Completion obligations shall render the Supplier liable to the imposition of liquidated damages pursuant to GCC Clause 26, unless an extension of time is agreed upon, pursuant to GCC Sub-Clause 34.1.

#### 35. Termination

- 35.1 Termination for Default
  - a) The Procuring Entity, without prejudice to any other remedy for breach of Contract, by written notice of default sent to the Supplier, may terminate the Contract in whole or in part:
    - i) if the Supplier fails to deliver any or all of the Goods within the period specified in the Contract, or within any extension thereof granted by the Procuring Entity pursuant to GCC Clause 34;
    - ii) if the Supplier fails to perform any other obligation under the Contract; or
    - iii) if the Supplier, in the judgment of the Procuring Entity has engaged in Fraud and Corruption, as defined in paragraph 2.2 a of the Appendix to the GCC, in competing for or in executing the Contract.
  - b) In the event the Procuring Entity terminates the Contract in whole or in part, pursuant to GCC Clause 35.1(a), the Procuring Entity may procure, upon such terms and in such manner as it deems appropriate, Goods or Related Services similar to those undelivered or not performed, and the Supplier shall be liable to the Procuring Entity for any additional costs for such similar Goods or Related Services. However, the Supplier shall continue performance of the Contract to the extent not terminated.

# 35.2 Termination for Insolvency.

The Procuring Entity may at any time terminate the Contract by giving notice to the Supplier if the Supplier becomes bankrupt or otherwise insolvent. In such event, termination will be without compensation to the Supplier, provided that such termination will not prejudice or affect any right of action or remedy that has accrued or will accrue thereafter to the Procuring Entity

#### 35.2 Termination for Convenience.

- a) The Procuring Entity, by notice sent to the Supplier, may terminate the Contract, in whole or in part, at any time for its convenience. The notice of termination shall specify that termination is for the Procuring Entity's convenience, the extent to which performance of the Supplier under the Contract is terminated, and the date upon which such termination becomes effective.
- b) The Goods that are complete and ready for shipment within twenty-eight (28) days after the Supplier's receipt of notice of termination shall be accepted by the Procuring Entity at the Contract terms and prices. For the remaining Goods, the Procuring Entity may elect:
  - i) to have any portion completed and delivered at the Contract terms and prices; and/or
  - to cancel the remainder and pay to the Supplier an agreed amount for partially completed Goods and Related Services and for materials and parts previously procured by the Supplier.

#### 36. Assignment

36.1 Neither the Procuring Entity nor the Supplier shall assign, in whole or in part, their obligations under this Contract, except with prior written consent of the other party.

## 37. Export Restriction

37.1 Notwithstanding any obligation under the Contract to complete all export formalities, any export restrictions attributable to the Procuring Entity, to Kenya, or to the use of the products/goods, systems or services to be supplied, which arise from trade regulations from a country supplying those products/goods, systems or services, and which substantially impede the Supplier from meeting its obligations under the Contract, shall release the Supplier from the obligation to provide deliveries or services, always provided, however, that the Supplier can demonstrate to the satisfaction of the Procuring Entity that it has completed all formalities in a timely manner, including applying for permits, authorizations and licenses necessary for the export of the products/goods, systems or services under the terms of the Contract. Termination of the Contract on this basis shall be for the Procuring Entity's convenience pursuant to Sub-Clause 35.3.

## SECTION VII - SPECIAL CONDITIONS OF CONTRACT

The following Special Conditions of Contract (SCC) shall supplement and/or amend the General Conditions of Contract (GCC). Whenever there is a conflict, the provisions herein shall prevail over those in the GCC.

[The Procuring Entity shall select insert the appropriate wording using the samples below or other acceptable wording, and delete the text in italics].

## SECTION VII - SPECIAL CONDITIONS OF CONTRACT

The following Special Conditions of Contract (SCC) shall supplement and / or amend the General Conditions of Contract (GCC). Whenever there is a conflict, the provisions herein shall prevail over those in the GCC.

[The KENYA REVENUE AUTHORITY shall select insert the appropriate wording using the samples below or other acceptable wording, and delete the text in italics]

Number of GC	Amendments of, and Supplements to, Clauses in the General Conditions of Contract
Clause	
GCC 1.1(h)	The KENYA REVENUE AUTHORITY is: Procuring Entity
GCC 4.2 (a)	The meaning of the trade terms shall be as prescribed by Incoterms. If the meaning of any trade term and the rights and obligations of the parties thereunder shall not be as prescribed by Incoterms, they shall be as prescribed by: [exceptional; refer to other internationally accepted trade terms]
GCC 4.2 (b)	The version edition of Incoterms shall be <i>INCOTERMS 2015</i>
GCC 8.1	For notices, the KRA's address shall be: Deputy Commissioner-Supply Chain Management Times Tower Building, 21st Floor, P.O Box 48240–00100 GPO, Tel. +254 02 281 7022 Nairobi, Kenya. website: www.kra.go.ke Email:eprocurement@kra.go.ke
GCC 10.4.2	The place of arbitration shall be <i>The place of arbitration shall be Nairobi</i> , <i>Kenya</i> )
GCC 13.1	Details of Shipping and other Documents to be furnished by the Supplier are [insert the required documents, such as a negotiable bill of lading, a non-negotiable sea way bill, an airway bill, a railway consignment note, a road consignment note, insurance certificate, Manufacturer's or Supplier's warranty certificate, inspection certificate issued by nominated inspection agency, Supplier's factory shipping details etc.]-  The above documents shall be received by the KENYA REVENUE AUTHORITY before arrival of the Goods and, if not received, the Supplier will be responsible for any consequent expenses.
GCC 15.1	The prices variation/ adjustment for the Goods supplied and the related Services performed <i>shall</i> be adjustable in accordance with the Public Procurement and Asset Disposal Act (2015) and the Public Procurement and Asset Disposal Regulations (2020).
GCC 16.1	Sample provision
	GCC 16.1—The method and conditions of payment to be made to the Supplier under this Contract shall be as follows:
	A. Payment for Goods supplied from abroad:  Payment of foreign currency portion shall be made in [insert currency of the Contract Price] in the following manner:
	(i) Advance Payment: Ten (10) percent of the Contract Price shall be paid within thirty (30) days of signing of the Contract, and upon submission of claim and a bank guarantee

	for equivalent amount valid until the Goods are delivered and, in the form, provided in the Tendering document or another form acceptable to the KENYA REVENUE AUTHORITY.
	(ii) <b>On Shipment:</b> Eighty (80) percent of the Contract Price of the Goods shipped shall be paid through irrevocable confirmed letter of credit opened in favour of the Supplier in a bank in its country, upon submission of documents specified in GCC Clause 12.
	(iii) <b>On Acceptance:</b> Ten (10) percent of the Contract Price of Goods received shall be paid within thirty (30) days of receipt of the Goods upon submission of claim supported by the acceptance certificate issued by the KENYA REVENUE AUTHORITY.
	B. Payment of local currency portion of a foreign Supplier shall be made in Kenya shillings within thirty (30) days of presentation of claim supported by a certificate from the KENYA REVENUE AUTHORITY declaring that the Goods have been delivered and that all other contracted Services have been performed.  C. Payment for Goods and Services supplied from within Kenya:
	Payment for Goods and Services supplied from within Kenya shall be made in [currency], as follows:
	(i) <b>Advance Payment:</b> Ten (10) percent of the Contract Price shall be paid within thirty (30) days of signing of the Contract against an invoice and a bank guarantee for the equivalent amount and in the form provided in the Tendering document or another form acceptable to the KENYA REVENUE AUTHORITY.
	(ii) <b>On Delivery:</b> Eighty (80) percent of the Contract Price shall be paid on receipt of the Goods and upon submission of the documents specified in GCC Clause 13. The bank guarantee shall then be released.
	(iii) <b>On Acceptance:</b> The remaining ten (10) percent of the Contract Price shall be paid to the Supplier within thirty (30) days after the date of the acceptance certificate for the respective delivery issued by the KENYA REVENUE AUTHORITY.
GCC 16.5	The payment-delay period after which the KENYA REVENUE AUTHORITY shall pay interest to the supplier shall be [insert number] days.
000101	The interest rate that shall be applied is [insert number] %
GCC 18.1	A Performance Security ["shall" be required]  Performance security shall be 5% of the Contract Value and may be required in accordance with Sections 142, 143, 144 and 145 of the Public Procurement and Asset Disposal Act, 2015.
GCC 18.3	If required, the Performance Security shall be inform of a Bank Guarantee from a Bank or authorized financial institution Regulated by Central Bank of Kenya (CBK) or inform of a performance guarantee/bond from an Insurance Company Registered and Licensed by the Insurance Regulatory Authority (IRA) equivalent to Five Percent (5%) of the contract value.
GCC 18.4	Discharge of the Performance Security shall take place: [ insert date if different from the
GCC 23.2	one indicated in sub clause GCC 18.4]  The packing, marking and documentation within and outside the packages shall be: [insert in detail the type of packing required, the markings in the packing and all documentation required]
GCC 24.1	The insurance coverage shall be as specified in the Incoterms.  If not in accordance with Incoterms, insurance shall be as follows:  [insert specific insurance provisions agreed upon, including coverage, currency and amount]
	with the state of

	If not in accordance with Inactomic manageribility for transportations shall be as follows:
	If not in accordance with Incoterms, responsibility for transportations shall be as follows:
	[insert "The Supplier is required under the Contract to transport the Goods to a specified
	place of final destination within Kenya, defined as the Project Site, transport to such place
	of destination in Kenya, including insurance and storage, as shall be specified in the
	Contract, shall be arranged by the Supplier, and related costs shall be included in the
	Contract Price"; or any other agreed upon trade terms (specify the respective
	responsibilities of the KENYA REVENUE AUTHORITY and the Supplier)]
GCC 25.2	Incidental services to be provided are:
	[Selected services covered under GCC Clause 25.2 and/or other should be specified with
	the desired features. The price quoted in the Tender price or agreed with the selected
	Supplier shall be included in the Contract Price.]
GCC 26.1	The inspections and tests shall be: [insert nature, frequency, procedures for carrying out
	the inspections and tests]
GCC 26.2	The Inspections and tests shall be conducted at: [ TIMES TOWER BUILDING
GCC 27.1	The liquidated damage shall be: [insert number] % per week
GCC 27.1	The maximum amount of liquidated damages shall be: [insert number] %
GCC 28.3	
	The period of validity of the Warranty shall be: [insert number] days
	For purposes of the Warranty, the place(s) of final destination(s) shall be:
	[insert name(s) of location(s)]
	Sample provision
	GCC 28.3—In partial modification of the provisions, the warranty period shall be
	hours of operation or months from date of acceptance of the Goods or ()
	months from the date of shipment, whichever occurs earlier. The Supplier shall, in addition,
	comply with the performance and/or consumption guarantees specified under the Contract.
	If, for reasons attributable to the Supplier, these guarantees are not attained in whole or in
	part, the Supplier shall, at its discretion, either:
	(a) make such changes, modifications, and/or additions to the Goods or any part thereof
	as may be necessary in order to attain the contractual guarantees specified in the Contract
	at its own cost and expense and to carry out further performance tests in accordance with
	GCC 26.7,
	or
	(b) pay liquidated damages to the KENYA REVENUE AUTHORITY with respect
	to the failure to meet the contractual guarantees. The rate of these liquidated damages shall
	be ().
	[The rate should be higher than the adjustment rate used in the Tender evaluation under
	TDS 34.6(f)]
GCC 28.5, GCC 28.6	The period for repair or replacement shall be: [insert number(s)] days.
GCC 33.6	If the value engineering proposal is approved by the KENYA REVENUE AUTHORITY
	the amount to be paid to the Supplier shall be% (insert appropriate percentage.
	The percentage is normally up to 50%) of the reduction in the Contract Price.

## **SECTION VIII - CONTRACT FORMS**

This Section contains forms which, once completed, will form part of the Contract. The forms for Performance Security and Advance Payment Security, when required, shall only be completed by the successful tenderer after contract award.

# FORM No. 1: NOTIFICATION OF INTENTION TO AWARD

this N	Notific ormat	cation of Intention to Award shall be sent to each Tenderer that submitted a Tender. Send cation to the Tenderer's Authorized Representative named in the Tender Information Form on below.			
<u>FOR</u>	<u>MAT</u>				
1.	For	the attention of Tenderer's Authorized Representative			
	I)	Name:[insert Authorized Representative's name]			
	ii)	Address:[insert Authorized Representative's Address]			
	iii)	Telephone:[insert Authorized Representative's telephone/fax numbers]			
	iv)	Email Address:[insert Authorized Representative's email address]			
	sent	PORTANT: insert the date that this Notification is transmitted to Tenderers. The Notification must be to all Tenderers simultaneously. This means on the same date and as close to the same time possible.]			
2	Date	e of transmission: [email] on [date] (local time)			
	This	s Notification is sent by (Name and designation)			
3.	Not	ification of Intention to Award			
	I)	Employer:[insert the name of the Employer]			
	ii)	Project:[insert name of project]			
	iii)	Contract title:[insert the name of the contract]			
	iv)	Country:[insert country where ITT is issued]			
	v)	ITT No:[insert ITT reference number from Procurement Plan]			
	abo	s Notification of Intention to Award (Notification) notifies you of our decision to award the ve contract. The transmission of this Notification begins the Standstill Period. During the Standstill lod, you may:			
4.	Request a debriefing in relation to the evaluation of your tender				
	Sub	mit a Procurement-related Complaint in relation to the decision to award the contract.			
	a)	The successful tenderer			
		i) Name of successful Tender			
		ii) Address of the successful Tender			
		iii) Contract price of the successful Tender Kenya Shillings(in words			
	b)	Other Tenderers			
		nes of all Tenderers that submitted a Tender. If the Tender's price was evaluated include the luated price as well as the Tender price as read out. For Tenders not evaluated, give one main			

reason the Tender was unsuccessful.

S/No.	Name of Tender	Tender Price as read out	Tender's evaluated price (Note a)	One Reason Why Not Evaluated
1				
2				
3				
4				
5				

#### (Note a) State NE if not evaluated

- 5. How to request a debriefing
  - a) DEADLINE: The deadline to request a debriefing expires at midnight on [insert date] (local time).
  - b) You may request a debriefing in relation to the results of the evaluation of your Tender. If you decide to request a debriefing your written request must be made within three (5) Business Days of receipt of this Notification of Intention to Award.
  - c) Provide the contract name, reference number, name of the Tenderer, contact details; and address the request for debriefing as follows:

I)	Attention:	[insert full name of person,	if applicable]
ii)	Title/position:	[insert title/position]	
ii)	Agency:	_[insert name of Employer]	
iii)	Email address:	[insert email address]	

- d) If your request for a debriefing is received within the 3 Days deadline, we will provide the debriefing within five (3) Business Days of receipt of your request. If we are unable to provide the debriefing within this period, the Standstill Period shall be extended by five (3) Days after the date that the debriefing is provided. If this happens, we will notify you and confirm the date that the extended Standstill Period will end.
- e) The debriefing may be in writing, by phone, video conference call or in person. We shall promptly advise you in writing how the debriefing will take place and confirm the date and time.
- f) If the deadline to request a debriefing has expired, you may still request a debriefing. In this case, we will provide the debriefing as soon as practicable, and normally no later than fifteen (15) Days from the date of publication of the Contract Award Notice.
- 6 How to make a complaint
  - a) Period: Procurement-related Complaint challenging the decision to award shall be submitted by midnight, [insert date] (local time).
  - b) Provide the contract name, reference number, name of the Tenderer, contact details; and address the Procurement-related Complaint as follows:

I)	Attention:	_[insert full name of person, if applicable]
ii)	Title/position:	[insert title/position]
iii)	Agency:	[insert name of Employer]
iv)	Email address:	[insert email address]

- c) At this point in the procurement process, you may submit a Procurement-related Complaint challenging the decision to award the contract. You do not need to have requested, or received, a debriefing before making this complaint. Your complaint must be submitted within the Standstill Period and received by us before the Standstill Period ends.
- d) Further information: For more information refer to the Public Procurement and Disposals Act 2015 and its Regulations available from the Website <a href="www.ppra.go.ke">www.ppra.go.ke</a> or email <a href="complaints@ppra.go.ke">complaints@ppra.go.ke</a>.

You should read these documents before preparing and submitting your complaint.

- e) There are four essential requirements:
- i) You must be an 'interested party'. In this case, that means a Tenderer who submitted a Tender in this tendering process, and is the recipient of a Notification of Intention to Award.
- ii) The complaint can only challenge the decision to award the contract.
- iii) You must submit the complaint within the period stated above.
- iv) You must include, in your complaint, all of the information required to support your complaint.

## 7. <u>Standstill</u> Period

- i) DEADLINE: The Standstill Period is due to end at midnight on [insert date] (local time).
- ii) The Standstill Period lasts ten (14) Days after the date of transmission of this Notification of Intention to Award.
- iii) The Standstill Period may be extended as stated in paragraph Section 5 (d) above.

If you have any questions regarding this Notification please do not hesitate to contact us.

On behalf of the Employer:		
Signature:		
Name:		
Title/position:		
Telephone:		
Email:		

## FORM NO. 2 - REQUEST FOR REVIEW

**Board Secretary** 

#### FORM FOR REVIEW(r.203(1))

# PUBLIC PROCUREMENT ADMINISTRATIVE REVIEW BOARD APPLICATION NO.......OF......20....... **BETWEEN** ......APPLICANT AND ......RESPONDENT (KENYA REVENUE AUTHORITY) REQUEST FOR REVIEW I/We....,the above named Applicant(s), of address: Physical address..........P. O. Box No....... Tel. No...... Email ....., hereby request the Public Procurement Administrative Review Board to review the whole/part of the above mentioned decision on the following grounds, namely: 1. By this memorandum, the Applicant requests the Board for an order/orders that: 1. 2. FOR OFFICIAL USE ONLY Lodged with the Secretary Public Procurement Administrative Review Board on......day of .....20...... **SIGNED**

# FORM NO. 3 LETTER OF AWARD

[Use letter head paper of the KENYA REVENUE AUTHORITY]	
[Date]	
To:[name and address of the Supplier]	
Subject:Notification of Award Contract No	
This is to notify you that your Tender dated	SCC] name
You are requested to furnish the Performance Security within 30 days in accordance with the Con of Contract, using for that purpose the of the Performance Security Form included in Section X, C Forms, of the Tendering document.	
Authorized Signature:	
Name and Title of Signatory:	
Name of Agency:	

**Attachment: Contract Agreement** 

# FORM NO. 4 - CONTRACT AGREEMENT

[The	succe	essful	tenderer shall fill in this form in accordance with the instructions indicated]
year] prince Entity laws	ipal py"), of [in	TWEE lace of the nsert:	ENT made the[insert: number] day of[insert: month], [insert: N (1)[insert complete name of Procuring Entity and having its of business at [insert: address of Procuring Entity] (hereinafter called "Procuring the one part; and (2)[insert name of Supplier], a corporation incorporated under the country of Supplier] and having its principal place of business at[insert: address reinafter called "the Supplier"), of the other part.
1.	WHI	EREA	S the Procuring Entity invited Tenders for certain Goods and ancillary services, viz.,
	_		ef description of Goods and Services] and has accepted a Tender by the Supplier for the those Goods and Services, the Procuring Entity and the Supplier agree as follows:
	i)		nis Agreement words and expressions shall have the same meanings as are ectively assigned to them in the Contract documents referred to.
	ii)		following documents shall be deemed to form and be read and construed as part of this eement. This Agreement shall prevail over all other contract documents.
		a)	the Letter of Acceptance
		b)	the Letter of Tender
		c)	the Addenda Nos(if any)
		d)	Special Conditions of Contract
		e)	General Conditions of Contract
		f)	the Specification (including Schedule of Requirements and Technical Specifications)
		g)	the completed Schedules (including Price Schedules)
		h)	any other document listed in GCC as forming part of the Contract
	iii)	spec the	consideration of the payments to be made by the Procuring Entity to the Supplier as ified in this Agreement, the Supplier hereby covenants with the Procuring Entity to provide Goods and Services and to remedy defects therein in conformity in all respects with the isions of the Contract.
2.	Good may	ds and becor	ring Entity hereby covenants to pay the Supplier in consideration of the provision of the I Services and the remedying of defects therein, the Contract Price or such other sum as me payable under the provisions of the Contract at the times and in the manner prescribed ntract.
3.			ESS whereof the parties hereto have caused this Agreement to be executed in accordance aws of Kenya on the day, month and year indicated above.
For a	nd or	n beha	lf of the KENYA REVENUE AUTHORITY
Signe	ed:		[insert signature]
in the	e capa	acity (	of[insert title or other appropriate designation] In the presence of
			[insert identification of official witness] For and on behalf of the Supplier
Signe	ed:		[insert signature of authorized representative(s) of the Supplier] in the capacity of_
			[insert title or other appropriate designation] in the presence of_
			[insert identification of official witness]

# FORM NO. 5 - PERFORMANCE SECURITY [Option 1 - Unconditional Demand Bank Guarantee]

[Gu	arantor letterhe	d]
Ben	eficiary:	[insert name and Address of
Етр	oloyer]	
Date	e:	[Insert date of issue]
	r <b>antor:</b> rhead]	[Insert name and address of place of issue, unless indicated in the
1.	We have b	een informed that(hereinaft
	er called "th	Contractor") has entered into Contract Nodated
	Employer as Contract").	with (name of Employer) (the he Beneficiary), for the execution of (hereinafter called "the
2.		we understand that, according to the conditions of the Contract, a uarantee is required.
3.	Beneficiary a being payabl payable, upo Beneficiary's accompanying obligation(s)	of the Contractor, we as Guarantor, hereby irrevocably undertake to pay the y sum or sums not exceeding in total an amount of(in words),¹ such sum in the types and proportions of currencies in which the Contract Price is receipt by us of the Beneficiary's complying demand supported by the statement, whether in the demand itself or in a separate signed document or identifying the demand, stating that the Applicant is in breach of its under the Contract, without the Beneficiary needing to prove or to show our demand or the sum specified therein.
4.		shall expire, no later than the Day of, 2 <sup>2</sup> , and any demand for it must be received by us at the office indicated above on or before that
5.	[six months]	agrees to a one-time extension of this guarantee for a period not to exceed one year], in response to the Beneficiary's written request for such extension, to be presented to the Guarantor before the expiry of the guarantee."
 [Nai	ne of Authorize	Official, signature(s) and seals/stamps]

Note: All italicized text (including footnotes) is for use in preparing this form and shall be deleted from the final product.

## FORM No. 6 - PERFORMANCE SECURITY [Option 2– Performance Bond]

[Note: Procuring Entities are advised to use Performance Security – Unconditional Demand Bank Guarantee instead of Performance Bond due to difficulties involved in calling Bond holder to action] [Guarantor letterhead or SWIFT identifier code] **Beneficiary:** \_\_\_\_\_\_\_ [insert name and Address of Employer] Date: [Insert date of issue] PERFORMANCE BOND No.:\_\_\_\_ Guarantor: \_\_\_\_\_[Insert name and address of place of issue, unless indicated in the letterhead] By this Bond\_\_\_\_\_ as Principal (hereinafter called "the Contractor") 1. and \_\_\_\_\_\_ ] as Surety (hereinafter called "the Surety"), are held and firmly bound unto \_\_\_\_\_\_ ] as Obligee (hereinafter called "the Employer") in the amount of\_for the payment of which sum well and truly to be made in the types and proportions of currencies in which the Contract Price is payable, the Contractor and the Surety bind themselves, their heirs, executors, administrators, successors and assigns, jointly and severally, firmly by these presents. 2. WHEREAS the Contractor has entered into a written Agreement with the Employer dated the \_\_\_\_day of , 20\_\_\_\_\_\_, for\_\_\_\_ \_\_\_\_\_aay or , 20\_\_\_\_\_\_, for\_\_\_\_\_in accordance with the documents, plans, specifications, and amendments thereto, which to the extent herein provided for, are by reference made part hereof and are hereinafter referred to as the Contract. NOW, THEREFORE, the Condition of this Obligation is such that, if the Contractor shall promptly 3. and faithfully perform the said Contract (including any amendments thereto), then this obligation shall be null and void; otherwise, it shall remain in full force and effect. Whenever the Contractor shall be, and declared by the Employer to be, in default under the Contract, the Employer having performed the Employer's obligations thereunder, the Surety may promptly remedy the default, or shall promptly: complete the Contract in accordance with its terms and conditions; or obtain a tender or tenders from qualified tenderers for submission to the Employer for 2) completing the Contract in accordance with its terms and conditions, and upon determination by the Employer and the Surety of the lowest responsive Tenderers, arrange for a Contract between such Tenderer, and Employer and make available as work progresses (even though there should be a default or a succession of defaults under the Contract or Contracts of completion arranged under this paragraph) sufficient funds to pay the cost of completion less the Balance of the Contract Price; but not exceeding, including other costs and damages for which the Surety may be liable hereunder, the amount set forth in the first paragraph hereof. The term "Balance of the Contract Price," as used in this paragraph, shall mean the total amount payable by Employer to Contractor under the Contract, less the amount properly paid by Employer to Contractor; or pay the Employer the amount required by Employer to complete the Contract in accordance with its terms and conditions up to a total not exceeding the amount of this Bond. The Surety shall not be liable for a greater sum than the specified penalty of this Bond. 4.

issuing of the Taking-Over Certificate. No right of action shall accrue on this Bond to or for the use of any person or corporation other than the Employer named herein or the heirs, executors, administrators, successors, and assigns of the Employer.

5.

Any suit under this Bond must be instituted before the expiration of one year from the date of the

6. In testimony whereof, the Contractor has hereunto set his hand and affixed his seal, and the Surety has caused these presents to be sealed with his corporate seal duly attested by the signature of his legal representative,

this day	of20
SIGNED ON	on behalf of
Ву	in the capacity of
In the presence of	
SIGNED ON	on behalf of
Ву	in the capacity of
In the presence of	

## **FORM NO. 7 - ADVANCE PAYMENT SECURITY** [Demand Bank Guarantee]

[Guarantor i	letterhead l
--------------	--------------

Beneficiary:			[Insert
name and Address of Employer]  Date: [Insert date of issue]			
ADVANCE PAYMENT GUARANTEE No.: number]	[Insert	guarantee	reference
Guarantor: [Insert name and address of place of issue, unless indicated in t	he letterhe	ad]	
1. We have been informed that (hereinafter called Contract No dated with the Be (hereinafter called "the Contract").	d "the Conneficiary,	ntractor") has e	entered into ecution of
2. Furthermore, we understand that, according to the conditions of the sum (in words) is to be made against an advance payment g		ın advance pay	ment in the
3. At the request of the Contractor, we as Guarantor, hereby irrevocably sum or sums not exceeding in total an amount of upon receipt by us of the Beneficiary's complying demand supported by the demand itself or in a separate signed document accompanying or identify Applicant:	(in words e Beneficia	ry's statement,	whether in
<ul><li>(a) has used the advance payment for purposes other than the costs of mol</li><li>(b) has failed to repay the advance payment in accordance with the Contra which the Applicant has failed to repay.</li></ul>			
4. A demand under this guarantee may be presented as from the present from the Beneficiary's bank stating that the advance payment referred to about on its account number at			
5. The maximum amount of this guarantee shall be progressively red payment repaid by the Contractor as specified in copies of interim statement be presented to us. This guarantee shall expire, at the latest, upon our rece certificate indicating that ninety (90) percent of the Accepted Contract Amount for payment, or on the day of, 2, <sup>2</sup> which demand for payment under this guarantee must be received by us at this office.	ts or payments or payments of a coount, less particular the control of the contro	ent certificates py of the interiorovisional sum arlier. Consequent	which shall m payment as, has been
6. The Guarantor agrees to a one-time extension of this guarantee for a popular year], in response to the Beneficiary's written request for such extension, Guarantor before the expiry of the guarantee.			
[Name of Authorized Official, signature(s) and seals/stamps]  Note: All italicized text (including footnotes) is for use in preparing this for product.	m and sha	ll be deleted fro	om the final

<sup>&</sup>lt;sup>1</sup>The Guarantor shall insert an amount representing the amount of the advance payment and denominated either in the currency of the advance payment as specified in the Contract.

<sup>&</sup>lt;sup>2</sup> Insert the expected expiration date of the Time for Completion. The Employer should note that in the event of an extension of the time for completion of the Contract, the Employer would need to request an extension of this guarantee from the Guarantor. Such request must be in writing and must be made prior to the expiration date established in the guarantee.

# FORM NO. 8 BENEFICIAL OWNERSHIP DISCLOSURE FORM (Amended and issued pursuant to PPRA CIRCULAR No. 02/2022)

#### INSTRUCTIONS TO TENDERERS: DELETE THIS BOX ONCE YOU HAVE COMPLETED THE FORM

This Beneficial Ownership Disclosure Form ("Form") is to be completed by the successful tenderer pursuant to Regulation 13 (2A) and 13 (6) of the Companies (Beneficial Ownership Information) Regulations, 2020. In case of joint venture, the tenderer must submit a separate Form for each member. The beneficial ownership information to be submitted in this Form shall be current as of the date of its submission.

For the purposes of this Form, a Beneficial Owner of a Tenderer is any natural person who ultimately owns or controls the legal person (tenderer) or arrangements or a natural person on whose behalf a transaction is conducted, and includes those persons who exercise ultimate effective control over a legal person (Tenderer) or arrangement.

Tender Reference No.:		[insert identification
no] Name of the Tender Title/Descript	ion:	[insert name of the
assignment] to:	_[insert complete name of K	ENYA REVENUE AUTHORITY]
In response to the requirement in your additional information on beneficial or options that are not applicable]		[insert date of notification of award] to furnish [select one option as applicable and delete the

I) We here by provide the following beneficial ownership information.

Details of beneficial ownership

	Details of all Beneficial Ow	ners % of shares a person holds in the company Directly or indirectly	% of voting rights a person holds in the company	Whether a person directly or indirectly holds a right to appoint or remove a member of the board of directors of the company or an equivalent governing body of the Tenderer (Yes / No)	Whether a person directly or indirectly exercises significant influence or control over the Company (tenderer) (Yes / No)
1.	Full Name  National identity card number or Passport number	Directly % of shares	Directly% of voting rights	1. Having the right to appoint a majority of the board of the directors or an equivalent	Exercises     significant     influence or     control over     the Company
1.	Personal Identification Number (where applicable)	Indirectly % of shares	Indirectly % of voting rights	governing body of the Tenderer: Yes No 2. Is this right held directly or	body of the Company (tenderer)
	Nationality			indirectly?:	
	Date of birth [dd/mm/yyyy]  Postal address			Direct	2. Is this influence or control
	Residential address				exercised
	Telephone number			Indirect	directly or indirectly?
	Email address				Direct
	Occupation or profession				Indirect

	Details of all Beneficia	al Owners	% of shares a person holds in the company Directly or indirectly	% of voting rights a person holds in the company	Whether a person directly or indirectly holds a right to appoint or remove a member of the board of directors of the company or an equivalent governing body of the Tenderer (Yes / No)	Whether a person directly or indirectly exercises significant influence or control over the Company (tenderer) (Yes / No)
						•••
2.	Full Name  National identity card number or		Directly % of shares	Directly% of voting rights	1. Having the right to appoint a majority of the board of the directors or an	1. Exercises significant influence or control over
	Passport number  Personal Identification Number (where applicable)	Indirectly  Indirectly % of voting rights		equivalent governing body of the Tenderer: YesNo 2. Is this right held directly or	the Company body of the Company (tenderer) YesNo	
	Nationality(ies)				indirectly?:	
	Date of birth [dd/mm/yyyy]				Direct	2. Is this influence or control
	Postal address					exercised
	Residential address					directly or indirectly?
	Telephone number				Indirect	Diment
	Email address					Direct
	Occupation or profession					
						Indirect
			<u> </u>			
3.						
			-			
e.t			-			
.c						

- II) Am fully aware that beneficial ownership information above shall be reported to the Public Procurement Regulatory Authority together with other details in relation to contract awards and shall be maintained in the Government Portal, published and made publicly available pursuant to Regulation 13(5) of the Companies (Beneficial Ownership Information) Regulations, 2020.(Notwithstanding this paragraph Personally Identifiable Information in line with the Data Protection Act shall not be published or made public). Note that Personally Identifiable Information (PII) is defined as any information that can be used to distinguish one person from another and can be used to deanonymize previously anonymous data. This information includes National identity card number or Passport number, Personal Identification Number, Date of birth, Residential address, email address and Telephone number.
- III) In determining who meets the threshold of who a beneficial owner is, the Tenderer must consider a natural person who in relation to the company:
  - (a) holds at least ten percent of the issued shares in the company either directly or indirectly;
  - (b) exercises at least ten percent of the voting rights in the company either directly or indirectly;

- (c) holds a right, directly or indirectly, to appoint or remove a director of the company; or
- (d) exercises significant influence or control, directly or indirectly, over the company.
- IV) What is stated to herein above is true to the best of my knowledge, information and belief.

Name of the Tenderer:*[insert complete name of the Tenderer]
Name of the person duly authorized to sign the Tender on behalf of the Tenderer: ** [insert complete name of
person duly authorized to sign the Tender]
Designation of the person signing the Tender: [insert complete title of the person signing the
Tender]
Signature of the person named above: [insert signature of person whose name and capacity are
shown above]
Date this [insert date of signing] day of [Insert month], [insert year]

Bidder Official Stamp