

**CLARIFICATIONS / ADDENDUM SET "2"**

17<sup>th</sup> May, 2022


**KRA/HQS/NCB/068 2021-2022- PROPOSED ESTABLISHMENT OF K9  
BREEDING AND PUPPY PROGRAM IN LOITOKTOK**

Kenya Revenue Authority wishes to inform prospective bidders of the clarifications highlighted below.

No.	CLARIFICATION	CLARIFICATION RESPONSE.
1.	Under Evaluation Criteria is Tender securing declaration form mandatory?	Prospective bidders are hereby advised that the Tender securing declaration form is mandatory and forms part of mandatory evaluation criteria. <b>(Bid security is not required for this tender)</b> <b>Bidders are advised to Duly fill, sign and stamp the Tender securing declaration form which is attached as Annex 1.</b>
2.	On the tender document the BOQ for the renovations to proposed k9 dispensary at Loitokitok border station has a requirement for 16% vat and 10% contingency When you get to the summary of the whole BOQ on page 78 of the tender document you have again requested us to add a 5% contingency and 16 % VAT on the a figure that already has a VAT and contingency	Prospective bidders are hereby advised that the 16% VAT and 10% Contingency requested in page 77 is omitted. Revised BQS for Dispensary is hereby attached <b>as annex 2.</b>
3.	Closing/opening dates: 20/05/2022 at 11:00 am.	New Closing/opening dates: <b>27/05/2022 at 11:00 am</b>

This Clarification form part of the bidding document and is binding to the bidder. All other terms and conditions of the tender remain the same. Prospective bidders are therefore required to immediately acknowledge receipt of this addendum through [eprocurement@kra.go.ke](mailto:eprocurement@kra.go.ke).

Regards,



**Rhodah Nzovila**

**For: Deputy Commissioner - Supply Chain Management**



Annex 1.

**TENDER-SECURING DECLARATION FORM**

*[The Bidder shall complete this Form in accordance with the instructions indicated]*

Date:.....*[insert date (as day, month and year) of Tender Submission]*

Tender No.:.....*[insert number of tendering process]*

To:.....*[insert complete name of Purchaser]* I/We, the undersigned, declare

that:

1. I/We understand that, according to your conditions, bids must be supported by a Tender-Securing Declaration.
2. I/We accept that I/we will automatically be suspended from being eligible for tendering in any contract with the Purchaser for the period of time of *[insert number of months or years]* starting on *[insert date]*, if we are in breach of our obligation(s) under the bid conditions, because we – (a) have withdrawn our tender during the period of tender validity specified by us in the Tendering Data Sheet; or (b) having been notified of the acceptance of our Bid by the Purchaser during the period of bid validity, (i) fail or refuse to execute the Contract, if required, or (ii) fail or refuse to furnish the Performance Security, in accordance with the instructions to tenders.
3. I/We understand that this Tender Securing Declaration shall expire if we are not the successful Tenderer(s), upon the earlier of:
  - a) our receipt of a copy of your notification of the name of the successful Tenderer; or
  - b) thirty days after the expiration of our Tender.
4. I/We understand that if I am/we are/in a Joint Venture, the Tender Securing Declaration must be in the name of the Joint Venture that submits the bid, and the Joint Venture has not been legally constituted at the time of bidding, the Tender Securing Declaration shall be in the names of all future partners as named in the letter of intent.

Signed:.....

Capacity / title (director or partner or sole proprietor, etc.) .....

Name: .....

Duly authorized to sign the bid for and on behalf of: *[insert complete name of Tenderer]*

Dated on ..... day of ..... *[Insert date of signing]* Seal or

stamp







# KENYA REVENUE AUTHORITY

ISO 9001:2015 CERTIFIED

Annex 2.

BILL OF QUANTITIES FOR RENOVATIONS TO PROPOSED K9 DISPENSARY AT LOITOKITOK BORDER STATION					
Item	Description	Unit	Qty	Rate	Amount (ksh)
1.0	<b>Preliminaries:</b>				
	The site visit is mandatory for bidders. The site is located at Loitokitok KRA Border station.				
	The contractor shall comply with all Local authority by-laws and pay charges in connection therewith. The contractor should therefore allow in his tender for expenses.				
	The contractor shall provide all the required equipment and PPEs for approval by the Project Manager.				
	The Contractor shall exercise necessary safety measures so as not to cause any damage to the existing structure and adjoining properties.				
	The contractor shall provide at his own cost and risk all necessary water, electric light and power required for use in the works. The contractor shall pay all charges in connection therewith.				
	The contractor shall be entirely responsible for the security of the works, stores, materials, personnel etc and shall provide all necessary watching, lighting and other precautions as necessary to ensure the security and the protection of the public.				



# KENYA REVENUE AUTHORITY

ISO 9001:2015 CERTIFIED


The contractor shall allow for providing and maintaining hoarding and access gates of 30gauge gci sheets, 2.5m high from the ground level nailed on gum poles/celcured timber as maybe necessary for the protection of the works area to the approval of the Project Manager and Local Authorities. The contractor shall be responsible for pay any charges in respect to hoarding installations during the contract period.

**Total carried to summary**

Item	Description	Unit	Qty	Rate	Amount (ksh)
<b>2.0</b>	<b><u>Demolition</u></b>				
	Carefully hack the floor to remove dilapidated pvc floor tiles, make good affected areas and cart away arising debris	sm	120		
	Carefully remove existing dilapidated doors and cart away debris	No	12		
	Carefully remove existing dilapidated ceiling and cart away arising debris	sm	120		
	Carefully remove existing p.c.c roof tiles and the dilapidated polyethene underlay, clean the tiles and store as directed for re-use. Cart away all the arising debris.	sm	150		
	Carefully remove existing dilapidated under eaves filling and cart away arising debris	sm	10		
	Carefully remove broken glazed panels on casement windows and doors and cart away arisings	sm	5		
	Carefully remove existing broken p.c. paving blocks around the canteen and cart away arising debris	sm	15		
	<b>Total carried to summary</b>				
<b>3.0</b>	<b><u>Wall finishes</u></b>				
	<u>Emulsion paint</u>				
	Prepare the surfaces and apply one undercoat and 2coats silk vinyl paint to existing plastered wall surfaces internally	sm	240		
	Ditto 2coats weatherguard emulsion paint to existing decorative clay grille wall and window cills	sm	15		
	<u>Gloss paint</u>				
	Ditto 2coats bitumastic paint to the plinth externally	sm	46		
	<b>Total carried to summary</b>				
<b>4.0</b>	<b><u>Floor finishes</u></b>				
	<u>Ceramic Tiles</u>				



Tulipe Ushuru Tujitegemee !







# KENYA REVENUE AUTHORITY

ISO 9001:2015 CERTIFIED

Supply and fix 2no. layers of heavy gauge polythene underlay to existing timber roof structure	sm	150		
Allow for fixing back the Double Roman p.c.c roofing tiles to the existing roof structure.	sm	150		
Allow for 10% breakage of Double Roman p.c.c roofing tiles	sm	15		
Ditto 450mm; 1/2round mono-pitch ridge	m	16		
Prepare and apply one undercoat and 2 coats of first grade self priming red oxide roofshield or an equivalent approved by the Project Manager.	sm	150		
Prepare the surfaces of the fascia/barge boards apply one undercoat and 2 coats of gloss paint	m	8.5		
<u>Rainwater goods</u>				
Supply and fix 140mm dia. Half round uPVC rainwater gutter complete with gutter support brackets fixed to the fascia board.	m	31		
140mm E.O gutter for click-fit stop end with running outlet	No	3		
140mm E.O gutter for click-fit gutter joint union	No	3		
110mm down pipe complete with downpipe clips	m	9		
110mm down pipe bend	No	3		
110mm down pipe shoe	No	3		
<u>Eaves Filling</u>				
Allow for under eaves filling in 25x25mm cypress timber battens complete with mosquito wire gauze	sm	15		
Prepare surfaces and apply one undercoat and 2 coats of gloss paint to new timber surfaces.	sm	15		
Ditto to existing under eaves filling timber battens	sm	70		
<b>Total carried to summary</b>				
<u>Fixtures and fittings</u>				
Allow for repairs to existing wardrobes and cabinets, shelving and general fittings in 3 No Rooms. Proposed repairs to be approved by the Project Manager.				
<u>Plumbing installation works</u>				
Allow for cleaning and replacing damaged fittings & accessories to whbs, W'Cs, showers, bath tubs, cisterns and connection to water supply, testing and commissioning.				



*Tulipe Ushuru Tujitegemee !*

KENYA  
VISION 2030



# KENYA REVENUE AUTHORITY

ISO 9001:2015 CERTIFIED

	Supply and lay 330 x 330mm x 2mm non-slip ceramic tiles as SAJ or equal and equivalent. The tile sample to be approved by the Project Manager.	sm	120		
	100x25mm ceramic skirting	m	116		
	<b>Total carried down</b>				
<b>5.0</b>	<b>Doors</b>				
	Supply and fix 50mm mahogany veneered standard solid flush door with lipping including mahogany door frame complete with fanlight				
	Door size 900 x 2100mm	No	10		
	Ditto mahogany panelled door size 900x2100mm complete with 4 fielded and raised panels	No	2		
	Prepare the surfaces and apply 3 coats of polyurethane varnish to panelled doors and door frames. Rate to include staining and preparation of surface by sanding.	sm	8		
	Ditto gloss paint to solid flush doors	sm	40		
	<i>Iron Mongery</i>				
	The following ironmongery as 'Union' or other equal and approved with matching screws				
	100mm pressed brass butt hinges	Pr	12		
	2 lever union lock with brass handles	No	12		
	150x750mm aluminium kick plate	No	24		
	Round aluminium door stopper-DS-R1 AS-floor mounted	No	12		
	<b>Total carried to summary</b>				
<b>6.0</b>	<b>Windows</b>				
	Supply and fix 5mm thick clear sheet glass to existing casement windows with metal putty	sm	5		
	Prepare and apply gloss paint to casement windows	sm	15		
	<b>Total carried to summary</b>				
<b>7.0</b>	<b>Ceiling finishes</b>				
	Supply and fix Washable PVC ceiling white panels complete with support metal stud framing	sm	120		
	25 x 100mm PVC moulded cornice	m	116		
	Allow for 600x600mm ceiling trap door	No	1		
	<b>Total carried to summary</b>				
<b>8.0</b>	<b>Roof finishes</b>				



Tulipe Ushuru Tujitegeme !

KENYA VISION 2030





# KENYA REVENUE AUTHORITY

ISO 9001:2015 CERTIFIED

	Allow for connection to existing water supply, inspection of the existing drainage and waste water system, testing and commissioning.				
	Supply and installation of 5000ltr plastic water storage tank including connection to existing mains supply complete with all fixing accessories & ppr pipework, 3/4" ball valve, 1/2" peglar tap and waterbooster pump(pedrollo PKM60) or an equivalent. The rate to include 2500x2500mm concrete class 20 base slab tankplatform to the approval of the Project Manager.	No	1		
	Allow for inspection, repairs, testing and commissioning of existing Hot water cylinder	No	1		
	<b>Total carried to summary</b>				
<b>11.0</b>	<b>Electrical installation works</b>				
	Provide the P.C sum of kshs 30,000/= for Electrical installation works to the approval of the Project Manager.	Item			
	<b>Total carried to summary</b>				
<b>12.0</b>	<b>External works</b>				
	Prepare and apply Termidor anti-termite treatment or an equivalent around the canteen building as per manufacturer's instruction.	sm	46		
	<u>Paving slabs</u>				
	Supply and lay 600x600x50mm p.c paving slabs on 50mm thick sand bed	sm	17		
	Allow for repairing and jointing the existing p.c paving slabs	sm	10		
	Allow trimming/pruning existing small ground covering plants/flowers, weeding and planting additional to match the existing, watering and tending well till full establishment	sm	50		
	<b>Total carried to summary</b>				
	<b>SUMMARY</b>				
1	Preliminaries				
2	Demolitions				
3	Wall finishes				
4	Floor finishes				
5	Doors				
6	Windows				



*Tulipe Ushuru Tujitegeme!*

KENYA VISION 2030



# KENYA REVENUE AUTHORITY

ISO 9001:2015 CERTIFIED

7	Ceiling finishes				
8	Roof finishes				
9	Plumbing installation works				
10	Electrical installation works				
11	External works				
<b>GRAND TOTAL</b>					

1. **The Summary to the Bills of Quantities** will take this form or some other form but including these items.

SUMMARY				TOTAL PRICE
CONSTRUCTION OF 45 KENNELS				
CONSTRUCTION OF 10 NO MATERNITY KENNELS				
CONSTRUCTION OF BOUNDARY WALL				
RENOVATION OF DISPENSARY				
<b>SUB TOTAL</b>				
Add 5% Contingency				
Add 16% VAT				
<b>GRAND TOTAL (CARRIED FORWARD TO FORM OF TENDER)</b>				